STATE OF NEW HAMPSHIRE

PUBLIC UTILITIES COMMISSION

DG 20-049

Liberty Utilities (EnergyNorth Natural Gas) Corp.

d/b/a Liberty Utilities

Cast Iron Bare Steel Replacement Program

Direct Testimony

of

Randall S. Knepper Director – Safety Division

June 12, 2020

DG 20-049 Exhibit 2

DG 20-049

This page was intentionally left blank

1	Q. Please state your name, occupation and business address.
2	A. My name is Randall S. Knepper. I am employed as the Safety and Security Director of the
3	Safety Division for the New Hampshire Public Utilities Commission. My business address is
4	21 S. Fruit Street, Suite 10, Concord, New Hampshire 03301.
5	Q. Please summarize your education and professional work experience.
6	A. I received a Bachelor of Science in Mechanical Engineering from the University of
7	Rochester and a Master of Science in Civil Engineering from the University of
8	Massachusetts. I am a licensed Professional Engineer in the State of New Hampshire,
9	License No. 9272. For continuing education, I have completed 21 Technical Training
10	Courses and 23 Online Training Sessions provided by the Training and Qualification Center
11	of the Pipeline and Hazardous Materials Safety Administration (PHMSA). See RSK
12	Attachment 1.
13	I have been the Director of Safety for the New Hampshire Public Utilities Commission
14	since December 2004. Prior to that I was an Environmental Consultant and Business
15	Development Manager at The Smart Associates, Environmental Consultants, Inc., located in
16	Concord, New Hampshire. For 16 years I was employed at a local gas distribution company.
17	My previous work experience included a number of Business and Operations roles at
18	Keyspan Energy Delivery New England (Keyspan) and EnergyNorth Natural Gas Inc.
19	(EnergyNorth), including Key Account Executive, Commercial & Industrial Sales Manager,
20	Sales Engineer, Senior Engineer, Staff Engineer, and CAD Supervisor. For many of those
21	years, I designed natural gas distribution systems, recommended capital improvement
22	projects, recommended system expansions, wrote Operations and Maintenance procedures,
23	and oversaw construction projects. While performing the duties of each of these occupations
24	I was responsible for compliance related to applicable local, state, and federal codes. Prior to

3

1		my utility experience I worked at Westinghouse Electric designing high voltage transmission
2		lines as a Project Engineer.
3		In addition, I have served as Staff Engineer for the New Hampshire Site Evaluation
4		Committee prior to its most recent reorganization in 2014 and currently serve as subject
5		matter expert for the New Hampshire Advisory Council on Emergency Preparedness and
6		Security. My professional work experience spans more than 30 years.
7	Q.	Are you affiliated with any professional organizations?
8	A.	Yes. I am a member of the Association of Energy Engineers (AEE). I serve on multiple
9		committees of the National Association of Pipeline Safety Representatives (NAPSR),
10		including prior positions as Chair and Past Chair. I have served as editor of all of the past
11		editions of NAPSR's Compendium of State Pipeline Safely Requirements & Initiatives
12		Providing Increased Public Safety Levels Compared to Code of Federal Regulations. I
13		currently chair the Staff Pipeline Safety Subcommittee of the National Association of
14		Regulatory Commissioners (NARUC); I serve on the Common Ground Alliance Technology
15		Committee; I am appointed as a member of the Gas Technology Institute's Public Interest
16		Advisory Committee; and I am a board member of the New Hampshire Public Works
17		Standards and Training Council. Finally, I have testified before the United States Congress
18		on pipeline safety issues.
19	Q.	What is the purpose of your testimony in this proceeding?
20	A.	My testimony is comprised of the following elements:
21		1) Comments on the final reconciliation of the FY 2020 CIBS program that will terminate
22		with this proceeding in accordance with Commission Order No. 26,266 (June 28, 2019),
23		issued in Docket DG 19-054;

2) Recommendations for future Commission consideration regarding aged and worn pipe
 replacement programs.

3 4	Q. Would you please summarize the process the Safety Division has used to review Liberty's cast iron and bare steel replacement program since its inception?
5	A. A complete detail of the parameters of the CIBS program is included in Attachment J,
6	Section 20 of the Settlement Agreement approved in Order No. 25,370 (May 30, 2012),
7	approved in Docket DG 11-040 concerning the Liberty Utilities acquisition of EnergyNorth
8	Natural Gas from National Grid. A copy of Attachment J, Section 20 is provided as RSK
9	Attachment 2 to my testimony.
10	Safety Division Staff reviewed the Company's written reports of actual cutouts of
11	certain segments of bare steel mains that were replaced in CIBS FY 2020 (April 1, 2019-
12	March 31, 2020) through this program. The CIBS Program requires sample physical cutouts
13	of bare steel mains to be hand-delivered to the Safety Division for examination by its Staff.
14	Staff does not require physical cutouts of cast iron mains. The condition reports prepared by
15	the Company provide the Safety Division with valuable pipeline integrity data, including
16	pipeline wall thickness, pipeline age, soil conditions, system pressure, and location
17	information of bare steel pipe segments related to various types and vintages of removed bare
18	steel segments. These characteristics determine integrity and corrosion assumptions that
19	should be incorporated into distribution integrity management planning. Since the program
20	inception, Staff has continually seen deep pitting, seam cracks, holes, and other undesirable
21	features of the bare steel mains. For CIBS FY 2020, 4 projects required bare steel
22	replacement that necessitated written condition reports; 1 of the 4 bare steel pipe locations
23	included in the report had 100% wall loss (i.e., holes) and 2 of the 4 had wall losses of at

1		least 50%. ¹ This indicates that the pipeline in question had far exceeded acceptable safety
2		requirements and was leaking 24 hours a day, 365 days per year, with ratepayers bearing the
3		expense through the cost of gas adjustment recovery mechanism. The average age of these 4
4		selected bare steel main projects was 72.5 years of service from installation to replacement.
5		Since 2009, 63 ² individual reports have been completed regarding bare steel segments, which
6		is an average of 5.25 per year. The average age of each bare steel segment removed is 83.1
7		years, excluding two reports where Liberty could not determine the age of the segment
8		removed. See RSK Attachment 3 and RSK Attachment 4 for additional details related to the
9		historical CIBS program written bare steel reports.
10		According to its most recent CIBS filing, Liberty has reduced the amount of leak prone pipe
11		from 68.74 miles in FY 2019 to 55.83 miles in FY 2020 ³ . This 12.91 mile decrease includes
12		11.13 miles as a result of the CIBS program (10.55 miles replaced plus 1.56 miles
13		abandoned, less 0.97 miles related to coated steel and plastic mains.) ⁴ . The remainder of the
14		12.91 mile decrease is comprised of 1.78 miles ⁵ related to municipal work and Liberty's cast
15		iron encroachment policy; both are considered beyond the scope of the CIBS program.
16		Included in the 10.55 miles replaced is 3.97 miles of leak prone pipe that was upsized.
17 18	Q.	Compared to the FY 2019 CIBS Program, how does the overall cost per foot of mains replaced compare from year to year?

¹ See Liberty Mostone/Frost (RAM-BRF) Testimony, Attachment at BP 025 to 029.

 $^{^{2}}$ Liberty and its predecessor companies have provided 63 written reports to date. Two of the reports submitted were on coated steel segments in FY2010, thus only 61 were required. In 4 written reports Liberty did not identify the age of pipes; in those cases Staff assumed an age based on installation dates of nearby mains in the vicinity and a review of service documentation.

³ The source of this mileage is Liberty Attachment CAM-1, page 4 of 4, Bates Page 045 (line 13).

⁴ The source is Liberty Attachment RAM-BRF-2 AJ52, Bates Page 030, (Note Liberty states cell R52 is 1.56 abandoned miles but 3 projects were not started so need to exclude .05 miles of potential abandonment. This is derived from 260ft /5280 ft/mile associated with R40 Ledge St and Ramon Avenue in Nashua). Note 11.14 is attained through rounding but 11.13 is used throughout Liberty testimony.

⁵ The source is Liberty RAM-BRF Testimony, Bates Page 009 line 16, and Attachment RAM-BRF-1, Bates Page 023.

1	A. Liberty in FY 2020 incurred costs per mile of mains replaced of \$1.919 million per mile,
2	which is equivalent to \$363/ft. ⁶ Liberty in FY 2019 incurred cost per mile of mains replaced
3	of \$1.687 million per mile which is equivalent to \$319.5/ft. This is a rather large 12%
4	increase in a single year where more main was replaced and typically receives a lower
5	amount of allocated overhead costs. In most cases, the overall cost per foot of main replaced
6	decreases as the quantity replaced increases but this did not occur in FY 2020. Liberty's
7	explanation is comprised of three main factors:
8	1) more segments are located in asbestos contaminated areas of Hudson, which requires
9	expensive construction delays and expenditures;
10	2) increased municipal costs associated with primary arterial streets requiring increased
11	traffic control requirements and restricted hours per day to accomplish work; and
12	3) higher per unit costs of bids received from a new five-year gas contract for construction
13	and replacement services.
14	Liberty testimony in this docket describes Liberty's performance as able to "successfully
15	manage" the CIBS program as a whole despite its FY 2020 variances of actual costs to
16	estimates of 15% for loaded costs and 27% between estimates and actual costs on a direct
17	cost basis. ⁷ Liberty describes the overall 15% variance as "slightly elevated".
18	Of the 39 projects proposed in January 2019, 3 were not initiated. Of the remaining 36
19	projects, 7 were not completed and were extended into the FY 2021 season. These 7
20	projects, which had significantly reduced the scope of the project, prevented the overall
21	variances from being even higher since they were considered negative variances. Nearly half

⁶ Source: Liberty RAM-BRF Testimony stating \$21,369,317 in costs incurred for 11.13 miles replaced. Bates Page 008 line 16. This is equivalent to \$363/ft.
⁷ Liberty RAM-BRF Testimony. Bates Page 011 line 16 -18, 21 and Bates Page 013 Line 18.

1		of the projects, 13 of the 29 completed projects had variances higher than 27%. Beyond
2		those projects listed, another four of the projects had variances that doubled or more than
3		doubled the initial estimate. The highest variance was more than 2.5 times the original
4		estimate where the estimated cost was \$346,298 and the actual loaded cost was \$870,165.
5		All combined, this made FY 2020 the highest per unit cost of replacement projects that
6		Liberty has undertaken and is reflected in the incremental revenue requirement of
7		\$14,885,260.8 If the CIBS base amount provision, carryover cost limitations, upsizing,
8		abandonment, and non bare steel service cost recovery limitations were not included,
9		Liberty's revenue requirement would have been \$21,369,387.9
10	Q.	Are there any other notable events included in Liberty's FY 2020 reconciliation?
11	A.	Yes, for the first time a Keene cast iron replacement project was included in the CIBS
12		program. A single project in Keene on Marlboro Street and Martin Street consisting of 4,710
13		feet and costing \$776,178 was included. While there was a single footnote in last year's
14		CIBS FY 2019 attachment that revenues of Keene were being combined with the remainder
15		of Liberty's revenues, there was no project included as a replacement project in CIBS FY
16		2019. In CIBS FY 2020 CAM-1 Attachment BP 045 includes the same footnote but Liberty
17		did include the project mentioned above. The original January 2019 proposed project list
18		submitted to Staff by Liberty did not contain a Keene project, but the May 2019 project list
19		submitted to Staff did contain the Marlboro Street project in Keene. The Safety Division did
20		not notice the project because it was listed in the Company's Southern Division, where in
21		most other Company filings the Keene Division is separated and is not included as part of the
22		Southern Division. Staff noted that the corresponding amount of cast iron remaining in

⁸ Liberty RAM-BRF Testimony, Bates Pages 019, 020.
⁹ Liberty RAM-BRF Testimony, Bates Page 008 line 16, Bates Page 020, and 021.

1	Keene does not appear to be reflected in associated line 13 of CAM-1 attachment in FY 2020
2	or FY 2019. Staff once again believes Liberty should prepare a comprehensive business plan
3	for Keene prior to undertaking large projects in its Keene territory so that Staff can be better
4	informed if the upsized project comports with the overall plan for Keene, including whether
5	the low pressure system will remain and how the conversion plans to CNG will be
6	implemented. Since the CIBS accelerated recovery program will terminate with this
7	proceeding, the approximately 6.75 miles ¹⁰ of cast iron in Keene will not have to be updated
8	or included in a filing with the Commission going forward.
9	
10	Liberty abandoned 13 bare steel services and replaced 230 bare steel services with
11	polyethylene. 247 existing services that were coated steel or polyethylene were tied over
12	from the retired leak-prone main to the newly installed polyethylene mains. 20 new services
13	were installed to customers along that main that were previously not customers of Liberty.
14	The 20 new services was the highest amount Liberty has achieved during the course of the
15	CIBS program.
16	
17 18	Q. Does Liberty still commit to replacing the remaining bare steel and cast iron by 2024 as previous testimonies in prior CIBS proceedings had projected.
19	A. No, Liberty's FY 2020 testimony does not mention any future replacement timelines. RSK
20	Attachment 5 includes a Company discovery response that indicates that 2024 is no longer
21	Liberty's goal for completion of all CIBS pipe replacement in its service territories. Given
22	the 55 miles of existing systems and the inclusion of the 6.75 miles of cast iron within the

¹⁰ Liberty PHMSA 7100.1 reports, filed annually with Safety Division, reflect 6.756 miles of cast iron remain in Keene as of December 31, 2019.

1		Keene system into Liberty's replacement program, coupled with other significant projects
2		that Liberty is planning, it is doubtful that the Company will complete all replacements by
3		2024, as it had originally said it would do. Absent a Commission mandate to have leak prone
4		pipe removed by a certain date, Liberty can prolong the replacement rate.
5 6	Q.	Does Staff recommend an end date for replacement work be established as part of this final CIBS proceeding?
7		Yes, Staff recommends that the Commission require Liberty to set a targeted goal to remove
8		and replace all remaining cast iron and bare steel mains from its distribution system by the
9		end of calendar year 2025, with the exception of mains equal to or greater than a 10 inch
10		nominal diameter and mains associated with the Keene system. Downstream bare steel
11		services attached to such remaining mains should also be targeted. Liberty should notify
12		Commission Staff when the final main is removed.
13 14 15 16	Q.	With the termination of the CIBS program, is Liberty required to annually file detailed cost estimates and descriptions of the remaining replacement work with a quantification of services replaced? Does the information provide valuable data for tracking metrics?
17	A.	No, with the termination of the CIBS program, Liberty is no longer required to file such
18		reports or provide physical samples of replaced bare steel mains. Nor is a hearing on the
19		status of the program for cost recovery required. However, that data would provide a full
20		accounting on a segment by segment basis of the many construction replacement projects
21		that Liberty is undertaking and would allow the Safety Division to compare replacement
22		project records against leak reports, odorization reports and capital expenditures. It would
23		also give an indication of where crews will be located for planning Safety Division
24		inspection work and the type of Liberty work to be accomplished at any given time.
25	Q.	What options are available for the Commission to implement such a requirement?
26	A.	There are 3 potential options:

1	1) The Commission can include within this docket a provision that orders Liberty to provide
2	the same records and materials that it has been providing for the past 12 years, similar to
3	page 16 of Attachment RAM/BRF BP030 for replacement work and Attachment CAM-1 BP
4	047-050 for impacts.
5	
6	2) The Commission can require that Liberty provide sufficient detail each May in its E-22
7	report of capital expenditures, as required by Puc 509.11. RSK Attachments 6A, 6B and 7
8	provide samples of the detail of replacement work capitalized in Liberty's budgeting (6A), of
9	what Liberty provided on the E-22 for FY 2021, filed in May of 2020 (6B), and what it
10	provided with a data response that provides much more detail (7).
11	
12	3) The Commission can also require enhanced details to be provided on daily crew reports
13	that indicate work order number, system pressure, replacement project description and
14	length, and clearer description of the work activities to be accomplished. Daily crew reports
15	are required as part of Commission Order No. 25,370 in Docket DG 11-040 as part of
16	Settlement Attachment J, item 14 but lacks details regarding what types of information
17	should be included in the daily crew report. RSK Attachment 8 is a sample of a Liberty daily
18	crew report. The Commission has the authority to require Options 1, 2, and 3, or any
19	combination of those.
20	Q. Which options are recommended by Staff?
21	A. Staff believes information on the E-22 that is supplemented with details as shown in RSK
22	Attachment 7 would be sufficient for the replacement work. Combined with Option 3, that
23	approach would allow future tracking of significant expenditures and would allow for limited
24	inspection comments for future audits and improved rate case reviews. Staff would propose

11

1	similar changes to the E-22 form in a future Puc 500 rulemaking and this remedy would be
2	sufficient in the interim.
3	Q. What are the results of Staff's Audit?
4	RSK Attachment 9 is the Commission Staff audit of Liberty's CIBS FY 2020 program
5	conducted by Anthony Leone, a Utility Analyst in the Gas Division. In summary, the
6	Analyst reviewed work orders, supporting documents, invoices, journal entries, Excel
7	spreadsheets of the FY 2020 CIBS Program, and any other necessary supporting
8	documentation that would substantiate the information presented in the Company's filings.
9 10 11	Q. Did Liberty produce a report regarding the number of Conversions of Non Gas Customers?
12	No, Commission Order No. 25,370 did not require Liberty to provide any statistics regarding
13	Liberty customer additions for mains associated with the CIBS program as had been required
14	in previous Commission Orders. Liberty did state that 20 customers were added for FY
15	2020, compared to 16 in FY 2019 and 6 in FY 2018. It did not indicate that there were any
16	changes to its marketing program, or that Liberty would continue marketing efforts going
17	forward, given the Company's testimony in prior CIBS dockets that it does not believe
18	marketing to be a fruitful exercise to encourage customer service additions.
19	Q. Does this conclude your testimony?

20 A. Yes

RSK Attachment 1 Liberty Utilities CIBS FY 2020 (April 1, 2019 - March 31, 2020) DG 20-049 June 12, 2020

	Knepper Applicable PHMSA Training Completed		
	Online Computer Based Training	Status	Date
1	PHMSA-PL1DIMP Introduction of Distribution Integrity Management Program WBT	Successful	5/3/2011
2	PHMSA-PL1GLAW Introduction to Gas Laws WBT	Successful	8/11/2014
3	PHMSA-PL1HCA High Consequence Areas WBT	Successful	7/4/2005
4	PHMSA-PL1ICDA Internal Corrosion Direct Assessment WBT	Successful	4/1/2011
5	PHMSA-PL1IPROC Integrity Management Processes WBT	Successful	7/6/2005
6	PHMSA-PL10DOR Natural Gas Odorization WBT	Successful	4/4/2011
7	PHMSA-PL1PRESS Fundamentals of Gas Pressure Regulators WBT	Successful	2/26/2007
8	PHMSA-PL1RA Introduction to Risk Assessment Methods WBT	Successful	4/25/2015
9	PHMSA-PL2FLMEC - Fundamentals of Fluid Mechanics WBT	Successful	4/24/2015
10	PHMSA-PL2P195 Introduction to Part 195 WBT	Successful	4/14/2015
11	PHMSA-PL3CP Fundamentals of Pipeline Corrosion and Cathodic Protection WBT	Successful	8/14/2007
12	PHMSA-PL3ECDA External Corrosion Direct Assessment WBT	Successful	4/1/2011
13	PHMSA-PL3ELEC Fundamentals of Basic DC Electricity WBT	Successful	8/18/2007
14	PHMSA-PL3OQ Operator Qualification WBT Course	Successful	1/31/2006
15	PHMSA-PL3PIG Fundamentals of Launching and Receiving Maintenance Pigs WBT	Successful	6/8/2010
16	PHMSA-PL3PP Fundamentals of Plastic Pipe WBT	Successful	4/12/2007
17	PHMSA-PL3REG Regulatory Overview WBT	Successful	4/8/2015
18	PHMSA-PL3SCADA Fundamentals of SCADA Systems WBT	Successful	3/14/2011
19	PHMSA-PL3SCCDA Stress Corrosion Cracking Direct Assessment WBT	Successful	8/23/2006
20	PHMSA-PL3WELD Introduction to Pipeline Welding WBT	Successful	6/1/2007
21	PHMSA-PL4LNG Fundamentals of Liquefied Natural Gas (LNG) WBT	Successful	6/15/2005
21	PHMSA-PL3IC - Investigating and Managing Internal Corrosion of Pipelines WBT	Successful	10/6/2016
22	PHMSA-PL3DA Drug and Alcohol Testing for the Pipeline Industry WBT	Successful	10/8/2016
	COURSES	Status	Date
1	PHMSA-PL1297 Gas Integrity Management (IM) Protocol Course	Successful	5/5/2005
2	PHMSA-PL4253 Liquefied Natural Gas (LNG) Safety Technology and Inspection Course	Successful	7/29/2005
3	PHMSA-PL1250 Safety Evaluation of Gas Pipeline Systems Course		
4		Successful	12/15/2005
	PHMSA-PL2284 (HAZWOPER) Refresher for Pipeline Safety Representatives	Successful	1/9/2007
5	PHMSA-PL3322 Evaluation of Operator Qualification (OQ) Programs Course	Successful Successful	1/9/2007 1/21/2016
5 6	PHMSA-PL3322 Evaluation of Operator Qualification (OQ) Programs Course PHMSA-PL3256 Pipeline Failure Investigation Techniques Course	Successful Successful Successful	1/9/2007 1/21/2016 2/9/2007
5 6 7	PHMSA-PL3322 Evaluation of Operator Qualification (OQ) Programs Course PHMSA-PL3256 Pipeline Failure Investigation Techniques Course PHMSA-PL1255 Gas Pressure Regulation and Overpressure Protection Course	Successful Successful Successful Successful	1/9/2007 1/21/2016 2/9/2007 4/12/2007
5 6 7 8	PHMSA-PL3322 Evaluation of Operator Qualification (OQ) Programs Course PHMSA-PL3256 Pipeline Failure Investigation Techniques Course PHMSA-PL1255 Gas Pressure Regulation and Overpressure Protection Course PHMSA-PL1310 Plastic and Composite Materials Course	Successful Successful Successful Successful Successful	1/9/2007 1/21/2016 2/9/2007 4/12/2007 6/15/2007
5 6 7 8 9	PHMSA-PL3322 Evaluation of Operator Qualification (OQ) Programs Course PHMSA-PL3256 Pipeline Failure Investigation Techniques Course PHMSA-PL1255 Gas Pressure Regulation and Overpressure Protection Course PHMSA-PL1310 Plastic and Composite Materials Course PHMSA-PL3242 Welding and Welding Inspection of Pipeline Materials Course	Successful Successful Successful Successful Successful Successful	1/9/2007 1/21/2016 2/9/2007 4/12/2007 6/15/2007 6/15/2007
5 6 7 8 9 10	 PHMSA-PL3322 Evaluation of Operator Qualification (OQ) Programs Course PHMSA-PL3256 Pipeline Failure Investigation Techniques Course PHMSA-PL1255 Gas Pressure Regulation and Overpressure Protection Course PHMSA-PL1310 Plastic and Composite Materials Course PHMSA-PL3242 Welding and Welding Inspection of Pipeline Materials Course PHMSA-PL3254 Joining of Pipeline Materials Course 	Successful Successful Successful Successful Successful Successful	1/9/2007 1/21/2016 2/9/2007 4/12/2007 6/15/2007 6/15/2007 6/15/2007
5 6 7 8 9 10 11	 PHMSA-PL3322 Evaluation of Operator Qualification (OQ) Programs Course PHMSA-PL3256 Pipeline Failure Investigation Techniques Course PHMSA-PL1255 Gas Pressure Regulation and Overpressure Protection Course PHMSA-PL1310 Plastic and Composite Materials Course PHMSA-PL3242 Welding and Welding Inspection of Pipeline Materials Course PHMSA-PL3254 Joining of Pipeline Materials Course PHMSA-PL3257 Pipeline Safety Regulation Application and Compliance Procedures Course 	Successful Successful Successful Successful Successful Successful Successful	1/9/2007 1/21/2016 2/9/2007 4/12/2007 6/15/2007 6/15/2007 8/17/2007
5 6 7 8 9 10 11 12	 PHMSA-PL3322 Evaluation of Operator Qualification (OQ) Programs Course PHMSA-PL3256 Pipeline Failure Investigation Techniques Course PHMSA-PL1255 Gas Pressure Regulation and Overpressure Protection Course PHMSA-PL1310 Plastic and Composite Materials Course PHMSA-PL3242 Welding and Welding Inspection of Pipeline Materials Course PHMSA-PL3254 Joining of Pipeline Materials Course PHMSA-PL3257 Pipeline Safety Regulation Application and Compliance Procedures Course PHMSA-PL3600 Root Cause/Incident Investigation Course 	Successful Successful Successful Successful Successful Successful Successful Successful	1/9/2007 1/21/2016 2/9/2007 4/12/2007 6/15/2007 6/15/2007 8/17/2007 8/17/2007
5 6 7 8 9 10 11 12 13	 PHMSA-PL3322 Evaluation of Operator Qualification (OQ) Programs Course PHMSA-PL3256 Pipeline Failure Investigation Techniques Course PHMSA-PL1255 Gas Pressure Regulation and Overpressure Protection Course PHMSA-PL1310 Plastic and Composite Materials Course PHMSA-PL3242 Welding and Welding Inspection of Pipeline Materials Course PHMSA-PL3254 Joining of Pipeline Materials Course PHMSA-PL3257 Pipeline Safety Regulation Application and Compliance Procedures Course PHMSA-PL3600 Root Cause/Incident Investigation Course PHMSA-PL3292 Safety Evaluation of Inline Inspection (ILI)/Pigging Programs Course 	Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful	1/9/2007 1/21/2016 2/9/2007 4/12/2007 6/15/2007 6/15/2007 6/15/2007 8/17/2007 8/21/2009 6/11/2010
5 6 7 8 9 10 11 12 13 14	 PHMSA-PL3322 Evaluation of Operator Qualification (OQ) Programs Course PHMSA-PL3256 Pipeline Failure Investigation Techniques Course PHMSA-PL1255 Gas Pressure Regulation and Overpressure Protection Course PHMSA-PL1310 Plastic and Composite Materials Course PHMSA-PL3242 Welding and Welding Inspection of Pipeline Materials Course PHMSA-PL3254 Joining of Pipeline Materials Course PHMSA-PL3257 Pipeline Safety Regulation Application and Compliance Procedures Course PHMSA-PL3292 Safety Evaluation of Inline Inspection (ILI)/Pigging Programs Course PHMSA-PL3293 Corrosion Control of Pipeline Systems Course 	Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful	1/9/2007 1/21/2016 2/9/2007 4/12/2007 6/15/2007 6/15/2007 8/17/2007 8/21/2009 6/11/2010 6/25/2010
5 6 7 8 9 10 11 12 13 14 15	 PHMSA-PL3322 Evaluation of Operator Qualification (OQ) Programs Course PHMSA-PL3256 Pipeline Failure Investigation Techniques Course PHMSA-PL1255 Gas Pressure Regulation and Overpressure Protection Course PHMSA-PL1310 Plastic and Composite Materials Course PHMSA-PL3242 Welding and Welding Inspection of Pipeline Materials Course PHMSA-PL3254 Joining of Pipeline Materials Course PHMSA-PL3257 Pipeline Safety Regulation Application and Compliance Procedures Course PHMSA-PL3200 Root Cause/Incident Investigation Course PHMSA-PL3292 Safety Evaluation of Inline Inspection (ILI)/Pigging Programs Course PHMSA-PL3293 Corrosion Control of Pipeline Systems Course PHMSA-PL3291 Fundamentals of (SCADA) System Technology and Operation Course 	Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful	1/9/2007 1/21/2016 2/9/2007 4/12/2007 6/15/2007 6/15/2007 8/17/2007 8/21/2009 6/11/2010 6/25/2010 4/1/2011
5 6 7 8 9 10 11 12 13 14 15 16	 PHMSA-PL3322 Evaluation of Operator Qualification (OQ) Programs Course PHMSA-PL3256 Pipeline Failure Investigation Techniques Course PHMSA-PL1255 Gas Pressure Regulation and Overpressure Protection Course PHMSA-PL1310 Plastic and Composite Materials Course PHMSA-PL3242 Welding and Welding Inspection of Pipeline Materials Course PHMSA-PL3254 Joining of Pipeline Materials Course PHMSA-PL3257 Pipeline Safety Regulation Application and Compliance Procedures Course PHMSA-PL3292 Safety Evaluation of Inline Inspection (ILI)/Pigging Programs Course PHMSA-PL3293 Corrosion Control of Pipeline Systems Course PHMSA-PL3291 Fundamentals of (SCADA) System Technology and Operation Course PHMSA-PL3355 Safety Evaluation of Control Room Management Programs 	Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful	1/9/2007 1/21/2016 2/9/2007 4/12/2007 6/15/2007 6/15/2007 8/17/2007 8/21/2009 6/11/2010 6/25/2010 4/1/2011 8/29/2014
5 6 7 8 9 10 11 12 13 14 15 16 17	 PHMSA-PL3322 Evaluation of Operator Qualification (OQ) Programs Course PHMSA-PL3256 Pipeline Failure Investigation Techniques Course PHMSA-PL1255 Gas Pressure Regulation and Overpressure Protection Course PHMSA-PL1310 Plastic and Composite Materials Course PHMSA-PL3242 Welding and Welding Inspection of Pipeline Materials Course PHMSA-PL3254 Joining of Pipeline Materials Course PHMSA-PL3257 Pipeline Safety Regulation Application and Compliance Procedures Course PHMSA-PL3200 Root Cause/Incident Investigation Course PHMSA-PL3292 Safety Evaluation of Inline Inspection (ILI)/Pigging Programs Course PHMSA-PL3291 Fundamentals of (SCADA) System Technology and Operation Course PHMSA-PL3355 Safety Evaluation of Control Room Management Programs PHMSA-PL1245 Safety Evaluation of Distribution Integrity Management Programs (DIMP) Course 	Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful	1/9/2007 1/21/2016 2/9/2007 4/12/2007 6/15/2007 6/15/2007 8/17/2007 8/21/2009 6/11/2010 6/25/2010 4/1/2011 8/29/2014 4/23/2015
5 6 7 8 9 10 11 12 13 14 15 16 17 18	 PHMSA-PL3322 Evaluation of Operator Qualification (OQ) Programs Course PHMSA-PL3256 Pipeline Failure Investigation Techniques Course PHMSA-PL1255 Gas Pressure Regulation and Overpressure Protection Course PHMSA-PL1310 Plastic and Composite Materials Course PHMSA-PL3242 Welding and Welding Inspection of Pipeline Materials Course PHMSA-PL3254 Joining of Pipeline Materials Course PHMSA-PL3257 Pipeline Safety Regulation Application and Compliance Procedures Course PHMSA-PL3292 Safety Evaluation of Inline Inspection (ILI)/Pigging Programs Course PHMSA-PL3293 Corrosion Control of Pipeline Systems Course PHMSA-PL3291 Fundamentals of (SCADA) System Technology and Operation Course PHMSA-PL3255 Safety Evaluation of Distribution Integrity Management Programs (DIMP) Course PHMSA-PL2258 Safety Evaluation of Hazardous Liquid Pipeline Systems Course 	Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful	1/9/2007 1/21/2016 2/9/2007 4/12/2007 6/15/2007 6/15/2007 8/17/2007 8/21/2009 6/11/2010 6/25/2010 4/1/2011 8/29/2014 4/23/2015 5/15/2015
5 6 7 8 9 10 11 12 13 14 15 16 17 18 19	 PHMSA-PL3322 Evaluation of Operator Qualification (OQ) Programs Course PHMSA-PL3256 Pipeline Failure Investigation Techniques Course PHMSA-PL1255 Gas Pressure Regulation and Overpressure Protection Course PHMSA-PL1310 Plastic and Composite Materials Course PHMSA-PL3242 Welding and Welding Inspection of Pipeline Materials Course PHMSA-PL3254 Joining of Pipeline Materials Course PHMSA-PL3257 Pipeline Safety Regulation Application and Compliance Procedures Course PHMSA-PL3292 Safety Evaluation of Inline Inspection (ILI)/Pigging Programs Course PHMSA-PL3293 Corrosion Control of Pipeline Systems Course PHMSA-PL3291 Fundamentals of (SCADA) System Technology and Operation Course PHMSA-PL355 Safety Evaluation of Distribution Integrity Management Programs (DIMP) Course PHMSA-PL3267 Fundamentals of Integrity Management Course 	Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful	1/9/2007 1/21/2016 2/9/2007 6/15/2007 6/15/2007 6/15/2007 8/17/2007 8/21/2009 6/11/2010 6/25/2010 4/1/2011 8/29/2014 4/23/2015 5/15/2015 7/31/2015
5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20	 PHMSA-PL3322 Evaluation of Operator Qualification (OQ) Programs Course PHMSA-PL3256 Pipeline Failure Investigation Techniques Course PHMSA-PL1255 Gas Pressure Regulation and Overpressure Protection Course PHMSA-PL1310 Plastic and Composite Materials Course PHMSA-PL3242 Welding and Welding Inspection of Pipeline Materials Course PHMSA-PL3257 Pipeline Safety Regulation Application and Compliance Procedures Course PHMSA-PL3257 Pipeline Safety Regulation Application and Compliance Procedures Course PHMSA-PL3292 Safety Evaluation of Inline Inspection (ILI)/Pigging Programs Course PHMSA-PL3293 Corrosion Control of Pipeline Systems Course PHMSA-PL3291 Fundamentals of (SCADA) System Technology and Operation Course PHMSA-PL3258 Safety Evaluation of Distribution Integrity Management Programs (DIMP) Course PHMSA-PL3267 Fundamentals of Integrity Management Course PHMSA-PL3266 External Corrosion Direct Assessment (ECDA) Field Course 	Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful	1/9/2007 1/21/2016 2/9/2007 4/12/2007 6/15/2007 6/15/2007 8/17/2007 8/21/2009 6/11/2010 6/25/2010 4/1/2011 8/29/2014 4/23/2015 5/15/2015 7/31/2015 8/14/2015
5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21	 PHMSA-PL3322 Evaluation of Operator Qualification (OQ) Programs Course PHMSA-PL3256 Pipeline Failure Investigation Techniques Course PHMSA-PL1255 Gas Pressure Regulation and Overpressure Protection Course PHMSA-PL1310 Plastic and Composite Materials Course PHMSA-PL3242 Welding and Welding Inspection of Pipeline Materials Course PHMSA-PL3254 Joining of Pipeline Materials Course PHMSA-PL3257 Pipeline Safety Regulation Application and Compliance Procedures Course PHMSA-PL3292 Safety Evaluation of Inline Inspection (ILI)/Pigging Programs Course PHMSA-PL3293 Corrosion Control of Pipeline Systems Course PHMSA-PL3291 Fundamentals of (SCADA) System Technology and Operation Course PHMSA-PL355 Safety Evaluation of Distribution Integrity Management Programs (DIMP) Course PHMSA-PL3267 Fundamentals of Integrity Management Course 	Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful Successful	1/9/2007 1/21/2016 2/9/2007 4/12/2007 6/15/2007 6/15/2007 8/17/2007 8/21/2009 6/11/2010 6/25/2010 4/1/2011

DG 20-049 Exhibit 2 RSK Attachment 2 DG 20-049 Liberty CIBS Program June 12, 2020 Page 1 of 6

(20) <u>Cast Iron Bare Steel Replacement Program:</u>

A cast iron/bare steel replacement program ("CIBS Program") shall be implemented that will be based on a construction year (April through December). By no later than January 15 of each year, EnergyNorth shall provide a copy of its CIBS Plan, defined below, to Staff for review and comment. EnergyNorth shall meet with Staff in technical sessions to discuss the plan to be implemented for the subsequent construction year. After review by Staff, EnergyNorth will take all reasonable steps to carry out and implement the plan, taking into account Staff comments.

The CIBS plan, which will cover cast iron and bare steel pipe replacements, will describe each replacement project, itemizing the proposed projects by general category, along with the targeted amount of investment to be made during the following construction year, which budget shall not be less than the CIBS base amount for capital expenditures described in paragraph e below ("CIBS Plan"). The CIBS Plan will prioritize cast iron and bare steel pipe replacements based on factors including leakage, material condition, age and other components affecting pipe integrity. The CIBS Plan will not address replacement of cast iron and bare steel pipes required in public works projects and/or carried out pursuant to the Cast Iron Encroachment Policy referenced in Condition 12 above.

EnergyNorth agrees to engage in an annual evaluation and selection process to identify and target investments to be proposed in the CIBS Plan, as follows:

a. It will undertake an annual review of the performance of its distribution system as it relates to the integrity of its cast iron and bare steel pipelines. This review will provide: (1) a detailed analysis of leak activity over the preceding ten years on the bare steel and cast iron gas mains, and (2) an evaluation of which main segments represent the highest priority segments for replacement. Consideration will be given to the age of the main, the date the leak(s) occurred, leak classification, type of leak, number of clamps used in leak repair, condition of main when repaired, specific leak location, building types in the area of the main segment and quantity of bare steel services attached to the potential segment to be replaced.

b. Adjustments in the priority of main segment replacement could be made due to planned paving projects, public relations, or identification of new main segments by operating personnel in the field that were not captured through EnergyNorth's data systems.

c. Using the process identified in (a) and (b) above, EnergyNorth shall rank and prioritize those mains to be replaced in the associated construction year and provide its plans to the Commission.

d. Categories of spending will include the following:

- 1.1 unprotected bare steel main replacement, as determined by the evaluation and selection process;
- 1.2. cast iron main replacement as determined by the evaluation and selection process;
- 1.3. cast iron or bare steel main replacement candidates requested by field operating personnel; and
- 1.4. bare steel services replaced as a result of a segment of bare steel main or cast iron main that is selected.

Categories of spending that are <u>not</u> included in the CIBS:

- 2.1. costs of moving inside meters to outside;
- 2.2. costs of reconnecting existing plastic services or existing coated steel services from cast iron mains or bare steel mains to the newly installed replacement main;
- 2.3. costs of any mains replaced made of polyethelene or steel that have a protective coating;
- 2.4. costs of any mains that are abandoned;
- 2.5. costs of coated steel mains that "act as bare steel mains" such as poorly coated steel mains or disbonded steel mains, unless approved by the Safety Division;
- 2.6. incremental costs of upsizing with the exception of (n) below; and
- 2.7 carryover costs in aggregate exceeding 5% of the approved estimated total expenditures under the CIBS program for the construction year, unless approved by the Safety Division. Such carryover costs include items such as restoration costs not incurred during the construction year.
- 2.8 Replacements made under the Cast Iron Encroachment Policy are not eligible for accelerated rate recovery in the Cast Iron/Bare Steel Program unless a special circumstance is approved by the Safety Division.

e) EnergyNorth shall bear the initial \$500,000 of capital expenditures under the CIBS program ("the CIBS Base Amount") (in accordance with the Handy Whitman index). The CIBS Base Amount excludes replacement projects required by public works projects and/or carried out pursuant to the Cast Iron Encroachment Policy referenced in Condition 12. Provided that investments were made in accordance with the approved CIBS plan, EnergyNorth will be allowed a permanent increase in its base distribution delivery rates to recover the annual revenue requirement for those investments that are found to be reasonable and prudent made in the preceding construction year and in excess of the CIBS Base Amount. The permanent capital investment recovery allowance will not take effect until the actual costs of the

previous construction year are approved by the Commission. Petitions for cost recovery will be submitted annually thereafter not later than May 1, for an effective date of July 1.

f) After Staff completes the review of the CIBS Plan for a given construction year, EnergyNorth shall track all capital investments made in accordance with the approved CIBS Plan. EnergyNorth will reconcile actual capital expenditures with the CIBS Plan targets at the conclusion of the CIBS Plan period.

g) EnergyNorth agrees that it will file a report with the Commission on May 15 of each year detailing the actual amount of capital investments made in accordance with implementing the CIBS Plan during the prior construction year ("CIBS Report"). The report will include a calculation of the incremental revenue requirement associated with the capital investments in rate base that exceeds the CIBS Base Amount, using the Commission-approved imputed or actual capital structure and cost of capital determined using the Commission-approved return on equity and cost of debt. If the Commission has not made a final determination in the first rate case by the time the first adjustment is to be calculated, a reasonable proxy will be used for the rate calculation and an adjustment will be made to the revenue requirement to reconcile to the approved cost of capital rates when the rates from the first rate case go into effect.

h) EnergyNorth agrees to file its annual CIBS Report on the prior construction year's activities at the time it makes its rate adjustment filing on May 15. The Settling Parties and Staff understand that, in implementing the CIBS Plan, the circumstances encountered during the year may require reasonable deviations from the original plan. In such cases, EnergyNorth shall include an explanation of any deviations in the report. For cost recovery purposes, EnergyNorth shall have the burden to show that any deviations were due to circumstances out of its reasonable control or, if within its control, were reasonable and prudent. The CIBS Report shall include a breakdown of footage replaced by municipal projects that involve Cast Iron /Bare Steel as well the footage replaced under the Cast Iron Encroachment Policy. Samples of reporting that Staff has reviewed previously are included in Attachment A.

i) The CIBS Program will remain in place through and beyond EnergyNorth's future rate cases until terminated by the Commission or by mutual agreement at the end of a given construction year, with a final capital allowance pertaining to the final year.

j) EnergyNorth can elect to not finalize its CIBS Plan until after the winter frost patrol ends in early April. By May 1, EnergyNorth shall finalize actual projects and provide a copy of the final CIBS Plan to Staff. In addition, the priority rankings of main segments for replacement will be subject to change over the course of the year due to new information. In such case, if EnergyNorth believes it is prudent to change the rankings from the approved CIBS Plan, it will notify Staff, stating the reasons for the change prior to construction. If Staff does not believe that particular components of the revised plans are reasonable and the matter is not resolved between EnergyNorth and Staff, Staff may object and the matter may be referred to the Commission for resolution.

k) EnergyNorth acknowledges that Staff review will not relieve EnergyNorth of its obligation to operate its business and maintain safe, reliable service through expenditures and other capital investments in the ordinary course of business that are not set forth in the CIBS Plan, nor will it bind Staff to a particular position regarding the adequacy and/or effectiveness of the plan.

1) However, EnergyNorth will be authorized to include in its CIBS Plan the replacement of cast iron and bare steel pipe located in the vicinity of public works projects, where replacement is not required as a part of the project, but permitted for convenience or other reasons, as determined by the Safety Division.

m) EnergyNorth shall provide GIS Mapping or other electronic means that shows the project scope with each submittal of the CIBS Plan.

n) No upsizing of pipe diameter shall be allowed for cost recovery within the CIBS Program on 60 psig systems. For low pressure systems (12 inches water column and below) no upsizing shall be allowed for cost recovery within the CIBS Program except for 3" nominal diameter low pressure pipe replaced with 4" nominal diameter pipe and other special circumstances as approved by the Safety Division.

o) EnergyNorth shall provide the Commission Staff with actual cutouts of the worst section within any bare steel main segment replaced prior to reconciling any cost adjustments for associated construction season. Cutouts shall be approximately 12 inches to 24 inches in length.

p) EnergyNorth shall provide a written report accompanying the actual cutouts in section 20(o) above that includes: photographs the replaced bare steel segment; a general description of the condition of the pipe; the street address from which it was taken; age of material; original wall thickness; measured depth of deepest pit of the cutout; operating pressure of replaced pipe; pH of soil condition of cutout surrounds; results of testing for microbiological acid producing bacteria (APB) and sulfate reducing bacteria (colonies per ML); and identification of the threshold of high bacteria counts.

II. Additional Granite State Electrical Safety Conditions (Electrical Underground Facility Protection)

Underground Damage Prevention Program Enhancement

 Granite State Electric Company (Granite State) will institute a new Locating/Mark-Out Policy within the existing Underground Damage Prevention Program. The Locating/Mark-Out Policy will provide enhanced public safety by increasing the commitments and responsibilities associated with locating and marking private underground residential facilities within Granite State's franchise territory. Notwithstanding the exemption contained in RSA 374:53 concerning facilities not owned by the operator, Granite State accepts the additional responsibility of locating privately owned, residential underground electrical facilities pursuant to excavation notifications, and agrees to establish the Locating/Mark-Out Policy ("Policy") described below.

Policy Implementation and Potential Discontinuation

- 2. Locating/Mark-Out Policy will be implemented within 120 days of the Closing Date.
- 3. Granite State reserves the right to discontinue the Policy with Staff review and consent but without the necessity of obtaining formal Commission approval if the incremental costs of implementing the Policy, not including advertising and marketing costs or other non-field costs, exceed \$10,000 annually. In the event Granite State disagrees with Staff's decision not to consent, it may file a request for review with the Commission. Granite State will file written notification of any discontinuation of the Policy with the Commission.

Policy Requirements

- 4. Within Granite State's franchise territory, Granite State will mark privately owned, residential underground facilities up to the meter and including the service entrance upon receipt of notifications received via the One Call Notification System.
- 5. The electrical service includes primary service voltage levels as well as secondary voltage levels.
- 6. The electrical service also includes service from aerial distribution systems as well as underground systems.
- 7. Notifications received for underground excavation involving commercial properties are not included in the waiver or this Policy.
- 8. The location and marking of excavations involving underground electrical facilities beyond the meter, such as from a house to a barn, lamp post, pool, shed and other structures, are not included in this Policy.

- 9. Granite State's responsibility under the Policy shall not extend beyond marking out the facility, and does not include repairs to such facilities.
- 10. Field Markouts made under the Policy shall clearly indicate private electrical facilities that are not owned or operated by GSE.
- 11. During each year the Policy is in effect, Granite State shall maintain a level of accuracy for markouts made under the Policy that is commensurate with the level achieved for its own facilities. An audit or equivalent method may be used to determine the accuracy percentage of Policy markouts.
- 12. Granite State will not be required to mark such services defined in this Policy where the customer refuses Granite State access or denies such markout service.

Program Reporting

- 13. By January 31, 2013, Granite State shall submit an initial report to the Safety Division of the average accuracy level for markouts made of underground facilities pursuant to the One Call Notification System, and the derivation with sufficient detail supporting the determination of the average used to measure the accuracy level for the Policy. The initial report shall indicate the levels of markout accuracy obtained for Granite State facilities as well as privately owned, residential facilities. The report shall also contain the elements listed in item 14 below. Staff shall review and comment on the submittal, and Granite State shall incorporate Staff's comments into subsequent reports in following years.
- 14. Granite State shall keep track of costs expended and associated data, including but not limited to: number of notifications received, number of markouts made, address locations of markouts, quantity and locations of customer refusals, and dates of services performed. A summary report with subtotals by month shall be submitted to Staff annually, no later than January 31st for the previous calendar year's Policy.
- 15. The new Policy does not require Granite State to file a monthly E-26 report for markouts made under the Policy.

				Liberty Utilities Cast Iror	Bare Steel Program							
	FY 2009	FY 2010	FY 2011	FY 2012	FY 2013	FY 2014	FY 2015	FY 2016	FY 2017	FY 2018	FY 2019	FY 2020
Address	Concord St	2-7 Cornell St	20-34 School St	18-56 Ash St	5-19 Lemon St	1-34 Dickerman St	Pennichuck St & Caron Ave	48 NEWBURY ST, NAS (ON UNDERHILL ST)	22-50 Bridge St, NAS	5-67 Williams St NAS	1-132 Allds St	8 Acton St
Pipe Size	Concord 2"	Concord 2"	Hudson 2"	Nashua 2"	Nashua 2"	Nashua 2"	Nashua 2"	Nashua 2"	Nashua 2"	Nashua 2"	Nashua 2"	Nashua 2"
Install Date	1953	1955	1947	1928	1902/1925	1902/1925	1956/1960	1917 est	1904	1940	1940	1950
Wall Thickness Age	0.166 in 55	Unknown 54	Unknown 63	Unknown 83	Unknown 110	0.154 in 111	0.143 in 58	0.188 in 99 est	0.188 in 112	0.154 in 77	0.154 in 78	0.154 in 69
Pressure	12 in water column	60 psig	12 in water column	12 in water column	12 in water column	12 in water column	12 in water column	12 in water column	12 in water column	12 in water column	12 in water column	12 in water column
Ground PH Pipe Condition	7 to 8 Deep pitting/Significant wall loss	7 to 8 Good condition	7.5 Deep Pitting/Fair to poor Condition	6.5 100% wall loss/Very poor Condition	6 100% wall loss/very poor condition	7.5 90% wall loss/poor condition	6 100% wall loss/Very poor condition	6 100% wall loss/Very poor condition	6 50% wall loss in pits/moderate condition	7.5 30% wall loss in pits	6 100% wall loss/Very poor condition	7 100% wall loss/ moderate pitting
Pipe condition	beep pitting/significant wailloss	Coated steel	beep Fitting/Fail to poor condition	100% wait loss/very poor condition	100% wai loss/very poor condition	50% wall loss/poor condition	100% wantossy very poor condition	100% Wall loss/ very poor condition	50% waitioss in pits/moderate condition	Su /a wai i loss in pits	100% wall loss/ very poor condition	100% wairiossy moderate pitting
Address	Woodman St	83 Pleasant St	2-18 Faxon St & 1-7 Faxon Ave	55-100 W North St	2-13 Grove St	1-44 Revere St & Fernwood St	90 Dodge St	49 Summer St (on Salem St)	18 Howard St, NAS	14-38 Brook St, NAS	1-21 Fowell Ave	Nottingham St & Highland St
Town Pipe Size	Concord 1.5"	Concord 2"	Nashua 2"	Manchester 8"	Nashua 2"	Nashua 2"	Nashua 2"	Nashua 2"	Nashua 2"	Nashua 2"	Nashua 2"	Hudson 1.25"
Install Date	1929	1900	1912	1960	1910	1902/1925	1959	1924	1912	1924	1924	1959
Wall Thickness	0.130 in	Unknown	Unknown	Unknown	Unknown	0.188 in	0.160 in	0.218 in	0.188 in	0.154 in	0.154 in	0.140 in
Age Pressure	79 12 in water column	109 12 in water column	98 12 in water column	51 12 in water column	102 12 in water column	111 12 in water column	55 12 in water column	91 12 in water column	104 12 in water column	93 12 in water column	94 12 in water column	60 60 psig
Ground PH	7 to 8	6	7.5	6	7	7	6	6	6	7	7	6
Pipe Condition	Deep pitting/Significant wall loss	some areas of pitting and wall loss	Multiple large holes/very poor condition	Deep Pitting/Poor Condition	Deep pitting/poor condition	37% wall loss/moderate condition	100% wall loss/very poor condition	100% wall loss/very poor condition	100% wall loss/very poor condition	25-50% wall loss pits	30-50% wall loss pits	30-50% wall loss/ selective corrosion
Address	Connell St	25-28 Depot St	116-130 Bowers St			17-28 Sunset Dr	93 Walnut St		2-15 Columbia Ave, NAS	4-26 Nutt St NAS	171-185 Concord St	Salvail Ct & Canal St
Town	Hudson	Franklin	Nashua			Belmont	Nashua		Nashua	Nashua	Nashua	Nashua
Pipe Size Install Date	1928	2" 1931	2"			2" Unknown	2"		2" 1915	2" 1924	2" 1954	
Wall Thickness	0.139 in	unknown	Unknown			0.188 in	0.160 in		0.188 in	0.154 in	0.154 in	0.154 in
Age	80 12 in water column	78 60 psig	97 12 in water column			Unknown 60 psig	101 12 in water column		101 12 in water column	93 12 in water column	64 12 in water column	91 12 in water column
Pressure Ground PH	12 in water column 6 to 7	60 psig 6	12 in water column 7			60 psig 6	12 in water column 6		12 in water column 6	12 in water column 6	12 in water column 7	12 in water column 76
Pipe Condition	Deep pitting/Significant wall loss	Good condition	Heavy wall loss/poor condition			100% wall loss/very poor condition	100% wall loss/very poor condition		100% wall loss/very poor condition	100% wall loss/very poor condition	100% wall loss/very poor condition	10-20% wall loss/ light corrosion
Address	Gloria Ave	Coated steel 80-113 Blossom St	1-19 Perkins St & 41-46 Bradley St			8-18 Maple St	57 Spaulding St		31-70 McKean St, NAS	3-75 Blossom St, NAS	126-226 Pine St	Second St & Oakwood St
Town	Hudson	Nashua	Concord			Nashua	Nashua		Nashua	Nashua	Hudson	Hudson
Pipe Size	2"	2"	1.5"			2"	2"		2"	2"	2"	2"
Install Date Wall Thickness	1954 0.148 in	1908 & 1913 Unknown	1955 Unknown			1957 0.154 in	1956 0.139 in		1923 0.188 in	1915 0.154 in	1957 0.154 in	1949 0.154 in
Age	54	101	55			56	58		93	102	61	70
Pressure Ground PH	60 psig 7 to 8	12 in water column	12 in water column			12 in water column 6.5	12 in water column		12 in water column	12 in water column	12 in water column	12 in water column
Ground Ph		J.	,							100% well less in the second thread sectors		Heavy corrosion/50% wall loss
Pipe Condition	Fair Condition	Extremely poor condition	Deep pitting/fair to poor condition			39% wall loss/moderate condition	100% wall loss/very poor condition		100% wall loss/very poor condition	100% wall loss in svc connect/mod corros	100% wall loss in pits/very poor condition	open seam
Address	Library St	5-11 Bristol St	Chester St -59 Berkeley St			3-25 Pratt St & Zellwood St	95 Shaker Rd		5-18 Edwin St, NAS	28-36 Fifield St. NAS	l	
Town	Hudson	Nashua	Nashua			Nashua	Concord		Nashua	Nashua		
Pipe Size Install Date	4"	4"	2" 1947			2"	1"		2"	2"		
Wall Thickness	1908 0.234 in	1947, 1951, 1954, 195? Unknown	Unknown			1894/1914 0.188 in	Unknown 0.133 in		1961 0.188 in	1959 0.154 in		
Age	100	62	63			119	Unknown		55	58		
Pressure Ground PH	12 in water column 6	12 in water column 7	12 in water column 7			60 psig	60 psig		12 in water column	12 in water column		
Pipe Condition	Fair Condition	Moderate uniform pitting/Fair Condition	Visible holes/Very poor condition			100% wall loss/very poor condition	27% wall loss/fair condition		100% wall loss/very poor condition	30% wall loss in pits/gen corros pitting		
Address Town	Mulberry St Nashua	12-25 Buck St Nashua				5-21 Ridge St Nashua	249 Medford St Manchester		2-16 Stevens St, NAS Nashua	75-235 Lake St, NAS Nashua		
Pipe Size	2"	2"				2"	2"		2"	2"		
Install Date Wall Thickness	1912	1901, 1903 & 1911 Unknown				Unknown 0.154 in	1956/1960 0.160 in		1904 0.188 in	1900 0.154 in		
Age	96	108				Unknown	58		112	117		
Pressure	12 in water column	12 in water column				12 in water column	60 psig		12 in water column	12 in water column		
Ground PH Pipe Condition	7 to 8 Concentrated deep pitting	6 to 7 Heavy Pitting/Poor Condition				6.5 39% wall loss/moderate condition	100% wall loss/very poor condition		/ 100% wall loss/very poor condition	30% wall loss/gen scaling and pitting		
Address Town	Prescott St & Putnam St Nashua	2-4 Fourth St Nashua				1-6 Jewell Ln Nashua	348 Lincoln St Manchester			4-22 Peabody St TIL Tilton		
Pipe Size	2"	2"				2"	3"			4"		
Install Date	1924 Not Taken Due to Pine Condition	1926				1947 0.154 in	1954 0.224 in			1931		
Wall Thickness Age	Not Taken Due to Pipe Condition 84	Unknown 83				0.154 in 66	0.234 in 60			0.237 in 86		
Pressure	12 in water column	12 in water column				12 in water column	60 psig			60 psig		
Ground PH Pipe Condition	6 to 7 Pipe breakage and pit holes	6 Significant deep pitting/Poor Condition				7 32% wall loss/moderate condition	6 12% wall loss/fair condition			7 20% wall loss/light corros & pitting		
	FY 2009	FY 2010										
Address	Reed Court	31-39 Newbury St										
Town Pipe Size	Nashua 2"	Nashua 2"										
Install Date	1908	1898, 1910, 1928										
Wall Thickness	0.121 in	Unknown 111										
Age Pressure	100 12 in water column	111 12 in water column										
Ground PH	6	3 to 4										
Pipe Condition	Significan wall Loss	Significant wall loss/Poor condition										
Address		5-21 Winter St										
Town		Tilton										
Pipe Size Install Date		4" 1931					+					
Wall Thickness		Unknown										
Age		78										
Pressure Ground PH		60 psig 7										
Pipe Condition		Fair Condition										
63	8	9	5	2	2	7	7	2	6	7	4	4
Samples												
				1		1	1	1	1	1	1	

DG 20-049 RSK Attac<u>brash</u> 2 DG 20-049 Liberty CIBS Program June 12, 2020 Page 2 of 2

FY	Age
2009-1	55
2009-2	79
2009-3	80
2009-4	54
2009-5	100
2009-6	96
2009-7	84
2009-8	100
2005-0	54
2010-1	109
2010-3	78
2010-3	101
2010-4	62
2010-5	108
2010-0	83
2010-7	111
2010-8	78
2010-9	
2011-1 2011-2	63
2011-2	98
	97
2011-4	55
2011-5	63
2012-1	83
2012-2	51
2013-1	110
2013-2	102
2014-1	111
2014-2	111
2014-3	
2014-4	56
2014-5	119
2014-6	
2014-7	66
2015-1	58
2015-2	55
2015-3	101
2015-4	58
2015-5	
2015-6	58
2015-7	60
<mark>2016-1</mark>	<mark>99</mark>
2016-2	91
2017-1	112
2017-2	104
2017-3	101
2017-4	93
2017-5	55
2017-6	112
2018-1	77
2018-2	93
2018-3	93
2018-4	102
2018-5	58
2018-6	117
2018-7	86
2019-1	78
2019-2	94
2019-3	64
2019-4	61
2020-1	69
2020-2	60
2020-3	91
2020-4	70
63	83.1

DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 1 of 76

LIBERTY UTILITIES BARE STEEL REPLACEMENT PROGRAM

2009-2020

Prepared by the New Hampshire Public Utilities Commission Safety Division



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 2 of 76

2020 Bare Steel Replacement Reports



DG 20-049 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 3 of 76

Address	8 Acton St
Town	Nashua
Pipe Size	2"
Install Date	1950
Wall Thickness	0.154"
Age	69
Pressure	12 in water column
Ground PH	7
Pipe Condition	100 % wall loss/ moderate pitting



DG 20-049 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 4 of 76

Address	Nottingham St & Highland St
Town	Hudson
Pipe Size	1.25"
Install Date	1959
Wall Thickness	0.140"
Age	60
Pressure	60 psig
Ground PH	6
Pipe Condition	30-50% wall loss/ selective corrosion



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 5 of 76

Address	Salvail Ct & Canal St
Town	Nashua
Pipe Size	2"
Install Date	1928
Wall Thickness	0.154"
Age	91
Pressure	12 in water column
Ground PH	76
Pipe Condition	10-20% wall loss/ light corrosion



DG 20-049 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 6 of 76

Address	Second St & Oakwood St
Town	Hudson
Pipe Size	2"
Install Date	1949
Wall Thickness	0.154"
Age	70
Pressure	12 in water column
Ground PH	7
Pipe Condition	Heavy corrosion/50% wall loss/ open seam



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 7 of 76

2019 Bare Steel Replacement Reports



DG 20-049 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 8 of 76

Address	1-132 Allds St Mulvaney St sample
Town	Nashua
Pipe Size	2"
Install Date	1940
Wall Thickness	0.154"
Age	78
Pressure	12 in water column
Ground PH	6
Pipe Condition	100 % wall loss in areas



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 9 of 76

Address	1-21 Fowell Ave	
Town	Nashua	401211-37640 1-31 PoweR Ave, Lawerdale Ave, and Park Ave
Pipe Size	2"	and the second parts
Install Date	1924	
Wall Thickness	0.154"	
Age	94	
Pressure	12 in water column	
Ground PH	7	
Pipe Condition	30-50% wall loss in pits	

DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 10 of 76

Address	171-185 Concord St Damon Ave sample
Town	Nashua
Pipe Size	2"
Install Date	1954
Wall Thickness	0.154"
Age	64
Pressure	12 in water column
Ground PH	7
Pipe Condition	100% wall loss in pits



DG 20-049 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 11 of 76

Address	126-226 Pine St Lovell St sample
Town	Nashua
Pipe Size	2"
Install Date	1957
Wall Thickness	0.154"
Age	61
Pressure	12 in water column
Ground PH	6
Pipe Condition	100% wall loss in pits



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 12 of 76

2018 Bare Steel Replacement Reports



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 13 of 76

Address	5-67 Williams St
Town	Nashua
Pipe Size	2"
Install Date	1940
Wall Thickness	0.154"
Age	77
Pressure	12 in water column
Ground PH	7.5
Pipe Condition	30% wall loss in pits



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 14 of 76

Address	14-38 Brook St	
Town	Nashua	401711-37635 Brook St @ 150 Chestnut St, NAS
Pipe Size	2"	
Install Date	1924	and the second sec
Wall Thickness	0.154"	
Age	93	The second second
Pressure	12 in water column	
Ground PH	7	
Pipe Condition	25-50% wall loss in pits	

DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 15 of 76

Address	4-26 Nutt St
Town	Nashua
Pipe Size	2"
Install Date	1924
Wall Thickness	0.154"
Age	93
Pressure	12 in water column
Ground PH	6
Pipe Condition	100% wall loss in pits Heavy Corrosion



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 16 of 76

Address	3-75 Blossom St	401711-37641 36 Blossom St, N
Town	Nashua	and the second second
Pipe Size	2"	HINE ALO
Install Date	1915	
Wall Thickness	0.154"	
Age	102	
Pressure	12 in water column	
Ground PH	6	
Pipe Condition	100% wall loss in pits Very Poor Condition	

DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 17 of 76

Address	28-36 Fifield St & Winnwood St	401711-37642 7 Winnwood St, NAS
Town	Nashua	
Pipe Size	2"	
Install Date	1959	
Wall Thickness	0.154"	
Age	58	
Pressure	12 in water column	
Ground PH	7	
Pipe Condition	30% wall loss in pits General Corrosion/Pitting	

DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 18 of 76

Address	75-235 Lake St	401711-37639 Russell St @ Lake St, NAS
Town	Nashua	THE REAL PROPERTY AND A REAL PROPERTY.
Pipe Size	2"	
Install Date	1900	a strandard
Wall Thickness	0.154"	
Age	117	
Pressure	12 in water column	D 12 113221151
Ground PH	7	
Pipe Condition	30% wall loss in pits General Scaling/Pitting	

DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 19 of 76

Address	4-22 Peabody St	401711-37614 Peabody St @ Winter St, TIL
Town	Tilton	
Pipe Size	4"	
Install Date	1931	
Wall Thickness	0.237"	
Age	86	
Pressure	60 psig	
Ground PH	7	
Pipe Condition	20% wall loss in pits Light Corrosion/Pitting	

DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 20 of 76


2017 Bare Steel Replacement Reports



041

DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 21 of 76

Address	22-50 Bridge St
Town	Nashua
Pipe Size	2"
Install Date	1904
Wall Thickness	0.188 in
Age	112
Pressure	12 in water column
Ground PH	6
Pipe Condition	50% Wall Loss/ Poor Condition



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 22 of 76

Address	18 Howard St	
Town	Nashua	
Pipe Size	2"	
Install Date	1912	
Wall Thickness	0.188 in	
Age	104	
Pressure	12 in water column	
Ground PH	6	
Pipe Condition	100% Wall Loss/ Very Poor Condition	



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 23 of 76

Address	2-15 Columbia Ave
Town	Nashua
Pipe Size	2"
Install Date	1915
Wall Thickness	0.188 in
Age	101
Pressure	12 in water column
Ground PH	6
Pipe Condition	100% Wall Loss/ Very Poor Condition




DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 24 of 76

Address	31-70 McKean St
Town	Nashua
Pipe Size	2"
Install Date	1923
Wall Thickness	0.188 in
Age	93
Pressure	12 in water column
Ground PH	6
Pipe Condition	100% Wall Loss/ Very Poor Condition



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 25 of 76

Address	5-18 Edwin St
Town	Nashua
Pipe Size	2"
Install Date	1961
Wall Thickness	0.188 in
Age	55
Pressure	12 in water column
Ground PH	6
Pipe Condition	100% Wall Loss/ Very Poor Condition



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 26 of 76

Address	2-16 Stevens St
Town	Nashua
Pipe Size	2"
Install Date	1904
Wall Thickness	0.188 in
Age	112
Pressure	12 in water column
Ground PH	7
Pipe Condition	100% Wall Loss/ Very Poor Condition



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 27 of 76

2016 Bare Steel Replacement Reports



048

DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 28 of 76

Address	48 Newbury St NAS (On Underhill St)
Town	Nashua
Pipe Size	2"
Install Date	Unknown
Wall Thickness	0.188 in
Age	Unknown
Pressure	12 in water column
Ground PH	6
Pipe Condition	100% Wall Loss/ Very Poor Condition



DG 20-049 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 29 of 76

Address	49 Summer St (On Salem St)	
Town	Nashua	
Pipe Size	2"	
Install Date	1924	
Wall Thickness	0.218 in	
Age	91	
Pressure	12 in water column	
Ground PH	6	PUMPINE CONTRACTOR
Pipe Condition	100% Wall Loss/ Very Poor Condition	A STATE OF THE PARTY OF THE PARTY

DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 30 of 76

2015 Bare Steel Replacement Reports



051

DG 20-049 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 31 of 76

Address	Pennichuck St & Caron Ave
Town	Nashua
Pipe Size	2"
Install Date	1956/1960
Wall Thickness	0.143 in
Age	58
Pressure	12 in water column
Ground PH	6
Pipe Condition	100% Wall Loss/ Very Poor Condition



DG 20-049 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 32 of 76

Address	90 Dodge St
Town	Nashua
Pipe Size	2"
Install Date	1959
Wall Thickness	0.160 in
Age	55
Pressure	12 in water column
Ground PH	6
Pipe Condition	100% Wall Loss/ Very Poor Condition

Dodge St NAS BS Cutout

DG 20-049 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 33 of 76

Address	93 Walnut St
Town	Nashua
Pipe Size	2"
Install Date	1913
Wall Thickness	0.160 in
Age	101
Pressure	12 in water column
Ground PH	6
Pipe Condition	100% Wall Loss/ Very Poor Condition



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 34 of 76

Address	57 Spaulding St	
Town	Nashua	
Pipe Size	2"	
Install Date	1956	
Wall Thickness	0.139 in	
Age	58	Barn Spald
Pressure	12 in water column	Spaldy NAI
Ground PH	6	
Pipe Condition	100% Wall Loss/ Very Poor Condition	

DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 35 of 76

Address	95 Shaker Road (Shaker Rd School)
Town	Concord
Pipe Size	1"
Install Date	Unknown
Wall Thickness	0.133 in
Age	Unknown
Pressure	60 psig
Ground PH	6
Pipe Condition	27% Wall Loss/ Fair Condition



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 36 of 76

Address	249 Medford St
Town	Manchester
Pipe Size	2"
Install Date	1956/1960
Wall Thickness	0.160 in
Age	58
Pressure	60 psig
Ground PH	6
Pipe Condition	100% Wall Loss/ Very Poor Condition



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 37 of 76

Address	348 Lincoln St	
Town	Manchester	
Pipe Size	3"	BS SUL
Install Date	1954	BS Stul evt out for Lincoln St
Wall Thickness	0.234 in	Lincoln St MAK
Age	60	
Pressure	60 psig	
Ground PH	6	
Pipe Condition	12% Wall Loss/ Fair Condition	

DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 38 of 76


2014 Bare Steel Replacement Reports



059

DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 39 of 76

Address	1-34 Dickerman St
Town	Nashua
Pipe Size	2"
Install Date	1902/1925
Wall Thickness	0.154 in
Age	111
Pressure	12 in water column
Ground PH	7.5
Pipe Condition	90% Wall Loss/ Poor Condition



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 40 of 76

Address	1-44 Revere St & Fernwood St
Town	Nashua
Pipe Size	2"
Install Date	1902/1925
Wall Thickness	0.188 in
Age	111
Pressure	12 in water column
Ground PH	7
Pipe Condition	37% Wall Loss/ Moderate Condition



DG 20-049 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 41 of 76

Address	17-28 Sunset Dr
Town	Belmont
Pipe Size	2"
Install Date	Unknown
Wall Thickness	0.188 in
Age	Unknown
Pressure	60 psig
Ground PH	6
Pipe Condition	100% Wall Loss/Very Poor Condition



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 42 of 76

Address	8-18 Maple St
Town	Nashua
Pipe Size	2"
Install Date	1957
Wall Thickness	0.154 in
Age	56
Pressure	12 in water column
Ground PH	6.5
Pipe Condition	39% Wall Loss/Moderate Condition



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 43 of 76

Address	3-25 Pratt St & Zellwood St
Town	Nashua
Pipe Size	2"
Install Date	1894/1914
Wall Thickness	0.188 in
Age	119
Pressure	60 psig
Ground PH	7
Pipe Condition	100% Wall Loss/ Very Poor Condition



DG 20-049 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 44 of 76

Address	5-21 Ridge St
Town	Nashua
Pipe Size	2"
Install Date	Unknown
Wall Thickness	0.154 in
Age	119
Pressure	12 in water column
Ground PH	6.5
Pipe Condition	39% Wall Loss/ Moderate Condition



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 45 of 76

Address	1-6 Jewell Lane
Town	Nashua
Pipe Size	2"
Install Date	1947
Wall Thickness	0.154 in
Age	66
Pressure	12 in water column
Ground PH	7
Pipe Condition	32% Wall Loss/ Moderate Condition





DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 46 of 76

2013 Bare Steel Replacement Reports



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 47 of 76

Address	5-19 Lemon St
Town	Nashua
Pipe Size	2"
Install Date	1902/1925
Wall Thickness	Unknown
Age	110
Pressure	12 in water column
Ground PH	6
Pipe Condition	100% Wall Loss/ Very Poor Condition



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 48 of 76

Address	2-13 Grove St
Town	Nashua
Pipe Size	2"
Install Date	1910
Wall Thickness	Unknown
Age	102
Pressure	12 in water column
Ground PH	7
Pipe Condition	Deep Pitting/ Poor Condition



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 49 of 76

2012 Bare Steel Replacement Reports



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 50 of 76

Address	18-56 Ash St
Town	Nashua
Pipe Size	2"
Install Date	1928
Wall Thickness	Unknown
Age	83
Pressure	12 in water column
Ground PH	6.5
Pipe Condition	100% Wall Loss/ Very Poor Condition



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 51 of 76

Address	55-100 W North St
Town	Manchester
Pipe Size	8"
Install Date	1960
Wall Thickness	Unknown
Age	51
Pressure	12 in water column
Ground PH	6
Pipe Condition	Deep Pitting/ Poor Condition



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 52 of 76

2011 Bare Steel Replacement Reports



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 53 of 76

Address	20-34 School St	
Town	Hudson	C. And an Augentical -
Pipe Size	2"	
Install Date	1947	
Wall Thickness	Unknown	
Age	63	
Pressure	12 in water column	
Ground PH	7.5	
Pipe Condition	Deep Pitting/ Fair to Poor Condition	

DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 54 of 76

Address	2-18 Faxon St & 1-7 Faxon Ave	
Town	Nashua	
Pipe Size	2"	
Install Date	1912	
Wall Thickness	Unknown	
Age	98	Compression and Caller
Pressure	12 in water column	
Ground PH	7.5	
Pipe Condition	Multiple Large Holes/ Very Poor Condition	8

DG 20-049 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 55 of 76

Address	116-130 Bowers St	-
Town	Nashua	
Pipe Size	2"	-
Install Date	1913	
Wall Thickness	Unknown	6
Age	97	
Pressure	12 in water column	The second
Ground PH	7	
Pipe Condition	Heavy Wall Loss/ Poor Condition	



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 56 of 76

Address	1-19 Perkins St & 41-46 Bradley St	
Town	Concord	46 Brad
Pipe Size	1.5"	a St & 41
Install Date	1955	A REAL PROPERTY OF THE REAL PR
Wall Thickness	Unknown	
Age	55	
Pressure	12 in water column	A Carter
Ground PH	7	
Pipe Condition	Deep Pitting/ Fair to Poor Condition	

DG 20-049 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 57 of 76

Address	Chester St-59 Berkeley St
Town	Nashua
Pipe Size	2"
Install Date	1947
Wall Thickness	Unknown
Age	63
Pressure	12 in water column
Ground PH	7
Pipe Condition	Visible Holes/ Very Poor Condition



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 58 of 76

2010 Bare Steel Replacement Reports



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 59 of 76

Address	2-7 Cornell St
Town	Concord
Pipe Size	2"
Install Date	1955
Wall Thickness	Unknown
Age	54
Pressure	60 psig
Ground PH	7 to 8
Pipe Condition	Good Condition
	Coated Steel





DG 20-049 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 60 of 76

Address	83 Pleasant St
Town	Concord
Pipe Size	2"
Install Date	1900
Wall Thickness	Unknown
Age	109
Pressure	12 in water column
Ground PH	6
Pipe Condition	Some Areas of Pitting and Wall Loss





DG 20-049 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 61 of 76

Address	25-28 Depot St
Town	Franklin
Pipe Size	2"
Install Date	1931
Wall Thickness	Unknown
Age	78
Pressure	60 psig
Ground PH	6
Pipe Condition	Good Condition
	Coated Steel





DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 62 of 76

Address	80-113 Blossom St
Town	Nashua
Pipe Size	2"
Install Date	1908 & 1913
Wall Thickness	Unknown
Age	101
Pressure	12 in water column
Ground PH	5
Pipe Condition	Extremely Poor Condition



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 63 of 76

Address	5-11 Bristol St
Town	Nashua
Pipe Size	4"
Install Date	1947, 1951, 1954, 195?
Wall Thickness	Unknown
Age	62
Pressure	12 in water column
Ground PH	7
Pipe Condition	Moderate Uniform Pitting/ Fair Condition



DG 20-049 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 64 of 76

Address	12-25 Buck St
Town	Nashua
Pipe Size	2"
Install Date	1901, 1903 & 1911
Wall Thickness	Unknown
Age	108
Pressure	12 in water column
Ground PH	6 to 7
Pipe Condition	Heavy Pitting/ Poor Condition



DG 20-049 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 65 of 76

Address	2-4 Fourth St
Town	Nashua
Pipe Size	2"
Install Date	1926
Wall Thickness	Unknown
Age	83
Pressure	12 in water column
Ground PH	6
Pipe Condition	Significant Deep Pitting/ Poor Condition



DG 20-049 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 66 of 76

Address	31-39 Newbury St		
Town	Nashua		
Pipe Size	2"		
Install Date	1898, 1910, 1928		
Wall Thickness	Unknown		
Age	111		
Pressure	12 in water column		
Ground PH	3 to 4		
Pipe Condition	Significant Wall Loss/ Poor Condition		







DG 20-049 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 67 of 76

Address	5-21 Winter St		
Town	Tilton		
Pipe Size	4"		
Install Date	1931		
Wall Thickness	Unknown		
Age	78		
Pressure	60 psig		
Ground PH	7		
Pipe Condition	Fair Condition		



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 68 of 76

2009 Bare Steel Replacement Reports



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 69 of 76

Address	Concord St	
Town	Concord	
Pipe Size	2"	
Install Date	1953	
Wall Thickness	0.166 in	
Age	55	
Pressure	12 in water column	
Ground PH	7 to 8	
Pipe Condition	Deep pitting/Significant wall loss	



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 70 of 76

Address	2 Woodman St		
Town	Concord		
Pipe Size	1.5"		
Install Date	1929		
Wall Thickness	0.130 in		
Age	79		
Pressure	12 in water column		
Ground PH	7 to 8		
Pipe Condition	Deep pitting/Significant wall loss		



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 71 of 76

Address	Connell St
Town	Hudson
Pipe Size	2"
Install Date	1928
Wall Thickness	0.139 in
Age	80
Pressure	12 in water column
Ground PH	6 to 7
Pipe Condition	Deep pitting/Significant wall loss



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 72 of 76

Address	Gloria Avenue		
Town	Hudson		
Pipe Size	2"		
Install Date	1954		
Wall Thickness	0.148 in		
Age	54		
Pressure	60 psig		
Ground PH	7 to 8		
Pipe Condition	Fair Condition		





Address	Library St		
Town	Hudson		
Pipe Size	4"		
Install Date	1908		
Wall Thickness	0.234 in		
Age	100		
Pressure	12 in water column		
Ground PH	6		
Pipe Condition	Fair Condition		



DG 20-049 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 74 of 76

Address	Mulberry St
Town	Nashua
Pipe Size	2"
Install Date	1912
Wall Thickness	0.124 in
Age	96
Pressure	12 in water column
Ground PH	7 to 8
Pipe Condition	Concentrated Deep Pitting



DG 20-049 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 75 of 76

Address	Prescott St & Putnam St
Town	Nashua
Pipe Size	2"
Install Date	1924
Wall Thickness	Not Taken Due to Poor Condition
Age	84
Pressure	12 in water column
Ground PH	6 to 7
Pipe Condition	Pipe Breakage and Pit Holes



DG 20-049 Exhibit 2 RSK Attachment 4 DG 20-049 Liberty CIBS Program June 12, 2020 Page 76 of 76

Address	Reed Ct		
Town	Nashua		
Pipe Size	2"		
Install Date	1908		
Wall Thickness	0.121 in		
Age	100		
Pressure	12 in water column		
Ground PH	6		
Pipe Condition	Significant Wall Loss		



Liberty Utilities (EnergyNorth Natural Gas) Corp. d/b/a Liberty Utilities

DG 20-049 FY 2020 Cast Iron/Bare Steel Replacement Program Results

Staff Data Requests - Set 2

Date Request Received: 5/15/20 Request No. Staff 2-1 Date of Response: 5/29/20 Respondent: Brian Frost

REQUEST:

Please provide the Company's projected timeline to complete the replacement of all CIBS mains and services within the Company's service territories. Please include the following information:

- a) Existing miles of cast iron mains at the start and end of each year;
- b) Existing miles of cast iron services at the start and end of each year;
- c) Existing miles of bare steel mains at the start and end of each year;
- d) Existing miles of bare steel services at the start and end of each year;
- e) Linear footage replaced each year;
- f) Annual cost of CIBS replacement;
- g) Annual average cost per foot of CIBS replacement.

RESPONSE:

The Company does not have a projected timeline to complete replacement of all cast iron and bare steel mains. Additionally, since a CIBS-specific timeline is not available, projected data is not separated between cast iron, bare steel, gas mains, or gas services. Likewise, the Company does not have projections of future costs specifically for cast iron and bare steel replacement.

Looking at past filings, in Docket No. DG 19-054 the Company had 66.0 miles of cast iron and bare steel main remaining at the conclusion of the FY 2019 replacement program. In this docket the Company described a total planned cast iron and bare steel replacement during the year from all types of work as 12.9 miles. Based upon this year's planned construction, and simply assuming this year's rate of CIBS replacement will continue in future years, a future calendar is listed below.

Year	Total Replacement	Cast Iron and Bare Steel
	(miles)	Remaining (miles)
End of FY 2019 Program		53.1
FY 2020–21	8	45.1
FY 2021–22	8	37.1

Year	Total Replacement	Cast Iron and Bare Steel
	(miles)	Remaining (miles)
FY 2022–23	8	29.1
FY 2023–24	8	21.1
FY 2024–25	8	13.1
FY 2025–26	8	5.1
FY 2026–27	5.1	0

		2020		2021	
CapEx - Replenishment Mandated		1010			
Cathodic Protection Program	\$	400,000	\$	400,000	
Cathodic Protection/Corrosion Mitigation Program	\$	5,000	\$	5,000	
Corrosion & Miscellaneous Fitting	\$	150,000	\$	150,000	
Leak Repairs	\$	1,000,000	\$	1,200,000	
Meter Protection Program	\$	300,000	\$	300,000	
Meter Work Project (Meter Purchases)	\$	1,000,000	\$	1,420,545	
Replacement Services Random	\$	10,000	\$	10,000	
Replacement Services Random (Due to Leaks)	\$	550,000	\$	350,000	
Replacement Services Random (Non Leaks)	\$	350,000	\$	150,000	
Reserve for Unidenfitied Mandated Projects	\$	200,000	\$	200,000	
Valve Installation/Replacement	\$	90,000	\$	90,000	
Regulatory					
Main Replacement LPP Main Replacement LPP-Restoration	\$ \$	9,042,804 4,114,376	\$ \$	9,495,000 4,000,000	CIBS Program
Discretionany					
Discretionary Aldyl-A Replacement Program	\$		\$	450,000	
Capital Tools/Equipment	\$ \$	35,000	\$	25,000	
Dispatch and Control Center	\$	10,000	\$	10,000	
K Meter Replacement Program	\$	430,000	\$	430,000	
Main Replacement Fitting LPP	Ş	740,501	Ş	1,000,000	
Main Replacement Reactive	\$ \$	500,000	ې \$	500,000	
Nashua Paving	\$ \$	800,000	\$ \$		
Regulator removal Hi line LOU	\$ \$	50,000		- 175,000	
Reserve for Unidentified Projects	\$	25,000		25,000	
RTU Replacement Program	\$ \$	60,000		60,000	
SCADA Capital Improvements	\$ \$	80,000	\$	80,000	
Transportation Fleet and Equipment Purchases	Ş	198,000	\$	- 80,000	
Upgrade Synergi Software	\$	60,000	\$	- 65,000	
Safety					
2' Jamesbury replacement program	\$	60,000	\$	60,000	
CapEx - Improvement					
Mandated					
Dresser Coupling Replacement Program	\$	500,000	\$	550,000	
Inactive Service Program	\$	75,000		75,000	
Install Security Equipment - EN Facilities	\$	50,000		100,000	
LNG/LPG Capital Improvements	\$	100,000		100,000	
Main Replacement City/State Construction	\$	5,118,485		5,200,000	
Pre-Code Stee Pipe Protection Program/Replacement	\$	268,778		300,000	
Service Replacement City/State Construction Service Replacement Fitting City/State Construction	\$ \$	25,000 303,000	\$ \$	25,000 270,000	
Safety					
Salety					
Discretionary	-	00			
Fortis Software	\$	98,659	\$	-	
EN Facilities Capital Improvements	\$	600,000		600,000	
Facility Improvements & Additions - Keene	\$	25,000	\$	5,000	
Finance Unalloc Burden	\$	703,143	\$	700,000	
Flir Cameras - Security -Manchester	\$	986,000	\$	-	
Flir Cameras - Security-Keene	Ş	364,000		-	
Gas System Control & Regulation (ENG)	\$	350,000		325,000	
Gas System Planning & Reliability GPS Mapping Equipment	\$ \$	2,900,000		2,900,000	
	\$ \$	15,000		-	
iRestore System Enhancements	\$ \$	200,000			
IT - Software, Equipment & Infrastructure	\$ \$	75,000		75,000 500,000	
IT Systems Allocations - Corporate Material Bar Coding	\$ \$	55,000 187 500		500,000	
Materiai Bar Coaing NH GIS & OMS Database Split & Tuning	\$ \$	187,500 95,000		-	
NH GIS & OMS Database Split & Tuning Purchase Misc Capital Equipment & Tools	\$ \$	95,000 280,000		- 295,000	
SAP-Ariba EN Portion Procure to Pay Software	\$ \$			295,000	
SAP-Ariba EN Portion Procure to Pay Software SCADA Data center upgrades	\$ \$	350,798 50,000		-	
SCADA Data center upgraaes Service Mapping Project	\$ \$			-	
Service Mapping Project Transportation Fleet and Equipment Purchases	\$ \$	100,000 2,663,000		- 2,600,000	
CapEx - Growth					
Growth					
CNG/LNG Costs (placeholder)	\$	627,628		-	
Granite Bridge Alternative 2020	\$	50,000			
Growth Fitting	\$	1,504,528		1,500,000	
Growth New Main	\$	4,774,420		4,799,455	
Main Replacement/Growth Fitting	\$	5,000		5,000	
Marketing & Sales	\$	-	\$	100,000	
New Reinforcement Main for Growth ENG	\$	368,180		1,000,000	
New Service Comm/Industrial	\$	1,097,723		1,030,000	
New Service Residential	\$	3,156,007		4,025,000	
Reserve for Unidentified Growth ENG	\$	1,577,469		1,600,000	
Windham-Pelham Managed Expansion Project	\$	450,000	\$	-	
	\$	50,410,000	\$	49,330,000	



BSK Attachment 6B DG 20-049 Liberty CIBS Program June 12, 2020 Page 1 of 5

Steven E. Mullen Director, Rates & Regulatory Affairs O: 603-216-3516 E: Steven.Mullen@libertyutilities.com

May 13, 2020

Via ERF and US Mail

Debra A. Howland Executive Director New Hampshire Public Utilities Commission 21 S. Fruit Street, Suite 10 Concord, NH 03301-2429

Re: Liberty Utilities (EnergyNorth Natural Gas) Corp. and Liberty Utilities (EnergyNorth Natural Gas) Corp – Keene Division both d/b/a Liberty Utilities E-22 Proposed Expenditures for Additions, Extensions and Capital Improvements to Fixed Capital – 2020 Construction Season

Dear Ms. Howland:

Pursuant to Puc 509.11, enclosed for filing please find Liberty Utilities' E-22 Report of Proposed Expenditures for Additions, Extensions and Capital Improvements to Fixed Capital. Please note this report has been filed via the Commission's Electronic Report Filing System.

Thank you for your attention to this matter. Please do not hesitate to call if you have any questions.

Sincerely,

Stor M.

Steven E. Mullen

Enclosure

2149/2150

DG 20-049 RSK Attachment 6B Exhibit 2 DG 20-049 City.State Construction_2020 Liberty CIBS Program June 12, 2020 Page 2 of 5

NEW HAMPSHIRE PUBLIC UTILITIES COMMISSION YEARLY REPORT OF PROPOSED EXPENDITURES FOR ADDITIONS, EXTENSIONS AND CAPITAL IMPROVEMENTS TO FIXED CAPITAL

RET REFORT OF TROFOSED EXTENDITORES FOR ADDITIONS, EXTENSIONS AND CALIFICE INTROVEMENTS TO FIXED
(In Compliance with Puc 509.11)

No. TOWN STREET SIZE MATERIAL LENGTH COST DESCRIPTION 1 Various Service Replacement Fitting City/State Construction \$\$303.000 Blanket projet under EnergNorth for main replacement for city/state construction 2 Various Main Replacement City/State Construction \$\$4,654,819 Blanket projet under EnergNorth for fitting replacement for city/state construction 3 Keene Main Replacement City/State Construction \$\$4,65,666 construction 4 Keene Service Replacement City/State Construction \$\$25,000 Blanket projet under Keene for fitting replacement for city/state 4 Keene Service Replacement City/State Construction \$\$25,000 Blanket projet under Keene for fitting replacement for city/state 4 Keene Service Replacement City/State Construction \$\$25,000 Blanket projet under Keene for fitting replacement for city/state 5 1 1 1 1 1 1 1 6 1 1 1 1 1 1 1 7 1 1 1 1 1 1 1 1 8 1 <th></th> <th></th> <th>LOCATION</th> <th>PIF</th> <th>PE SPECIFICA</th> <th colspan="2">TIONS</th> <th>STIMATED</th> <th></th> <th>]</th>			LOCATION	PIF	PE SPECIFICA	TIONS		STIMATED]
1 Various Service Replacement Fitting City/State Construction \$ 303,000 construction 2 Various Main Replacement City/State Construction \$ 4,654,819 Blanket project under EnergyNorth for fitting replacement for city/state construction 3 Keene Main Replacement City/State Construction \$ 4,654,819 Blanket project under Keene for fitting replacement for city/state construction	No.	TOWN	STREET	SIZE	MATERIAL	LENGTH				
2 Various Main Replacement City/State Construction \$ 4,654,819 construction 3 Keene Main Replacement City/State Construction \$ 463,666 Blanket project under Keene for fitting replacement for city/state construction	1	Various	Service Replacement Fitting City/State Construction				\$	303,000	construction	8840-1925
3 Keene Main Replacement City/State Construction \$ 463,666 construction Image: Construction in the state of the stat	2	Various	Main Replacement City/State Construction				\$	4,654,819	construction	8840-1923
	3	Keene	Main Replacement City/State Construction				\$	463,666	construction	8843-1908
Image: Constraint of the symbol of the sym	4	Keene	Service Replacement City/State Construction				\$			8843-1909
Image: series of the series										-
Image: Constraint of the symbolImage: Constrai										1
Image: selection of the										-
Image: Section of the section of th										-
Image: Constraint of the system of the sy										-
Image: Constraint of the system Image: Constra										-
										-
										4
TOTAL \$ 5,446,485						TOTAL	\$	5,446,485]
Supervisor's Name / Title: (please print) Rich MacDonald / Vice President Operations Bich MacDonald	-					_				

Supervisor's Signature:

Rich MacDonald Date: 2020.05.12 10:03:54 -04'00'

Date Submitted: May 12, 2020

LOCATION PIPE SPECIFICATIONS ESTIMATED STREET SIZE MATERIAL LENGTH COST

No.	TOWN	STREET	SIZE	MATERIAL	LENGTH	COST	DESCRIPTION	
1	Various	Main Replacement Reactive				\$ 500,000	Blanket program to provide for replacement of gas mains and services during urgent or emergency situations which fall outside the normal scope of integrity, reinforcement, reliability and public works blankets.	8840-1916
2	Various	Replacement Services Random (Due to	Leaks)			\$ 550,000	Blanket project to provide random replacement services due to leaks	8840-1905
3	Various	Leak Repairs				\$ 1,000,000	Blanket program to address main valve cluster leaks which reoccur year to year after maintenance by replacing these assets.	8840-1910
5	Various	Main Replacement LPP				\$ 12,715,474	Blanket program under EnergyNorth to address defects affecting the physical soundness of distribution and facilities before they become a safety-related problem. The program calls for the prioritized replacement of unprotected bare steel and cast iron pipe.	8840-1911/2011
4	Various	Main Replacement Fitting LPP				\$ 740,501	Blanket program under EnergyNorth to identify and replace meter installations associated with the LPP Main Replacement Program.	8840-1913
6	Keene	Main Replacement LPP				\$ 441,706	Blanket program under Keene to address defects affecting the physical soundness of distribution and facilities before they become a safety-related problem. The program calls for the prioritized replacement of unprotected bare steel and cast iron pipe.	8843-2011
Supervis	or's Name / Title:	Richard MacDonald / Vice Presi	dent One	rations	TOTAL	\$ 15,947,681		1

NEW HAMPSHIRE PUBLIC UTILITIES COMMISSION YEARLY REPORT OF PROPOSED EXPENDITURES FOR ADDITIONS, EXTENSIONS AND CAPITAL IMPROVEMENTS TO FIXED CAPITAL (In Compliance with Puc 509.11)

(please print)

Supervisor's Signature: Rich MacDon

Rich MacDonald Digitally signed by Rich MacDonald Date: 2020.05.12 10:04:29 -04'00'

Date Submitted: _____

NEW HAMPSHIRE PUBLIC UTILITIES COMMISSION YEARLY REPORT OF PROPOSED EXPENDITURES FOR ADDITIONS, EXTENSIONS AND CAPITAL IMPROVEMENTS TO FIXED CAPITAL (In Compliance with Puc 509.11)

		LOCATION	PIF	PE SPECIFICA	ΓIONS	ESTIN	MATED]
No.	TOWN	STREET	SIZE	MATERIAL	LENGTH	CC	DST	DESCRIPTION	
1	Various	New Reinforcement Main for Growth				\$		Blanket project under EnergyNorth created as a placeholder for anticipated growth for year-ahead activity.	8840-194
	Various	Growth New Main				\$ 4	4,674,420	Blanket project under EnergyNorth for new main growth based on historical spending trends and anticipated year- ahead activity.	8840-194
2	Various	Growth Fitting				\$ 1	1,504,528	Blanket project under EnergyNorth for growth fitting (meters & services) based on historical spending trends and anticipated year-ahead activity.	8840-194
3	Various	New Service Comm/Industrial				\$ 1		Blanket project under EnergyNorth for new commercial/industrial service based on historical spending trends and anticipated a year-ahead activity.	8840-195
4	Various	New Service Residential				\$ 3	3,131,007	Blanket project under EnergyNorth for new residential service based on historical spending trends and anticipated a year-ahead activity.	8840-1950
	Pelham	Windham-Pelham Managed Expansion Project				\$	450,000	Blanket project for subsequent restoration/completion required by the Town of Pelham.	8840-1961
	Keene	Growth New Main				\$	100,000	Blanket project under Keene for new main growth based on historical spending trends and anticipated year-ahead activity.	8843-191
5	Keene	Main Replacement/Growth Fitting				\$	5,000	Blanket project under Keene for growth fitting (meters & services) based on historical spending trends and anticipated year-ahead activity.	8843-1916
	Keene	New Service Residential				\$		Blanket project under Keene for new residential service based on historical spending trends and anticipated a year- ahead activity.	8843-1917
	Keene	New Service Comm/Industrial				\$	30,000	Blanket project under Keene for new commercial/industrial service based on historical spending trends and anticipated a year-ahead activity.	8843-1918
Superviso	r's Name / Title	Richard MacDonald / Vice President	Operations	ļ	TOTAL	\$ 11	1,355,858]

(please print)

Supervisor's Signature:

Digitally signed by Rich MacDonald **Rich MacDonald**

Date: 2020.05.12 10:05:10 -04'00'

Date Submitted: _

NEW HAMPSHIRE PUBLIC UTILITIES COMMISSION

YEARLY REPORT OF PROPOSED EXPENDITURES FOR ADDITIONS, EXTENSIONS AND CAPITAL IMPROVEMENTS TO FIXED CAPITAL (In Compliance with Puc 509.11)

		LOCATION		PE SPECIFICA		ESTIMA		
No.	TOWN	STREET	SIZE	MATERIAL	LENGTH	COS		DESCRIPTION
1	Various	Reserve for Unidenfitied Mandated Projects				\$ 2	200,000	
2	Various	Upgrade Synergi Software					60,000	
3	Various	Inactive Service Program					75,000	
4	Various	GPS Mapping Equipment					15,000	
5	Various	Service Mapping Project				\$ 1	00,000	
6	Various	Meter Protection Program				\$ 3	300,000	
7	Various	Cathodic Protection Program				\$ 4	400,000	
8	Various	Replacement Services Random (Non Leaks)				\$ 3	350,000	
9	Various	Corrosion & Miscellaneous Fitting				\$ 1	50,000	
10	Various	Valve Installation/Replacement					85,000	
11	Various	K Meter Replacement Program				\$ 4	130,000	
12	Various	Dispatch and Control Center				\$	10,000	
13	Various	Purchase Misc Capital Equipment & Tools				\$ 2	280,000	
14	Various	Regulator removal Hi line LOU				\$	50,000	
15	Various	SCADA Capital Improvements				\$	80,000	
16	Nashua	Nashua Paving				\$ 8	300,000	
17	Various	LNG/LPG Capital Improvements				\$ 1	00,000	
18	Various	Reserve for Unidentified Growth ENG				\$ 1,5	577,469	
19	Various	Gas System Control & Regulation (ENG)				\$ 3	350,000	
20	Various	Pre-Code Stee Pipe Protection Program/Replacement				\$ 2	268,778	
21	Various	IT - Software, Equipment & Infrastructure				\$	50,000	
22	Various	Gas System Planning & Reliability				\$ 2,9	900,000	
23	Various	SCADA Data center upgrades				\$	50,000	
24	Various	IT Systems Allocations - Corporate				\$	55,000	
25	Various	Dresser Coupling Replacement Program				\$ 5	500,000	
26	Various	iRestore System Enhancements				\$ 2	200,000	
27	Various	Flir Cameras - Security -Manchester				\$ 9	986,000	
28	Various	NH GIS & OMS Database Split & Tuning				\$	95,000	
29	Various	RTU Replacement Program				\$	60,000	
30	Various	2' Jamesbury replacement program				\$	60,000	
31	Various	SAP-Ariba EN Portion Procure to Pay Software				\$ 3	350,798	
32	Various	Fortis Software				\$	98,659	
33	Various	Material Bar Coding					87,500	
34	Various	Transportation Fleet and Equipment Purchases				\$ 2,6	563,000	
35	Various	Meter Work Project (Meter Purchases)				\$ 1,0	000,000	
36	Various	EN Facilities Capital Improvements				\$ 6	500,000	
37	Various	Install Security Equipment - EN Facilities				\$	50,000	
38	Various	Granite Bridge Alternative 2020					50,000	
39	Various	Finance Unalloc Burden				\$ 7	/03,143	
40	Keene	Capital Tools/Equipment		1			35,000	
41	Keene	Cathodic Protection/Corrosion Mitigation Program				\$	5,000	
42	Keene	CNG/LNG Costs (placeholder)					527,628	
43	Keene	Facility Improvements & Additions - Keene					25,000	
44	Keene	Flir Cameras - Security-Keene			İ		364,000	
45	Keene	IT - Software, Equipment & Infrastructure			İ		25,000	
46	Keene	Keene HP Conversion to CNG				\$	-	
47	Keene	Replacement Services Random		1			10,000	
48	Keene	Reserve for Unidentified Projects		1			25,000	
49	Keene	Transportation Fleet and Equipment Purchases					98,000	
50	Keene	Valve Installation/Replacement		1		\$	5,000	
			1	1	TOTAL		559,975	

Supervisor's Name / Title: (please print)

Richard MacDonald / Vice President Operations

Rich MacDonald

Supervisor's Signature:

Digitally signed by Rich MacDonald Date: 2020.05.12 10:05:38 -04'00'

Date Submitted:

Other-2020

Nome Nome	WO Number	Project Name	Town	Scope	Primary Material Project Affects	Total Main Relay Length	Total Main Abandon Only Length	Sum of Relay and Abandon Length (Column F +	Total Number Of Services in Project	Loaded Cost Estimate	Project Cost/Foot (Column J/Column H)
	402011-37618	101 Major Dr, NAS	NASHUA			1,100	cengen		9	\$207,055	\$188.23
				Due to paving, relay approx. 200' of 6" CI LP on Main St from Lowell St to							
Del mon mon manual Del mon manua Del mon manual Del	402023-37620	1-15 Main St Hetcher St, NAS	NASHUA	St with 4" PL LP.	a	265		265	1	\$199,204	\$/51./1
	402011-37605	1-22 Second St, Ferry St, School St, and Oakwood St	HUDSON	St from Oakwood St to Ferry St with 2" PL 60# gas main. Relay approximately 200' 2" BS LP (1960), 30' 3" PL LP (2006), and 150' 2" CS LP (1962) on School St from Second St to Third	BS	1,445		1,445	12	\$384,742	\$266.26
	402011-37626	1-32 FARLEY ST, NAS	NASHUA	main. Relay 325' 4" CI LP (1909) on Reservoir St with 2" PL 60# main. Relay 485' 2" BS LP (1900) and 60' 4" CI LP (1928) on Wellington St with 2" PL 60# main. Relay 615' 4" CI	a	2,045		2,045	24	\$711,674	\$348.01
No. 10 No. 10	402023-37607	1-4 Hooksett Rd, Webster St, Beech St	MANCHESTER	St to Hooksett Rd with 8" PL LP. Relay approx. 220 of 4" CI LP main on Beech St from Webster St to #921 Beech St with 4" PL LP. Abandon approx. 190' of	a	350	190	540	3	\$143,415	\$265.58
	402023-37615	1-4 Lovell St	NASHUA	Due to paving, relay approx. 120' of 2" BS LP main on Lovell St from	BS	120		120	2	\$72,621	\$605.18
	402016-37604	16 Euclid Ave	NASHUA	Due to an encroachment, relay approx. 30' of 6" CI LP main on Euclid Ave at #16 Euclid with new 6" PL LP.	CI	30		30	0	\$44,534	\$1,484.47
Description Description <thdescription< th=""> <thdescription< th=""></thdescription<></thdescription<>				St to Miami Ct with 2" PL 60#.	a				6		\$317.10
	402023-37601 402023-37622			Due to paving, relay approx. 900' of 8" CI LP on Main St from W Pearl St to W	a				9		\$501.20 \$916.46
Display a propriet of the second se	402011-37603	21-69 S State St, CCD	CONCORD	Relay 145' of 3" CI LP with 4" PL LP on Wall St. Relay 287' of 10" CI LP with 4" PL LP on S State St from Wall St to Fayette St. Relay 258' of 4" CI LP with 4" PL LP on Fayette St. Relay 152' of 6" CI LP with 6" PL LP on Thompson St.	a	2,275		2,275	36	\$724,117	\$318.29
Nome Nome	402023-37602	231-339 Kelley St, Alsace St, and Youville St	MANCHESTER	Install approx. 240' of 6" PL LP on Montgomery St from Bremer St to the existing 6" PL LP dead end at #627 Montgomery. Extend approx. 365' of 2" 60 PSIG main on Kelley St from the existing 4" PL 60 PSIG dead end at #53	a	905	1,980	2,885	29	\$417,873	\$144.84
	402023-37603	253-309 Lake Ave	MANCHESTER	Due to paving, relay approx. 700' of 3" CI LP main on Lake Ave from Beech St	a	700		700	11	\$268.113	\$383.02
				Due to paving, relay approx. 80' of 2" BS LP main on Lovewell St from Ritter	BS						\$713.94
	402023-37604	396-430 Lake Ave	MANCHESTER	Due to paving, relay approx. 375' of 4" CI LP main on Lake Ave from Wilson	a	375		375	10	\$184,999	\$493.33
	401911-37607	42-68 S Spring St	CONCORD	Relay approximately 785' 4" CI LP (1899, 1857) on S Spring St with 2" PL 60#	a	785		785	19	\$226,573	\$288.63
	402023-37609	499-786 Massabesic St	MANCHESTER	Due to paving, relay approx. 645' of 4" CI LP main on Massabesic St from Tarrytown Rd to #773 Massabesic with new 4" PL LP main. Abandon approx. 750' of 6" CI & PL LP main on Massabesic St from Jewett St to #541	a	645	750	1,395	17	\$265,659	\$190.44
	402023-37606	621-642 Hall St	MANCHESTER	Due to paving, relay approx. 310' of 3" CI LP main on Hall St from E High St to	a	310		310	6	\$101,121	\$326.20
DBL DBL 000 000 DBL DBL 000 0000 DBL DBL 000 0000000000000000000000000000	402023-37621	69-168 Main St, Water St Factory St	NASHUA	Due to paving, relay approx. 825' of 6" & 12" CI LP main on Main St from Pearson Ave to High St with new 12" PL LP. Relay approx. 270' of 4" CI & CS LP main on Water St with new 4" PL LP. Relay approx. 105' of 4" CI & CS LP	a	1,200		1,200	7	\$836,441	\$697.03
	402023-37624	72-80 Allison St, CCD	CONCORD	Relay 285' of 4" CI LP with 4" PL LP. Transfer all services.	CI	285		285	6	\$107,866	\$378.48
	402011-37625	84-136 LEDGE ST, NAS FIRST-SEVENTH STS (CIBS)	NASHUA	from Third St to Seventh St with 8" PL LP. Relay approximately 370' 4" CI LP (1922), 155' 4" BS (1950), and 75' 4" PL LP (2005, 2006) on Seventh St from new regulator pit outlet	a	1,400		1,400	21	\$911,429	\$651.02
				with new 6" PL LP	a				1		\$3,833.60
Answer of the state o				Due to paving, relay approx. 1,120' of 4" CI LP main on Adams St from Elliot St to Baker St with new 4" PL LP. Extend approx. 180' of 4" PL LP main on Adams St from Elliot St to #11 Adams and tie into new 4" PL LP main installed	a		155		13		\$135.57
Max and with the set of the set	402016-37606	Amherst St at Vernon St	NASHUA	Due to a drainage encroachment, relay approx. 30' of 6" CI LP on Amherst St at Vernon St with new 6" PL LP.	a	60		60	0	\$74,456	\$1,240.93
Bail Mail Mail Mage manufactor PC PU FUR MIN PUP PUP PUP PUP PUP PUP PUP PUP PUP PU	402011-37631	Batchelder Ave, MNC	MANCHESTER	Relay on Batchelder Ave from Hayward St with 2" PL 60#. Relay on Havard St from Union St to Beech ST with 2" PL 60#. Do not disturb 12" CI LP on	a	840		840	23	\$471,412	\$561.20
No.10 No.10 <th< td=""><td>402011-37620</td><td>Booth St, NAS</td><td>NASHUA</td><td>Relay approximately 725" of 2" BS LP (1948, 1949) and 2" PL LP (1991) on</td><td>BS</td><td>725</td><td></td><td>725</td><td>13</td><td>\$208,154</td><td>\$287.11</td></th<>	402011-37620	Booth St, NAS	NASHUA	Relay approximately 725" of 2" BS LP (1948, 1949) and 2" PL LP (1991) on	BS	725		725	13	\$208,154	\$287.11
	402011-37616	Bridge St, MNC	MANCHESTER	Relay approximately 1295' 3" CI LP (1892, 1894) and 35' 4" PL LP (2013) on Bridge St from Maple St to Ashland St with 2" PL 60# main. Install approximately 40' of 2" PL 60# on Russel St at Bridge St intersection to stub	a	1,380		1,380	33	\$488,554	\$354.02
Delix D0 Origin D4, D40 Number D4 (7) (1) (2) (1) (1) (1) (1) (1) (1) (1) (1) (1) (1	402023-37613	Burnett St	NASHUA	Due to paving, relay approx. 255' of 4" CI LP main on Burnett St from Rice St to Oakland Ave with new 4" PL LP. Relay approx. 45' of 4" CS LP main on Rice St at Burnett St with new 4" PL LP. Relay approx. 30' of 4" CI LP main on	ci	330		330	6	\$206,075	\$624.47
Description Description of the sector of the s	402011-37609	Central St, MNC	MANCHESTER	Abandon on 1160' 6" CI (1907) on Central St from Maple St to Union St and	a	0	1,160	1,160	3	\$33,652	\$29.01
Normal Number Description of the product of the produ	402023-37625	Church St at Main St	LACONIA	Due to paving, relay approx. 70' of 8" CI LP main at the intersection on	a	70		70	0	\$42,573	\$608.19
Description Description Part of the UP FROM training adverse. O Add	402023-37623	Crescent St, NAS	NASHUA	Due to sewer replacement, relay approx. 220' of 4" CI LP main on Crescent St from Manchester St to the service for #5 Abbott St with new 4" PL LP. Abandon approx. 90' of 4" CI LP main on Crescent St from the service for #5	a	220	90	310	4	\$154,325	\$497.82
2011 100 Int S Int S< Int S Int S<	402011-37623			Relay 483' of 4" CI LP with 2" PL 60#. Transfer all services.	a				3		\$230.35
Control Contro Control Control Control Control Control Control Control Control				Due to paving, relay approx. 120' of 4" CI LP on Gates St from #11 Elliot St to	a				16		\$506.08
Auge 2013 3137 Geb 14 bidge MANGETS Manual Strip Geb 14 bidge scenario (100 More Sec 2014 More	402023-37614		NASHUA	Due to paving, relay approx. 325' of 4" CI LP main on Field St from Ferwood	a				5		\$540.92
Control 2013 Marcel 2013 Marcel 2014 Marcel	401923-37607	Goffs Falls Bridge	MANCHESTER	Due to bridge reconstruction, HDD 360' of 6" PL 60 PSIG main under the Goffs Falls Bridge. Tie into the existing 6" CS 60 PSIG main east of the bridge and the 6" PL 60 PSIG main west of the bridge. Relay approx. 275' of 2" PL 60	a	675		675	1	\$216,888	\$321.32
이미 1 2 File Interstate, MMC MARCHER Registrate from Call Field Field State State FIE, Call Field State State FIE, Call Field State State FIE, Call Field State State FIEld State FIEld State State FIEld State FIEld State State FIEld State State FIEld	402011-37614	Harrington Ave, MNC	MANCHESTER	Relay on Harrington Ave from Calef Rd to S Elm St with 4" PLLP. Relay on W Harrington Ave from S Elm St to house number 25 with 4" PLLP. Relay on S Elm St from Harrington Ave to house number 286 with 4" PLLP. Relay on	a	1,915	75	1,990	26	\$541,526	\$272.12
Unit 12-R Imply Max, Max, MOUNTSING Cloweds PL (P from S20 G23 LOBA) (web, Trander all exvisors. U 1.40 1.40	402011-37612	Hillcrest Ave, MNC	MANCHESTER	Relay on Hillcrest Ave from Calef Rd to dead end with 4" PL LP. Relay on	a	870		870	13	\$363,206	\$417.48
Coll 1-3763 Lund St, NA5 NA5HUA Relay on Lund St from Novell St to Lake St with 2" Pt. GB. Relay on Brewster St from Lund St to Danced St with 2" Pt. GB. Te over services and Bandon D 2023-3763 Coll 2,250 220 2,30 24 558,177 523,14 2023-3763 Manmach Rd MACKISTER Bithy approximately 320 of C C, S, R Pt. Dr main on Mannho Rd from Relay 200 of C C, S, R Pt. Dr main on Mannho Rd from Relay 200 of C C, S, R Pt. Dr main on Mannho Rd from Relay 200 of C C, S, R Pt. Dr main on Mannho Rd from Relay 200 of C C, S, R Pt. Dr main on Mannho Rd from Relay 200 of C C, S, R Pt. Dr main on Mannho Rd from Relay 200 of C C, S, R Pt. Dr main on Mannho Rd from Relay 200 of C C, S, R Pt. Dr main on Mannho Rd from Relay 200 of C C, S, R Pt. Dr main on Mannho Rd from Relay 200 of C C, S, R Pt. Dr main on Mannho Rd from Relay 200 of C C, S R Pt. Dr main on Mannho Rd from Relay 200 of C C, S R Pt. Dr main on Mannho Rd from Relay 200 of C C, S R Pt. Dr main on Mannho Rd from C Rela R R D. Relay 200 of C C, S R R R R R R R D. Relay 200 of C C, S R R R R R R R R R R R R R R R R R R	402011-37628	Holly Ave, MNC	MANCHESTER		a	1,470		1,470	21	\$408,936	\$278.19
unmode hit Manmoch hit Manmoch hit Manmoch hit Cl 2,00 2,00 2,00 3 5786.38 5536.28 5536.28 02011-3762 Perky SL, CLD CDNCORD Rely 420° of E° C1 P with F° R. 17. Transfer all services. 0 400 400 400 400 400 400 400 400 5536.08 5536.08 5536.08 5536.08 5536.08 5536.08 5536.00	402011-37619	Lund St, NAS	NASHUA	Relay on Lund St from Nowell St to Lake St with 2" PL 60#. Relay on Brewster St from Lund St to Linwood St with 2" PL 60#. Tie over services and abandon	a	2,250	270	2,520	24	\$583,177	\$231.42
Image: state of the	402023-37628	Mammoth Rd	MANCHESTEP	Relay approximately 2320' of 6" CI, CS, & PL LP main on Mammoth Rd from	a	2 470		2 470	22	\$786 369	\$318.37
number Number Rely approx. 160° 07° 1560 PS00 main on Patts Ave from Carde B to patts Ave from Ave from Carde B to patts Ave from Ave from Carde B to patts Ave from Ave from Carde B to patts Ave from Carde B to patts Ave from Carde B to patts Ave from Carde B to patts Ave from Carde B to patts Ave from Carde B to patts Ave from Carde B to patts				Wayland Ave to #25 Mammoth Rd with 6" PL LP. Relay 420' of 8" CI LP with 8" PL LP. Transfer all services.	0				33		
Units Jack Math Are Model (Jack) Init Streams with new JP. (20 PSG main). ID Job				Relay approx 160' of 7" BS 60 DSIG main on Diate Austroam Condin 2011	-				6		
Later Toric North Max Later S North Max North Max D <thd< th=""> D <thd< th=""> D D D<td></td><td></td><td></td><td>#136 Platts with new 2" PL 60 PSIG main.</td><td></td><td></td><td></td><td></td><td>3</td><td></td><td>\$499.48</td></thd<></thd<>				#136 Platts with new 2" PL 60 PSIG main.					3		\$499.48
1988-376 nohury Sindge Effect prof to install, call sind Main opened by dy contract. 0 3 3 30 2 5113.55 5113.55 0001-3761 hussel Ave, NdS NdSHA helps approximately XD7 CD [151], 1501 on Road Ave from Main give work. 0 1.10	452011-37603	кiver st	KEENE	River St with 4" PL LP. Abandon 150' of 6" Cl and 150' of 8" Cl, replace with 8" PL under box culvert	u	425		425	8	\$85,302	\$200.71
02013-3761 kursel Ave, NAS NASHA Halvy approximately 76 ° ° ° ° ° ° ° ° ° ° ° ° ° ° ° ° ° °	431908-37601	Roxbury St Bridge	KEENE	prior to install. Cast Iron Main will be encrouched upon as part of city box culvert replacement. Hole to be opened by city contractor.	a	300	3	303	2	\$113,562	\$374.79
2011-3766 Indust 51 at McKney 51 VEDE Due to a varie config. (mg vapos 20° of "C UP main on mound 51 at M L Mondes") at M L Mondes 0 0 0 0 0 538,79 532,291 2011-3766 South 51 EEEE Relay approx. 700 of "C UP main on South 31 from Moundes 51 at M L Mondes") at M L Mondes 0 760 13 512,368 512,368 519,94 2011-3766 South 51 EEEE Relay approx. 700 of "C UP main on South 31 from Moundes 51 to Bales" 0 760 13 512,368 518,758 2011-3760 Inion 55, MNC MARCHETTS Relay out mound 51 to Been 51 with 2"P (40,06 to not disting 1" C 0) 0 900 900 900 938 5536,838 5538,588 2008-37601 Winchester 51 KEENE Exel on Union 51 with 2"P (40,06 to not disting 1" C 0) 0 1,46 6 5142,2001 2008-37601 Winchester 51 KEENE Exel on Union 51 with 2"P (50,60 0 0 1,46 6 5142,2001 2008-37601 Winchester 51 KEENE Exel on Union 51 with 3"P (50,60 0 1,46 6 5142,2001 2008-37601 Winchester 51 from Key M to Island 51 with 3"P (5,596,50 0 1,46 6 5142,2001 2008-37601 Winchester 51 from Key M to	402011-37621	Russell Ave, NAS	NASHUA	Relay approximately 785' 4" CI LP (1924) on Russell Ave from Main St to Fifield St with 2" PL 60# main. Relay approximately 300' 2" BS LP (1911, 1959)	CI	1,190		1,190	19	\$313,054	\$263.07
20211-2760 South S1 EEEE Relay approx. 700 of * C 10 main on South S1 from Moord#Ock 10 bears do main 0 760 760 13 5221,363 5519/45 20211-2760 Ioin S5, MNC Relay on Union S4 70, 100 min 74, 000, Relay on Union 27, 00	432011-37606	Russell St at McKinley St	KEENE	Due to a water conflict, relay approx. 30' of 4" CI LP main on Russell St at the intersection of McKinley St with new 4" PL LP	a	30		30	0	\$38,759	\$1,291.97
Add/CostTrain Relative out tools of non Hoyward State State With # 7 PL GB. Relay on Howard State Mark 2014 Add/CostTrain Relative out tools of non Hoyward State State With # 7 PL GB. Relay on Howard State Mark 2014 State	432011-37605	South St	KEENE	Relay approx. 760' of 4" CI LP main on South St from Monadnock St to Baker St with new 4" PL LP.	CI	760		760	13	\$121,368	\$159.69
Sacoba-37601 Winchester St. Date to road reconstruction, relay approx. 1,140° of 8° CS 590G main on Winchester St from Key M to Hand St with 9° PS 5936. O 1,140 1,140 6 5350.10 <td>402011-37610</td> <td>Union St, MNC</td> <td>MANCHESTER</td> <td>Relay on Union St from Hayward St to Silver St with 4" PL LP. Relay on Batchelder Ave from Hayward St to Harvard St with 2" PL 60#. Relay on Harvard St from Union St to Beech St with 2" PL 60#. Do not disturb 12" Cl</td> <td>a</td> <td>920</td> <td></td> <td>920</td> <td>38</td> <td>\$536,828</td> <td>\$583.51</td>	402011-37610	Union St, MNC	MANCHESTER	Relay on Union St from Hayward St to Silver St with 4" PL LP. Relay on Batchelder Ave from Hayward St to Harvard St with 2" PL 60#. Relay on Harvard St from Union St to Beech St with 2" PL 60#. Do not disturb 12" Cl	a	920		920	38	\$536,828	\$583.51
Average Cost/Foot Total All Materials 37,853 4,673 42,486 568 514,232,021 55135 Miles 7,26 0.89 8.05 514,232,021 55135 Total Primary Material ** 52,283 4,673 39,956 535 513,520,472 Miles 0.68 0.89 7,57 - - Total Primary Material *55* 1,085 0 1,085 21 543,280,65	432008-37601	Winchester St	KEENE	Due to road reconstruction, relay approx. 1,140' of 8" CS 5 PSIG main on	a	1,140		1,140	6	\$350,104	\$307.11
Miles 7.16 0.89 8.05 Total Primary Material "0" 35,283 4.673 39,556 533.520,473 Miles 0.89 7.57 Total Primary Material "0" 1.085 0 1.085 21 5412,806					otal All Materials	37,813	4,673	42,486	568	\$14,323,021	Average Cost/Foot \$513.93
Mile 6.68 0.89 7.57 Total Primary Material "55" 1.085 21 \$417,805					Miles		0.89	8.05			
				Total Prin						\$13,520,473	
Milee 0.22 0.00 0.21				Total Prim					21	\$417,806	
					Miles	0.21	0.00	0.21			

DG 20-049 RSK AttadExphiebrit 28 DG 20-049 Liberty CIBS Program June 12, 2020

CREW COUNT

13

CONTRACTOR



SOC CONTACT INFORMATION		COUNT PER INSPECTOR	DIVISION	CONTRACT	
PAUL ROGOSIENSKI - GAS OPERATIONS MANAGER	(603) 327-6140	0	SOUTH	6	MEARS
ANTHONY BELAND - SUPERVISOR SOUTH	(603) 589-3920	0	CENTRAL	5	MIDWAY
BURROWS - S	(407) 879-5430	2	NORTH	2	RHW
BROWNELL - S	(603) 765-1772	0			FEENEY
GALLANT - S	(774) 452-5528	3			TOTAL CREWS
STEVE ROKES - MANAGER KEENE	(603) 209-2582	0			
MCCORD - S	(413) 475-0008	1			
IAN CRABTREE - SUPERVISOR CENTRAL	(978) 758-3504	0			
SMART - C	(603) 765-1782	0			
RICARDO - C	(603) 777-7721	3			
ROUSSEAU - C	(603) 661-5675	2			
HEATH LYNCH - SUPERVISOR NORTH	(603) 327-4092	0			
PAYNE - N	(603) 231-6323	1			
BARNES - N	(203) 627-9608	0			
TINKER - N	(603) 630-3216	1			
TOTAL CREWS ASSIGNED AN INSPECTOR		13			

DIVISION	LU SPAN OF CONTROL	CREW LEADER	CELL	ADDRESS	TOWN	JOB/ PERMIT #	MAIN	SERVICE OTHER	CRITICAL TASK	CONTR. SUPER	CELL	CONTRACTOR
CENTRAL	RICARDO	Bruce Terrio	603-759-9587	253-309 Lake Av	MNC	402023-37603/115269		¥		Tom Cowaill	857-309-6657	FEENEY
CENTRAL	RICARDO	Dionne, Al	(978) 360-1973	1568 Hooksett Rd	HOK	402051-38001018		x		Bennett, Dan	(508) 889-0720	MIDWAY
CENTRAL	RICARDO	Justin Pearce	603-234-7331	Dubuque St	MNC	402011-37615	х	~		Mark Nelson	603-309-0890	RHW
CENTRAL	ROUSSEAU	Joel Decato	603-396-3065	Mammoth Rd	MNC	402023.3763	x			Mark Nelson	603-309-0890	RHW
CENTRAL	ROUSSEAU	Darrin Lahaye Jr	978-478-8236	166 Riverbank Rd	MNC	402050-38001056/116410		х		Tom Cowgill	857-309-6657	FEENEY
NORTH	PAYNE	Terrio, Dale	(978) 360-2388	S. State St	CCD	402011-37603	х			Bennett, Dan	(508) 889-0720	MIDWAY
NORTH	TINKER	Masse, Jason	(603) 913-6430	56 Dow Rd	BOW	402051-38001024		х		Bennett, Dan	(508) 889-0720	MIDWAY
SOUTH	BURROWS	McKenney, William	603-770-6076	Harvest Moon	LON	401747-37642	х			Ricardo, Dave	603-440-4138	MEARS
SOUTH	BURROWS	Xavien Lagoa	978-320-7271	11 Bridle Path	LON	401947-37686/n/a	х		TIE-IN	Beavan McNamara	857-309-6785	FEENEY
SOUTH	GALLANT	Enright, Dan	603-396-6587	Farley St Permit 19-490	NAS	402011-37626	х			Ricardo, Dave	603-440-4138	MEARS
SOUTH	GALLANT	Joe Sarette	603-210-3014	49 Hunt St	NAS	401950-38001302		х		Gene Allen	603-396-2872	RHW
SOUTH	GALLANT	Joe Paddock	978-968-4185	89 West Hollis St	NAS	402050-38001057/20-255		х		Beavan McNamara	857-309-6785	FEENEY
SOUTH	MCCORD	Shawn James	603-234-0654	Roxbury St Bridge	KNE	431908-37601	х		CUT & CAP	Gene Allen	603-396-2871	RHW

DG 20-049 Exhibit 2

DG 20-049 RSK Attachment 9

STATE OF NEW HAMPSHIRE

Inter-Department Communication

DATE: June 16, 2020 **AT (OFFICE):** NHPUC

FROM:	Anthony Leone, Utility Analyst
SUBJECT:	Liberty Utilities (EnergyNorth Natural Gas) Corp. FY 2020 CIBS Replacement Program- DG 20-049 Fiscal Year 2020- April 1, 2019 – March 31, 2020 FINAL Audit Report
TO:	Steve Frink, Director, Gas/Water Division NHPUC Randy Knepper, Director, Safety Division NHPUC Jayson Laflamme, Assistant Director, Gas/Water Division NHPUC Iqbal Al-Azad, Utilities Analyst IV Gas/Water Division NHPUC

Introduction

Liberty Utilities (EnergyNorth Natural Gas) Corp. (Liberty or Company) filed its Fiscal Year (FY) 2020 Cast Iron/Bare Steel (CIBS) program results (April 1, 2019 through March 31, 2020) with the Commission on April 15, 2020 filed as Docket No. DG 20-049. These results and the subsequent request for recovery are filed pursuant to the settlement agreement in Order No. 25,370 (May 30, 2012) in Docket No. DG 11-040.

The costs associated with the FY 2020 CIBS program were reviewed and below is a summary of those costs from the RAM/BRF-1 & 2 Attachments. Specifically, the Company is requesting a \$1,612,633 increase in the annual revenue requirement based upon \$14,885,260 of eligible costs which included FY 2019 carryover costs at the maximum 5% of estimated FY 2020 costs.

FY 2020 Costs (Col. BE, line 51)	\$ 14,503,496
FY 2019 Carryover Costs @ 5% (RAM/BRF-1)	<u>\$ 930,987</u>
FY 2020 Sub-total Recoverable Costs	\$ 15,434,483
FY 2020 Adjusted CIBS Base Investment	<u>\$ (549,222)</u>
Total Recoverable Costs for FY 2020	\$ 14,885,260

Estimated Costs vs. Actual Costs

The FY 2020 estimated and actual loaded costs are compared in Column "BM" in Attachment A of Attachment RAM/BRF-2. An excel version of this schedule was provided for this audit to which the cost variance formula found was reviewed for accuracy and completeness. As indicated one Bates page 8 of the testimony of Mostone & Frost, the FY 2020 CIBS program anticipated 39 projects resulting in approximately 12.68 miles of cast iron/ bare steel main replaced or abandoned. The testimony further indicated the final amount was 29 projects completed in their entirety, 7 projects started but had reduced scopes, and 3 projects were deferred entirely. This resulted in 11.13 miles of cast iron/ bare steel main replaced or abandoned.

As indicated in Attachment A of Attachment RAM/BRF-2, the cost variance for the FY 2020 CIBS Program includes the original estimated cost for all projects, even those with reduced scopes. Therefore, the cost variances for the projects, which impact the overall program cost variance may not be accurately represented. In the absence of an approved method to reflect the cost variance of projects with reduced scopes and their impact to the overall cost variance, the analyst has prepared a chart comparing the cost variances per Division as found in Attachment A of Attachment RAM/BRF-2 and a recalculation removing, in their entirety, those projects that had reduced scopes. It is important to note that if and when these projects are completed, the overall cost may be under, at, or over budget.

	Northern	Central	Southern	Overall
Filed	+38%	+15%	+5%	+15%
Recalculated	+39%	+36%	+16%	+28%

Recoverable Costs - Work Order Review

Liberty provided the FY 2020 CIBS Program data, including estimated and actual costs, covering all 39 approved projects. The data was sent as Microsoft Excel spreadsheet (sheets) versions of Attachment RAM/BRF-2 and DBS/CAM-1 and CAM-2. The sheets provided work order numbers, locations, direct main and service costs as well as indirect/ loaded cost totals.¹ The loaded costs as identified on the sheets were comprised of items including benefits, overhead, and other indirect costs. The sheets also provided a short note describing any variance between the estimated and the final costs.

In addition, Liberty provided supporting data for each of the 6 projects chosen to review in depth for this report. Supporting data included detailed cost sheets for each project, the general ledger accounts where the costs were booked, what the cost was for, and when it was incurred. All of the initial supporting data reviewed indicated the costs were properly booked to at least Account #107-Construction Work In Progress ("CWIP") and as explained later, a sample was verified to be booked to Account #106- Completed Construction but Not Classified as of March 31, 2020, as required by the CIBS program rules. The posting of completed CIBS jobs to

¹ The term "Loaded Cost" refers to the sum of the direct charges (outside contractors, materials, police, flaggers, etc.) and indirect charges (benefits, overheads, back office, burdens, etc.).

Account #106 was reviewed in the prior audit and again verified in the current audit with no exceptions found.

The sheets provided for this review separated the costs of each work order by cost element which could then be grouped as main costs, service costs, direct costs or indirect costs. These totals were then traced to amounts in the RAM/BRF-2 schedule which tie out to the filing. The Analyst found no issues with verifying the data from the sheets to the schedule to the filing.

The CIBS program allows for the recovery of costs as long as the following requirements are met: The unprotected bare steel main replacement as determined by evaluation and selection process; cast iron main replacement as determined by evaluation and selection process; cast iron or bare steel main replacement requested by field operation personnel; and finally, bare steel services replaced as a result of a segment of bare steel main or cast iron main that is selected.

The following are not allowable recovery costs under the CIBS program: The costs of moving inside meters to the outside, costs of reconnecting existing plastic services or existing coated steel services from cast iron mains or bare steel mains to newly installed replacement main, costs of main replaced made of polyethylene or steel that have protective coating, mains that are abandoned, incremental costs of upsizing with exceptions unless approved by the Safety Division, costs of coated steel that act as bare steel mains such as poorly coated steel mains or disbanded steel mains unless approved by Safety Division, and carryover costs in aggregate exceeding 5% of the approved estimated total expenditures under the CIBS program for the construction year unless approved by the Safety Division. The carryover costs include items such as restoration costs not included during the construction year.

Degradation Fees

In June 2017, the New Hampshire State Supreme Court ruled that Manchester and other municipalities can charge fees to companies who dig up city streets to reach buried utility lines. According to Column AS of the RAM/BRF-2 file provided for this audit, the total degradation fees charged to Liberty in FY 2020 as a result of the CIBS Projects were:

Northern Division (Concord & Laconia areas)	\$158	3,097
Central Division (Manchester & Goffstown areas)	\$ 28	8,655
Southern Division (Nashua, Keene & Hudson areas)	\$	0
	\$186	5,752

In the prior audit, it was explained that the City of Manchester did not bill the Company for the full amount of degradation fees that were calculated as being due. Accordingly, Liberty did <u>not</u> include those estimated degradation fees in the requested recovery amount. Those fees would therefore be eligible as "carry-over" costs which for which recovery in FY 2020 is limited to 5% unless specific approval is requested and received. According to the Notes column of Attachment A of RAM/BRF-2 there were a number of restoration costs for which the Company had yet to be billed by the City of Manchester.

For FY 2020, Liberty again excluded the estimated degradation fees of \$876,840 (col. W) from the requested recovery amount, including only the actual, billed amount of \$28,655. The remaining estimated amount of unbilled degradation fees from the City of Manchester would therefore be \$848,185.

Also explained in the prior audit report, the Company provided the FY 2019 Degradation Fee rates and calculation methods for Concord and Manchester. The Company explained that Concord bills on the size of the trench, typically 2 or 3 feet wide. Whereas Manchester also includes a 2 foot area on either side of the trench where applicable. Therefore, each linear foot of replaced main or service that costs approximately \$15 in Concord, could cost up to approximately \$35 in Manchester. The City of Nashua does not currently charge degradation fees.

Northern Division 8 Planned / 6 Completed / 1 with Reduced Scope / 1 Project Deferred

As detailed in the RAM/BRF-2 file provided for this review, the actual loaded cost for the Northern Division projects was \$3,543,939 (Col AY). This figure represents recoverable main and service charges of \$2,851,680 (col. BE), non-recoverable costs of \$692,259 (cols. BA+BB). This figure does NOT include the estimated, loaded, carryover costs of \$562,769 (col. BG) as those costs are neither in the recovery amount requested by the Company nor have they been incurred. The RAM/BRF-2 file provided for the review includes notes explaining the variances and lists such causes as: daily permit time restrictions, removal of steam pipes, ledge, extra depth, and installation greater than estimated.

W/O #401711-37605, 8-42 Center Street, Concord \$616,882

(Col. AT)	(Col. AU)	(Col. AY-AV)	(Col. BA+BB)	(Col.BE)	(Col.BG)
Direct	Direct	Indirect	Non-	Total	Estimated
<u>Main</u>	Service	<u>Costs</u>	Recoverable	<u>Recoverable</u>	<u>Carryover</u>
\$495,722	\$78,702	\$132,695	(\$90,237)	\$616,882	\$119,359

The Company provided a detailed work order report as well as other details from the fixed asset system, Wennsoft. The system breaks out projects by Division (Northern for the Concord area, Central for the Manchester area, and Southern for the Nashua area) then by "Parent" work order. Each parent work order can have multiple "Child" work orders that are associated with that specific job. Each child work order uses the parents' work order *#* and affixes a number on the end usually starting with "001". Each child work order usually represents the work done on service line replacements. An example of a parent and associated child work orders have been included below for reference:

Center Street Main Replacement Work Order # 401711-37605 Center Street Services Replacement #1 Work Order # 401711-37605-001 Center Street Services Replacement #2 Work Order # 401711-37605-002

The Company also presented a Capital Expenditure report listing the direct main and direct service charges as well as any charges that were determined to be non-recoverable as agreed upon in the CIBS Program Guidelines. These reports were in the form of Excel

spreadsheets. The spreadsheets and the costs listed were reconciled to the RAM/BRF-2 Attachment of the Filing total of \$14,503,496 (col. BE, Line 51).

This particular work order contained non-recoverable charges. Specifically, the Company indicated 110 feet of new main pipe was non-recoverable. To determine the cost that is non-recoverable the Company divided the actual main cost with degradation fees by the actual footage of main installed, or \$633,823 / 2,448 feet. The result, \$258.91 per foot, is then multiplied by the 110 feet of new main to arrive at the non-recoverable total of \$28,481 (Col. AH, Line 3).

Lastly, the Analyst reviewed multiple invoices for this work order. These included for the contractor, Midway Utility Contractors, inspection fees from the City of Concord, easement charges, flaggers, police details and county registry. The analyst noted no exceptions while reviewing the invoices.

W/O #401911-37609, 206-320 Messer St, Laconia \$17,943
--

(Col. AT)	(Col. AU)	(Col. AY-AV)	(Col. BA+BB)	(Col.BE)	(Col.BG)
Direct	Direct	Indirect	Non-	Total	Estimated
<u>Main</u>	<u>Service</u>	<u>Costs</u>	<u>Recoverable</u>	Recoverable	<u>Carryover</u>
\$0	\$37,025	\$8,944	(\$28,027)	\$17,943	\$0

The Company provided a detailed Work Order report as well as other details from the fixed asset system, Wennsoft. The Company also provided a breakdown of the Capital Expenditures listing the direct main and direct service charges as well as any charges that were determined to be non-recoverable as agreed upon in the CIBS Program Guidelines as described in the first work order reviewed. These reports were in the form of Excel files. The Analyst reviewed the files and the costs and reconciled them to RAM/BRF-2 total of \$14,503,496 (col. BE, Line 51).

The RAM/BRF-2 sheet detailed that this specific work order eliminated the last of the CIBS mains in Laconia. Further, that total was 1,360 feet of CIBS that was abandoned. The Company also indicated the 7 services were tied over. The Company further indicated that of a portion of the 7 services were not recoverable through the CIBS program due to being new, existing plastic or coated steel. Direct and Indirect Costs, including non-recoverable costs and the new services, as found in the General Ledger, consisted of the following:

Direct Main and Service Costs		Indirect Main and Service Costs		
Labor	\$ 0	Burdens	\$ 13,104	
Materials	\$ 0	Cost of Removal	\$ (4,160)	
Vouchers	\$ <u>37,025</u>	AFUDC	<u>\$0</u>	
	\$37,025		\$ 8,944	

Lastly, the Analyst reviewed multiple invoices for this work order. These included for the contractor, Midway Utility Contractors, restotation fees from the City of Laconia, a crossing fee to the NHDOT, and fees from JDH Inspection Services. The analyst noted no exceptions while reviewing the invoices.

Central Division 16 Projects Approved / 12 Projects Completed / 4 with Scope Reduced

As detailed in the RAM/BRF-2 file provided for this review, the actual loaded cost for the Central Division projects was \$7,537,275 (Col AY). This figure represents recoverable main and service charges of \$6,208,963 (col. BE), non-recoverable costs of \$1,328,312 (cols. BA+BB). This figure does NOT include the estimated, loaded, carryover costs of \$1,733,955 (col. BG) as those costs are neither in the recovery amount requested by the Company nor have they been incurred. The RAM/BRF-2 file provided for the review includes notes explaining the variances and lists such causes as: daily permit time restrictions, removal of steam pipes, ledge, extra depth, and installation greater than estimated.

W/O #401911-37613, 123-396 Smyth Rd. Manchester \$104,544

(Col. AT)	(Col. AU)	(Col. AY-AV)	(Col. BA+BB)	(Col.BE)	(Col.BG)
Direct	Direct	Indirect	Non-	Total	Estimated
<u>Main</u>	<u>Service</u>	<u>Costs</u>	<u>Recoverable</u>	<u>Recoverable</u>	<u>Carryover</u>
\$106,387	\$60,788	(\$36,455)	(\$26,186)	\$104,544	\$-0-

The Company provided a detailed Work Order report as well as other details from the fixed asset system, Wennsoft. The Company also provided a breakdown of the Capital Expenditures listing the direct main and direct service charges as well as any charges that were determined to be non-recoverable as agreed upon in the CIBS Program Guidelines as described earlier. These reports were in the form of Excel spreadsheets. The Analyst reviewed the spreadsheets and the costs listed and reconciled them to the \$14,503,496 (col. BE, Line 51).

The non-recoverable total of (\$26,186) was comprised of (\$9,077) in coated steel and plastic relay and the laying of main beyond what is being replaced, which is not allowed to be recovered within the CIBS and (\$17,110) of non-recoverable services costs as they met the program guidelines for being non-recoverable. The method to calculate the cost of the new main was the same as reviewed in before, the total cost for the mains is divided by the total feet installed then multiplied by the additional feet.

\$71,932 (Col. AW) divided by 317 feet (Col. AG) = \$226.91 per foot \$226.961 multiplied by 40 feet = \$9,077 of new main not-recoverable through CIBS

Regarding the net negative indirect costs of (\$36,455), the Company explained that this job appears to have incurred net negative burden/ Overhead (OH) charges simply due timing. More specifically, to the timing of reversing the accrued (estimated) invoices that had been posted to the job, the posting of the actual invoices and the charging of burden/ OH to the job which are calculated using the actual invoices and only posted the following month.

Specifically, the Company explained that as a policy, burden/ OH charges are calculated and charged in the month following the month of the charges for which the calculation is based upon. For example, April burden/ OH charges for Job #123 are calculated from contractor invoices received and posted to Job #123 in March. In this specific instance, the Company was unable to secure and post the actual invoices from the contractor/ vendor until March of 2020, and therefore the actual burdens/ OH were not calculated and charged until April 2020. April

2020, is after the March 31 cut-off date for inclusion in the current CIBS Fiscal Year and therefore the Company did not include the approximately \$26,000 that the job actually incurred. The posting of accrued (estimated) entries to a job is a common accounting procedure for properly capturing and recording costs in the correct time period which have been incurred but not yet billed for, and for Liberty, is also used to allocate burden/OH charges throughout the life of the projects that take months to complete. The Analyst has no issues with the posting of accrued entries to record estimated costs as it is a common accounting procedure.

The Direct and Indirect Costs, including non-recoverable costs and the new services, as found in the GL as of March 31, 2020, consisted of the following:

Direct Main and Service Costs		Indirect Main and Service Costs		
Labor	\$ 1,383			
Materials	\$ 2,337	Burdens	\$ (26,076)	
Vouchers	\$134,574	Cost of Removal	\$ (11,387)	
Accrued V.	<u>\$ 28,882</u>	AFUDC	\$ <u>1,018</u>	
	\$167,175		\$ (36,445)	

Lastly, the Analyst reviewed multiple invoices for this work order. These included for the contractor, Midway Utility Contractors, inspection fees from the City of Manchester, police detail charges, and fees from JDH Inspection Services. The analyst noted no exceptions while reviewing the invoices.

<u>W/O #40191</u> 1	<u>1-37624, 555-6</u>	09 South Beecl	h St. Manchester	<u>\$94,548</u>	
(Col. AT) Direct	(Col. AU) Direct	(Col. AY-AV) Indirect	(Col. BA+BB) Non-	(Col.BE) Total	(Col.BG) Estimated
Main	Service	Costs	Recoverable	Recoverable	Carryover
\$103,078	\$23,368	(\$18,528)	(\$13,370)	\$94,548	\$61,098

The Company provided a detailed Work Order report as well as other details from the fixed asset system, Wennsoft. The Company also provided a breakdown of the Capital Expenditures listing the direct main and direct service charges as well as any charges that were determined to be non-recoverable as agreed upon in the CIBS Program Guidelines as described in the first work order reviewed. These reports were in the form of Excel spreadsheets. The Analyst reviewed the spreadsheets and the costs listed and reconciled them to the \$14,503,496 (col. BE, Line 51).

The non-recoverable main total of \$325 is comprised of 30 feet of main that was upsized. This differential is important due to the program guidelines not allowing for recovery through the CIBS of upgrading a 4-inch pipe a 6-inch pipe unless specifically designated by the Safety Director of the PUC. For FY 2020, this cost was calculated at \$10.84 per foot. The Company indicated the method of determining the cost of upsized pipe as: Each year for the CIBS program Liberty Utilities calculates the average project installed footage length for completed projects in the CIBS program. In FY 2020, Liberty indicated this was 1,548 feet. The company then places this average installed project length in the company's estimating tool to compare the cost difference of installing 4 inch and 6 inch pipe sizes. Paving and gas service costs are identical

regardless of pipe size therefore those factors are not included in the cost difference calculation. Specifically, based upon the above method, Liberty indicated that the average cost per foot is \$63.73 and \$74.57 for 4 inch and 6 inch pipes respectively.

Lastly, the Analyst reviewed multiple invoices for this work order. These included for the contractor, Midway Utility Contractors, inspection fees from the City of Manchester, police detail charges, and fees from JDH Inspection Services. The analyst noted no exceptions while reviewing the invoices.

Southern Division 15 Projects Approved / 11 Projects Completed / 2 with Scope Reduced / 2 Projects Deferred

As detailed in the RAM/BRF-2 file provided for this review, the actual loaded cost for the Southern Division projects was \$6,954,314 (Col AY). This figure represents recoverable main and service charges of \$5,442,853 (col. BE), non-recoverable costs of \$1,328,312 (cols. BA+BB). This figure does NOT include the estimated, loaded, carryover costs of \$1,511,461 (col. BG) as those costs are neither in the recovery amount requested by the Company nor have they been incurred. The RAM/BRF-2 file provided for the review includes notes explaining the variances and lists such causes as: daily permit time restrictions, removal of steam pipes, ledge, extra depth, and installation greater than estimated.

W/O #401911-37601, Baker St, Highland Ave. Nashua \$214,571

(Col. AT)	(Col. AU)	(Col. AY-AV)	(Col. BA+BB)	(Col.BE)	(Col.BG)
Direct	Direct	Indirect	Non-	Total	Estimated
<u>Main</u>	<u>Service</u>	<u>Costs</u>	<u>Recoverable</u>	Recoverable	<u>Carryover</u>
\$329,042	\$131,158	\$65,466	(\$311,094)	\$214,571	\$ -0-

The Company provided a detailed Work Order report as well as other details from the fixed asset system, Wennsoft. The Company also provided a breakdown of the Capital Expenditures listing the direct main and direct service charges as well as any charges that were determined to be non-recoverable as agreed upon in the CIBS Program Guidelines as described in the first work order reviewed. These reports were in the form of Excel spreadsheets. The Analyst reviewed the spreadsheets and the costs listed and reconciled them to the \$14,503,496 (col. BE, Line 51).

The non-recoverable total of \$311,094 was comprised of \$189,137 of main costs and \$121,957 in services costs, which the Analyst verified using supporting data, which backed up the RAM/BRF-2 attachment. The Direct and Indirect Costs, as found in the provided General Ledger, consisted of the following:

Lastly, the Analyst reviewed multiple invoices for this work order. These included for the contractor, Mears Construction. Mears also appeared to provide various other services including construction materials such as gravel and other specialized earth materials, inspection fees, police detail charges, and fees from JDH Inspection Services. The analyst noted no exceptions while reviewing the invoices.

Overhead

The total overhead (OH) incurred in FY 2020 was \$7,274,933. This total was spread over all of the FY 2020 and jobs according to Liberty's accounting policy. The Analyst has included the total OH figures since the 2016 FY below:

Туре	2016	2017	2018	2019	2020
Pension	\$659,922	\$1,217,387	\$1,392,396	\$1,504,931	\$542,585
Benefits	\$691,386	\$305,910	\$669,772	\$846,579	\$1,695,448
Payroll Taxes	\$357,020	\$463,855	\$538,518	\$594,328	\$632,697
Other	\$2,810,000	\$3,385,272	\$3,007,551	\$2,941,980	\$4,404,203
Total	\$4,518,335	\$5,372,424	\$5,608,237	\$5,887,817	\$7,274,933
% growth in OI					
from previous F	Y:	19%	4.2%	4.7%	23%

Liberty describes the "Pension" category as all pension expenses and post-employment benefits. The "Benefits" category as described by Liberty consists of costs for employee health, life and disability. "Payroll Taxes" covered Liberty's portion of the FICA, Medicare, FUTA and SUTA; and the "Other" category as charges for rent, utilities, back office, company insurance, incentive awards, time not worked and a percentage of corporate allocations.

The total amount of OH sought for recovery through the CIBS program should exclude OH applied to the portions of the jobs that are deemed unrecoverable per the program guidelines. From the jobs reviewed, the total amount of OH sought for recovery through the CIBS program did in fact exclude those portions of OH applied to the portions of each job that were deemed unrecoverable. Accordingly, relative to the files reviewed, most of the services costs, which include OH allocations as seen by the Analyst in the detail of expenses for each job, are <u>not</u> allowed for recovery through the CIBS Program, and therefore not all of the \$7,274,933 of incurred OH is included for recovery in the instant Docket.

Cost of Removal

The Analyst reviewed the Cost of Removal amounts found within the supporting materials sent by Liberty including the work order detail reports and supporting journal entries. The amount was 10% of the eligible original cost of each work order. A standard 10% Cost of Removal (COR) charge can also be found in use by other public utilities in the State of NH. The reason for using 10% is that most contractors may not separate the cost of removing the old pipe, main or service, from the overall cost of a project and therefore a typical amount of 10% has been used in numerous filings over many years. Accounting for the COR typically involves a Debit to Accumulated Depreciation and a Credit to Plant in Service for the same amounts.

Fiscal Year 2019 Carryover Projects

According to Bates page 10 of the testimony of Mostone & Frost, the total FY 2019 costs incurred in FY 2020 (carryover costs) were \$4,220,128. According to the FY 2019 CIBS Audit Report and testimony in DG 19-054 (FY 2019 CIBS program results), the estimated costs were

\$3,698,261, approximately 3%, or \$104,940, less than actual. As the carryover costs represent estimated and unknown amounts, a variance is most likely to occur from the final, known costs. According to the RAM/BRF-2 attachment, the carryover costs were for final paving restoration work and may be billed by third-party contractors/ vendors which is different than a Town or City who would bill for the degradation fee.

As stipulated in the CIBS Program Guidelines as originally agreed to in Docket DG 11-040, unless recommended by the Director of the (Gas) Safety Division of the PUC, the amount of costs carried over from one FY to a subsequent FY shall not exceed 5% of the approved budget for that subsequent FY. Liberty's FY 2020 CIBS filing indicates the Company is not requesting more than the 5% cap in the instant docket for recovery.

General Ledger Review

The Analyst was supplied with general ledger (GL) information covering a wide selection of projects. Specifically, the Analyst reviewed the entry that moves projects from Account #107-Construction Work in Process (CWIP) to either Account 106-Plant in Service but not Classified or the actual Plant accounts such as 3760-Distribution Mains.

This journal entry detailed below records the posting of several jobs, neither just CIBS nor the sample of CIBS reviewed for this report. With the entry below, Liberty forwarded a detailed breakdown of the specific entries, by work order, that makes up the \$29,712,077 total. Using this detailed report, the Analyst traced the recoverable amount for work order #401911-37613 of \$104,544 and the recoverable amount for work order #401911-37631 of \$176,160 to the detailed breakdown of this journal entry therefore verifying that at least the sample reviewed was no longer in CWIP.

Journal Entry	1,354,842 Posted	on 4/5/2020 as of 3/31/2020
----------------------	------------------	-----------------------------

Account # / Name	Debit	Credit
8840-2-0000-10-1618-1070	CWIP	\$29,712,077
8840-2-0000-80-1655-1080	Acc. Prov. For Dep. ²	\$ 410,384
8840-2-0000-10-1615-1060	Plant in Service	
	but not Classified	\$29,712,077
8840-2-0000-80-8610-4030	Depreciation Expense	\$ 410,384

Report Summary

In summary, the Analyst reviewed work orders, supporting documents, invoices, journal entries, excel spreadsheets of the FY 2020 CIBS Program and any other necessary supporting documentation, which accordingly, appear to substantiate the information presented in the Company's Filing.

² Accumulated Provision for Depreciation of Utility Plant

Executive.Director@puc.nh.gov

al-azad.iqbal@puc.nh.gov

amanda.noonan@puc.nh.gov

brian.frost@libertyutilities.com

catherine.mcnamara@libertyutilities.com

Christa.Shute@oca.nh.gov

david.simek@libertyutilities.com

jayson.laflamme@puc.nh.gov

karen.sinville@libertyutilities.com

lynn.fabrizio@puc.nh.gov

maureen.karpf@libertyutilities.com

michael.sheehan@libertyutilities.com

ocalitigation@oca.nh.gov

pradip.chattopadhyay@oca.nh.gov

randy.knepper@puc.nh.gov

Robert.Mostone@LibertyUtilities.com

steve.frink@puc.nh.gov

steven.mullen@libertyutilities.com