



Annual Reliability Report

2022 Report to the NH Public Utilities Commission

March 1, 2023

Table of Contents

| | |
|--|----|
| Executive Summary | 2 |
| Distribution System Reliability | 4 |
| Section 1.1 SAIFI (frequency), SAIDI (minutes), CAIDI (minutes), CIII (# of customers) – Distribution System Only – IEEE Criteria | 7 |
| Section 1.2 CAIFI (frequency), CTAIDI (hours) – Distribution System Only – IEEE Criteria | 8 |
| Section 1.3 SAIFI, SAIDI, CAIDI, CIII – Distribution System – Tree Related – IEEE Criteria | 8 |
| Section 1.4 SAIFI, SAIDI, CAIDI, CIII – Distribution (excluding Substation) Equipment Failures – IEEE Criteria | 9 |
| Section 1.5 SAIFI, SAIDI, CAIDI, CIII – Distribution Substation Equipment Failures - IEEE Criteria | 10 |
| Section 1.6 SAIDI (IEEE MED) – Storm MED; Equipment Failure MED- Total System | 12 |
| Section 1.7 SAIDI and SAIFI by Cause – Total System - IEEE Criteria | 13 |
| O&M Activity Summary | 18 |
| Section 2.1 Pole Inspections | 19 |
| Section 2.2 National Electrical Safety Code (NESC) Repairs | 19 |
| Section 2.3 Underground Circuit Inspections | 20 |
| Section 2.4 Overhead Circuit Patrols | 20 |
| Section 2.4(a) ROW Patrols | 22 |
| Section 2.4(b) Roadside Circuit Patrols | 23 |
| Capital Activity Summary | 28 |
| 2022 Projects | 33 |
| A22C01 Manchester Network Cable Replacement (Phase 2) - Under Construction | 33 |
| Worst Performing Circuit Lists | 40 |

Eversource

2022 Reliability Report

Executive Summary

Executive Summary

This report has been prepared in accordance with the terms of the October 9, 2020 Settlement Agreement approved by the New Hampshire Public Utilities Commission ("Commission" or "PUC") in Docket No. DE 19-057 (the "Settlement Agreement") including Appendix 4 of the Settlement Agreement. It provides information on Public Service Company of New Hampshire d/b/a Eversource Energy's ("Eversource" or the "Company") distribution system reliability and activities undertaken by the Company in calendar year 2022 focused on reliability.

Section 1 provides graphs of various reliability indices as specified in Appendix 4 of the Settlement Agreement. All graphs are based on IEEE reporting criteria, which was adopted by the NH Public Utilities Commission in 2014.

Section 2 provides a summary of specific operations and maintenance ("O&M") activities undertaken in 2022 which are generally targeted at maintaining or improving reliability. These activities include patrols of overhead distribution lines, inspections of underground developments and padmounted equipment, inspections of wood distribution poles for decay, and repairs of non-capital items on distribution lines related to the National Electrical Safety Code.

Section 3 provides information on capital projects targeting reliability, with information on the replacement of wooden distribution poles found to be defective through inspection, replacement of direct buried underground cable with new cable in conduit, and other capital reliability projects with spending greater than \$100,000 in the calendar year. This last category is further broken down into new projects initiated in 2022, and projects with spending in 2022 over the threshold but which were established in prior years. Projects established in 2022 also have project descriptions included. Projects included in Section 3 include any locations where reliability was listed as an objective of the project, even if the project had other justifications such as replacing obsolete assets or safety concerns. Spending in 2022 on defective pole replacements totaled \$1.38M. Spending on two projects replacing direct buried cable totaled \$550K. Spending on new reliability projects totaled \$22.836M, and on continued projects from prior years amounted to \$26.142M.

Section 4 contains the Company's annual report on the 50 worst performing circuits for the previous year.

The Company's reliability has improved over time, with reductions in the overall frequency of outages (SAIFI), the duration of outages (SAIDI), and the number of customers impacted when outages do occur (CIII). Improvements in SAIFI and CIII have led to a general increase in CAIDI. Summary charts are provided in Section 1.1.

Preventing outages from occurring and reducing the number of customers impacted by those outages are methods to improve SAIFI and CIII. Company work in areas such as tree trimming, the installation of covered wire, pole top distribution automation, and TripSavers, as well as other activities have resulted in the improvements shown. The increasing penetration of pole top distribution automation has the unfortunate impact of resulting in a general increase in CAIDI, as more customers are restored in under five minutes and the remaining customers are subject to the full duration of the outages that require lineworkers to effect repairs. Company initiatives to reduce CAIDI include expanding the regions of the state with troubleshooters to provide 24 hour coverage, utilizing the System Operations Center to manage the distribution system at voltages below 34.5 kV, adding SCADA control to lower voltage substations, and continued penetration of pole top Distribution Automation which can help identify a fault location while crews are en route to the outage.

Section 1

Distribution System Reliability

The following is a brief description of the reliability graphs contained in this section. All graphs represent data for the time frame 2018 through 2022 and reflect IEEE criteria, adopted by the NHPUC in the second quarter of 2014.

Section 1.1 shows Eversource NH SAIFI, CAIDI, SAIDI, and CIII. All graphs are based on IEEE criteria. The Company SAIFI and SAIDI have shown much improvement since 2018; 2022 was the best year for SAIDI since 1996. SAIDI performance of 79 in 2022 is comparable to 1991 and 1992, which have been the best years since at least 1989. 2019 was the first year since 1993 that SAIDI has been under 100 and it has stayed below 100 through 2022.

Eversource tracks metrics on minor storm days that are not defined by the PUC major storms (IEEE Major Exclusion Days ("MEDs")). The impact of minor storms is included in all presented data. Eversource experienced a total of 38 minor storm days in 2022 compared to 47 in 2021, 37 in 2020, 23 in 2019, and 28 in 2018. The impacts of these storms are included in the reported statistics. These storms contributed 40 minutes to Eversource's SAIDI performance in 2022, compared to 51 minutes in 2021, 47 minutes in 2020, 27 minutes in 2019, and 47 minutes in 2018.¹

Section 1.2 depicts CAIFI and CTAIDI over the 2018 through 2022 timeframe. These new indices have only been reported on since 2020. CAIFI is designed to show trends in customers interrupted and shows the number of customers affected out of the whole customer base. It is calculated by dividing the total number of customer interruptions by the number of distinct customers interrupted. CTAIDI is the average total duration of interruption for customers who had at least one interruption during the period of analysis and is calculated by dividing the total number of customer minutes of interruptions in the period by the number of distinct customers interrupted. Therefore, both CAIFI and CTAIDI indices refer only to customers who have experienced a service interruption in the period. For 2018 through 2022, CAIFI was in the range of 1.68 to 2.02 and CTAIDI has been in the range of 3.13 to 3.8 with 2022 reflecting roughly the average for the 5 year period.

Section 1.3 depicts Eversource tree related statistics. The largest cause group for outages is trees and limbs, primarily from outside of the clearance area, therefore all four indices closely follow the total distribution system indices shown in Section 1.1. More than half of all tree related outages included in the reporting metrics occur during minor storm events and, therefore, tend to be longer duration outages. SAIDI, SAIFI and CIII showed improvement in 2022 compared to 2021, with CAIDI showing an uptick due to tree related outages during minor storms.

Section 1.4 shows Eversource equipment related statistics on the distribution system. These statistics exclude substation equipment, which are presented separately in the Section 1.5. Equipment failures were between the second and fourth leading cause contributors for SAIDI and SAIFI over the presented time frame. SAIFI, SAIDI and CIII all showed a downward trend over the reporting period.


Section 1.5 shows results for distribution substation equipment failures. Power outages caused by equipment failures inside substations typically affect many customers and can be long in duration. That said, the reliability impact from substation outages has been minimal over the presented time frame. There was no equipment failure event in 2022, compared to one in 2021, one in 2020, three in 2019 and one in 2018.

Section 1.6 shows Total SAIDI and Equipment Failure SAIDI that occurred during IEEE MEDs. The reliability impact of these major storms is not included in Eversource statistics presented elsewhere.


¹ Please note that the minor storm data presented in this 2022 Reliability Report differs from the minor storm data presented in the 2021 Reliability Report filed in Docket DE 22-010. The Company discovered an inadvertent error with the data presented in the 2021 Reliability Report while compiling this 2022 Reliability Report. The data presented here is correct.

Section 1.7 shows SAIDI and SAIFI broken down by cause for each year 2018 through 2022. Tree related outages are the top driver of both statistics for the entire period, averaging 57 SAIDI minutes per year over the reporting period. Second, third and fourth places include Equipment Related, Action By Others and Other related outages. Outages due to equipment related causes averaged 10 SAIDI minutes per year. Action by Others, which includes causes such as motor vehicle accidents, customers and contractors digging into underground cables or felling trees on lines or vandalism, etc., averaged 10 SAIDI minutes per year. The "Other" category includes Public Safety Intentional Outages, Load Shedding, Planned Interruptions and Miscellaneous and averaged 12 SAIDI minutes per year over the reporting period.


Section 1.1 SAIFI (frequency), SAIDI (minutes), CAIDI (minutes), CIII (# of customers) – Distribution System Only – IEEE Criteria




Section 1.2 CAIFI (frequency), CTAIDI (hours) – Distribution System Only – IEEE Criteria




Section 1.3 SAIFI, SAIDI, CAIDI, CIII – Distribution System – Tree Related – IEEE Criteria





Section 1.4 SAIFI, SAIDI, CAIDI, CIII – Distribution (excluding Substation) Equipment Failures – IEEE Criteria



Section 1.5 SAIFI, SAIDI, CAIDI, CIII – Distribution Substation Equipment Failures - IEEE Criteria




Section 1.6 SAIDI (IEEE MED) – Storm MED; Equipment Failure MED- Total System



Section 1.7 SAIDI and SAIFI by Cause – Total System - IEEE Criteria

2018:




| Cause | SAIDI |
|-------------------|-------|
| Tree Related | 70.3 |
| Equipment Related | 15.6 |
| Other | 13.0 |
| Action By Others | 12.0 |
| Animal/Bird | 3.9 |
| Weather Related | 2.2 |
| Unknown | 1.6 |
| Employee Error | 1.2 |

| Cause | SAIFI |
|-------------------|-------|
| Tree Related | 0.52 |
| Other | 0.18 |
| Equipment Related | 0.14 |
| Action By Others | 0.09 |
| Animal/Bird | 0.07 |
| Unknown | 0.03 |
| Employee Error | 0.02 |
| Weather Related | 0.02 |

Section 1.7 cont'd SAIDI and SAIFI by Cause – Total System - IEEE Criteria

2019:




| Cause | SAIDI |
|-------------------|-------|
| Tree Related | 40.5 |
| Other | 13.9 |
| Equipment Related | 10.9 |
| Action By Others | 10.8 |
| Weather Related | 2.4 |
| Animal/Bird | 1.8 |
| Employee Error | 1.6 |
| Unknown | 0.8 |

| Cause | SAIFI |
|-------------------|-------|
| Tree Related | 0.31 |
| Other | 0.18 |
| Action By Others | 0.09 |
| Equipment Related | 0.09 |
| Animal/Bird | 0.02 |
| Employee Error | 0.02 |
| Weather Related | 0.02 |
| Unknown | 0.01 |

Section 1.7 cont'd SAIDI and SAIFI by Cause – Total System - IEEE Criteria

2020:




| Cause | SAIDI |
|-------------------|-------|
| Tree Related | 58.0 |
| Other | 10.6 |
| Action By Others | 10.4 |
| Equipment Related | 9.6 |
| Animal/Bird | 3.9 |
| Weather Related | 2.1 |
| Employee Error | 0.6 |
| Unknown | 0.5 |

| Cause | SAIFI |
|-------------------|-------|
| Tree Related | 0.42 |
| Other | 0.13 |
| Action By Others | 0.08 |
| Equipment Related | 0.08 |
| Animal/Bird | 0.05 |
| Weather Related | 0.02 |
| Employee Error | 0.01 |
| Unknown | 0.01 |

Section 1.7 cont'd SAIDI and SAIFI by Cause – Total System - IEEE Criteria

2021:




| Cause | SAIDI |
|-------------------|-------|
| Tree Related | 62.9 |
| Other | 13.2 |
| Equipment Related | 8.0 |
| Action By Others | 7.9 |
| Animal/Bird | 2.4 |
| Weather Related | 1.5 |
| Unknown | 0.5 |
| Employee Error | 0.2 |

| Cause | SAIFI |
|-------------------|-------|
| Tree Related | 0.47 |
| Other | 0.16 |
| Equipment Related | 0.08 |
| Action By Others | 0.07 |
| Animal/Bird | 0.03 |
| Weather Related | 0.01 |
| Unknown | 0.01 |
| Employee Error | 0.00 |

Section 1.7 cont'd SAIDI and SAIFI by Cause – Total System - IEEE Criteria

2022:



| Cause | SAIDI |
|-------------------|-------|
| Tree Related | 52.0 |
| Equipment Related | 7.4 |
| Other | 7.2 |
| Action By Others | 6.9 |
| Weather Related | 1.8 |
| Animal/Bird | 1.3 |
| Employee Error | 1.1 |
| Unknown | 1.0 |

| Cause | SAIFI |
|-------------------|-------|
| Tree Related | 0.37 |
| Other | 0.10 |
| Action By Others | 0.07 |
| Equipment Related | 0.06 |
| Animal/Bird | 0.02 |
| Employee Error | 0.02 |
| Weather Related | 0.02 |
| Unknown | 0.01 |

Section 2

O&M Activity Summary January 1, 2022 – December 31, 2022

Section 2.1 Pole Inspections

Program Description: Inspect for decayed or damaged poles to ensure reliable and safe use of this asset.

Total Unit Population: Eversource is responsible for ground line inspection of approximately 250,000 poles. Eversource performs ground line inspection of poles in Eversource set areas only. A visual overhead inspection is performed on all poles to which the Company is attached.

Maintenance Cycle: Wood poles are inspected on a 10-year cycle in accordance with Eversource Maintenance Plan Chapter 5.61 and Intracompany Operating Procedures in place with joint owners in the State of NH.

Reliability Benefit: Replacement of decayed poles results in a more reliable and resilient distribution system.

Results: Pole inspection plans are developed based on the total number of poles in the towns to be inspected. Copper, Chrome, Arsenic ("CCA") treated poles less than 20 years old, and those treated with other preservatives and less than 10 years old, are not checked for ground line decay (sound and bore and/or ground line excavation). In 2022, 18,151 poles were ground line inspected plus an additional 28,171 poles in joint owner maintenance area were visually inspected for overhead issues.

| \$ Plan | \$ Actual | \$ Variance |
|----------------|------------------|--------------------|
| \$689,000 | \$633,436 | (\$55,564) |

Expenses were lower than anticipated due to the number of newer poles which did not require inspection, based on age, in the towns inspected in 2022.

Section 2.2 National Electrical Safety Code (NESC) Repairs

Program Description: Repair non-capital items documented as part of circuit inspections or other NESC compliance surveys such as during surveys for third party attachments.

Total Unit Population: Eversource has approximately 12,200 miles of overhead distribution line and approximately 2,000 miles of underground distribution line.

Results: In 2022, 12 NESC repair maintenance orders were completed and 0 corrective maintenance orders are outstanding. Extensive repairs were completed as part of make-ready work for CATV expansion into the Lakes Region area as well as other areas of concentrated third-party activity.

| \$ Plan | \$ Actual | \$ Variance |
|----------------|------------------|--------------------|
| n/a* | n/a* | n/a* |

*Budgets are not developed or tracked at this level or for this activity. Work is completed under a variety of Field Work Orders ("FWOs")

Section 2.3 Underground Circuit Inspections

Program Description: Inspect Direct Buried facilities including cable in conduit installations. Periodic inspections of Direct Buried and associated equipment at the specified interval allows preventative and corrective actions to be performed prior to situations becoming hazardous to the public or resulting in equipment failure.

Total Unit Population: Eversource is responsible for approximately 28,800 assets which are located in underground developments or are underground facilities providing service from the company's overhead system totaling approximately 2,000 miles of underground line.

Maintenance Cycle: Direct buried (including cable in conduit) facilities are inspected on a 10-year cycle, in accordance with Eversource Maintenance Plan chapter 5.11. As needed, replace fault indicators on a scheduled basis at the time of inspection.

Reliability Benefit: Proactively inspect underground developments, padmounted transformers, and associated equipment to identify potential issues and to ensure they function when needed.

Results: In 2022, 2,701 assets were inspected.

| \$ Plan | \$ Actual | \$ Variance |
|----------------|------------------|--------------------|
| n/a* | n/a* | n/a* |

*Budgets are not developed or tracked at this level or for this activity. Inspection work is completed under a variety of Field Work Orders (FWOs).

Section 2.4 Overhead Circuit Patrols

Program Description: Patrol overhead distribution lines. Patrols may be done for a variety of reasons including infrared patrols, post-storm patrols, or other reasons. Each reason for patrolling has different criteria regarding how far into the circuit the patrol is performed. For example, infrared patrols cover only the backbone while post-storm patrols may include all circuitry out to a certain size protective device.

Total Unit Population: Eversource has approximately 12,200 miles of overhead distribution line.

Maintenance Cycle: Overhead roadside distribution line backbones are inspected with infrared imaging equipment at least once annually in accordance with Eversource Maintenance Plan chapter 5.22. Aerial patrols of lines in rights-of-way (ROW) are completed at least once per year in accordance with the Eversource Maintenance Plan chapter 5.45

Reliability Benefit: Infrared patrols are intended to identify overheated equipment which may cause an outage or damage other equipment. Post-storm patrols are intended to find leftover damage not repaired during the storm or imminent dangers, either of which may cause an outage in the future. Aerial ROW patrols are intended to identify items needing repair which may cause an outage in the future.

Results: Patrols completed in 2022:

ROW aerial patrols: All ROW lines or line segments were patrolled in February, and August of 2022, with additional patrols of certain lines over the course of the year associated with project work, in response to momentary events, or following storm events. A list of lines patrolled is included in Section 2.4(a) below.

Patrols of poor performing roadside circuits were conducted in 2022 to identify unfused transformers and laterals. A project was approved to add fusing to these locations to improve the reliability for these customers by preventing isolated events from affecting larger numbers of customers.

In addition, focused post storm circuit sweeps were conducted following multiple weather events throughout the year. Circuits with moderate or higher impacts were patrolled. Three phase backbone and large single and three phase laterals were patrolled. These patrols were conducted to identify anything which might cause an imminent outage, a danger to public safety, Eversource debris left beside the road, limbs on or over the primary, and broken or uprooted trees leaning on or over the primary conductors. All items were addressed immediately by entry and tracking in the Outage Management System.

The vegetation management ("VM") organization performs post event assessments following all tree related events that result in a permanent outage affecting 100 or more customers as well as when "three or more" outages occur in a circuit segment within 90 days to ensure no additional VM follow up is required. Additionally, VM performs a "reliability" assessment of the system during the 100% quality control inspection of the trimming that is completed annually. Arborists record locations where they observe electrical hardware issues and report them into the System Operations Center.

Infrared ("IR") patrols were reinstated in 2022 (they were paused in 2020 and 2021 due to COVID-19 precautions). The surveys are performed on substation equipment and circuit three phase backbones to identify situations which could lead to equipment failure due to heating from poor connections or failing equipment.

The roadside circuits patrolled are listed below in Section 2.4(b).

| \$ Plan | \$ Actual | \$ Variance |
|----------------|------------------|--------------------|
| n/a* | n/a* | n/a* |

*Budgets are not developed or tracked at this level or for this activity.

Section 2.4(a) ROW Patrols

| Area Work Center | Circuit | Berlin | 3525X | Keene | 76W1 |
|------------------|---------|----------|---------|------------------|--------|
| Bedford | 312 | Chocorua | 346 | Keene | 76W3 |
| Bedford | 314 | Chocorua | 347 | Keene | 76W4 |
| Bedford | 322 | Chocorua | 390 | Keene | 76W7 |
| Bedford | 323 | Chocorua | 395 | Keene | W110 |
| Bedford | 324 | Chocorua | 3218 | Keene | W15 |
| Bedford | 328 | Chocorua | 3218 | Keene | W15 |
| Bedford | 354 | Chocorua | 336X | Keene | W15 |
| Bedford | 358 | Chocorua | 346X2 | Keene | W185 |
| Bedford | 359 | Derry | 3184X | Keene | W2 |
| Bedford | 378 | Derry | 3184X10 | Keene | W9 |
| Bedford | 3108 | Derry | 32W1 | Keene | 313 |
| Bedford | 3138 | Derry | 32W4 | Keene/Newport | 311 |
| Bedford | 3143 | Derry | 32W5 | Lancaster | 348 |
| Bedford | 3151 | Derry | 365X | Lancaster | 355X10 |
| Bedford | 3155 | Epping | 377 | Lancaster | 355 |
| Bedford | 3164 | Epping | 380 | Lancaster | 384 |
| Bedford | 3194 | Epping | 3103 | Lancaster | 348X3 |
| Bedford | 3212 | Epping | 3162 | Lancaster | 376L |
| Bedford | 3392 | Epping | 3229 | Lancaster | 376W |
| Bedford | 3467 | Epping | 3152X | Lancaster | 384X1 |
| Bedford | 314X12 | Epping | 49W1 | Lancaster/Berlin | 351 |
| Bedford | 3194X1 | Hooksett | 318 | Lancaster/Tilton | 348X2 |
| Bedford | 3194X2 | Hooksett | 321 | Nashua | 353 |
| Bedford | 3271 | Hooksett | 335 | Nashua | 383 |
| Bedford/Hooksett | 325 | Hooksett | 356 | Nashua | 389 |
| Bedford/Hooksett | 334 | Hooksett | 370 | Nashua | 3110 |
| Bedford/Hooksett | 357 | Hooksett | 393 | Nashua | 3136 |
| Bedford/Hooksett | 3142 | Hooksett | 3182 | Nashua | 3144 |
| Bedford/Hooksett | 334R | Hooksett | 3613 | Nashua | 3146 |
| Bedford/Hooksett | 335X56 | Hooksett | 3614 | Nashua | 3147 |
| Bedford/Hooksett | 387 | Hooksett | 334G | Nashua | 3154 |
| Bedford/Nashua | 329 | Hooksett | 372 A&B | Nashua | 3159 |
| Bedford/Nashua | 3217 | Keene | 382 | Nashua | 3175 |
| Berlin | 352 | Keene | 3178 | Nashua | 3177 |
| Berlin | 3521 | Keene | 3235 | Nashua | 3445 |
| Berlin | 350X | Keene | 313X4 | Nashua | 3445 |
| Berlin | 350X2 | Keene | 3140X1 | Nashua | 3750 |
| Berlin | 350X2 | Keene | 382X2 | Nashua | 3020X |
| | | Keene | 4W1 | Nashua | 3110X |

| | |
|------------|---------|
| Nashua | 3168X |
| Nashua | 3891X |
| Newport | 315 |
| Newport | 316 |
| Newport | 3410 |
| Newport | 311 Tap |
| Newport | 317 Tap |
| Newport | 4181 |
| Newport | 4435 |
| Newport | 55W2 |
| Newport | 61W2 |
| Portsmouth | 3191 |
| Portsmouth | 339 |
| Portsmouth | 367 |
| Portsmouth | 3101 |
| Portsmouth | 3102 |
| Portsmouth | 3105 |
| Portsmouth | 3106 |
| Portsmouth | 3111 |
| Portsmouth | 3112 |
| Portsmouth | 3165 |

| | |
|------------|-------|
| Portsmouth | 3171 |
| Portsmouth | 3172 |
| Portsmouth | 3214 |
| Portsmouth | 3850 |
| Portsmouth | 3153X |
| Rochester | 32 |
| Rochester | 340 |
| Rochester | 362 |
| Rochester | 371 |
| Rochester | 386 |
| Rochester | 392 |
| Rochester | 399 |
| Rochester | 3157 |
| Rochester | 3157 |
| Rochester | 3174 |
| Rochester | 3228 |
| Rochester | 3425 |
| Rochester | 3601 |
| Rochester | 3148X |
| Rochester | 386A |
| Rochester | 399X1 |

| | |
|----------------|-------|
| Rochester | W122 |
| Tilton | 310 |
| Tilton | 319 |
| Tilton | 337 |
| Tilton | 338 |
| Tilton | 343 |
| Tilton | 345 |
| Tilton | 368 |
| Tilton | 398 |
| Tilton | 3025 |
| Tilton | 3122 |
| Tilton | 3149 |
| Tilton | 3196 |
| Tilton | 3548 |
| Tilton | 3625 |
| Tilton | 3798 |
| Tilton | 3222X |
| Tilton | 342A |
| Tilton | 342B |
| Tilton/Epping | 3137X |
| Tilton/Newport | 317 |

Section 2.4(b) Roadside Circuit Patrols

| |
|----------------|
| Bedford |
| 3108 |
| 3138 |
| 12W2 |
| 12W3 |
| 18W1_12 |
| 23X2_12 |
| 23X4_12 |
| 23X5_22 |
| 23X6_22 |
| 3108_12 |
| 3108X1_12 |
| 311X1_12 |
| 311X3_12 |
| 311X5_12 |
| 311X6_12 |
| 311X8 |

| |
|------------|
| 312X_12 |
| 3151X10_12 |
| 3151X9_12 |
| 3164X3_12 |
| 3164X8_12 |
| 3173X1_12 |
| 317X1_12 |
| 317X2 |
| 317X3_12 |
| 317X7 |
| 3194X1_12 |
| 322X10_12 |
| 322X12_12 |
| 323X5_12 |
| 3271X1_12 |
| 3271X2_12 |
| 3271X3_12 |
| 3271X45_12 |

| |
|-----------|
| 3271X5_12 |
| 327X10_12 |
| 327X8_12 |
| 328X1_12 |
| 328X9_12 |
| 334G_12 |
| 334X14_12 |
| 335X1_12 |
| 335X15_12 |
| 335X2_12 |
| 335X3_12 |
| 33H1_12 |
| 35H1_12 |
| 360X1_12 |
| 360X11_12 |
| 360X14_12 |
| 360X2_12 |
| 360X5_12 |

| |
|-----------------|
| 360X7_12 |
| 37W1_12 |
| 3W1_12 |
| 3W2 |
| 5W1 |
| 5W2 |
| 79W4_12 |
| 85W1_12 |
| JACKMAN |
| Berlin |
| 21H1_77 |
| 21H2 |
| 21H4 |
| 21H5 |
| 25W1_77 |
| 350X_77 |
| 350X1_77 |
| 350X2_77 |
| 351X4_77 |
| 3525X1_77 |
| 3525X2_77 |
| 3525X3_77 |
| 3525X4_77 |
| 3525X5_77 |
| Chocorua |
| 19W1 |
| 19W2 |
| 3116X1_45 |
| 3218_45 |
| 336X_45 |
| 336X1_45 |
| 346X1_45 |
| 347_45 |
| 395_45 |
| Derry |
| 31280 |
| 31840 |
| 26W1_23 |
| 3115X_23 |
| 3128X_23 |
| 3133X_23 |
| 3141X_23 |

| |
|---------------|
| 3156X |
| 3184X_23 |
| 32W1 |
| 32W3 |
| 32W4 |
| 32W5 |
| 365X_23 |
| 8W1_23 |
| Epping |
| 13H1 |
| 13H2 |
| 3103_65 |
| 3103X1_65 |
| 3115X11_65 |
| 3115X12_65 |
| 3115X7_65 |
| 3115X9_65 |
| 3137X1_65 |
| 3137X10_65 |
| 3137X3_65 |
| 3137X5_65 |
| 3137X6_65 |
| 3137X7_65 |
| 3137X8_65 |
| 3137X80_65 |
| 3152X_65 |
| 3152X1_65 |
| 3162X1_65 |
| 3229X1_65 |
| 3229X2_65 |
| 3229X3_65 |
| 3229X5_65 |
| 3229X6_65 |
| 377X1_65 |
| 377X11_65 |
| 377X15_65 |
| 377X16_65 |
| 377X19_65 |
| 377X2_65 |
| 377X20_65 |
| 377X29_65 |
| 377X3_65 |

| |
|-----------------|
| 377X5_65 |
| 377X6_65 |
| 377X7_65 |
| 380X1_65 |
| 380X2_65 |
| 380X3_65 |
| 49W1_65 |
| 63W1 |
| Hooksett |
| 13W1 |
| 14H4 |
| 14H7 |
| 14H8 |
| 14W1 |
| 14W2 |
| 14W7_11 |
| 14X126A_11 |
| 14X188_11 |
| 18W1_12 |
| 18W3 |
| 21W1 |
| 22W1 |
| 22W2 |
| 23W1 |
| 23W2 |
| 23W3 |
| 23W4 |
| 24H2 |
| 27W2 |
| 29H2_11 |
| 318X2_11 |
| 321X11_11 |
| 324X10_11 |
| 324X8_11 |
| 325X7_11 |
| 334X18_11 |
| 34W18_11 |
| 3614X3_11 |
| 3615X1_11 |
| 3615X2_11 |
| 3615X3_11 |
| 370X_11 |

| |
|--------------|
| 393X11_11 |
| 393X20_11 |
| 393X8_11 |
| 44W2 |
| 7W1_11 |
| Keene |
| 3140 |
| 24X1_36 |
| 26H1_36 |
| 26H2_36 |
| 28W1_36 |
| 3120X1_31 |
| 3120X2_31 |
| 3120X3_36 |
| 3120X4_36 |
| 3139X_31 |
| 313X1_36 |
| 313X2_36 |
| 313X4_36 |
| 313X7_36 |
| 3140_36 |
| 3140X1_36 |
| 3140X2_36 |
| 3140X3_36 |
| 3155X4_36 |
| 3173_36 |
| 3178_31 |
| 3178X3_31 |
| 3178X4_31 |
| 3178X5_31 |
| 3179X |
| 33W1 |
| 35W1 |
| 382X2_36 |
| 382X3_36 |
| 4W1 |
| 4W2 |
| 51W1_36 |
| 53H1_31 |
| 53H2_36 |
| 55H1_36 |
| 76W1 |

| |
|------------------|
| 76W3 |
| 76W4 |
| 76W5_31 |
| 76W7_31 |
| CHESTNUT |
| TB95L |
| W1 |
| W110 |
| W15 |
| W175_31 |
| W185 |
| W2 |
| W9_31 |
| Lancaster |
| 12W1_43 |
| 17W1_43 |
| 1W1 |
| 1W2 |
| 348X1_76 |
| 348X19_43 |
| 348X2_76 |
| 348X20_43 |
| 348X3 |
| 348X4_76 |
| 348X5_76 |
| 348X7_76 |
| 348X8_76 |
| 348X9_76 |
| 351X1_76 |
| 351X16_76 |
| 351X17_76 |
| 351X2_76 |
| 355X_76 |
| 355X1_76 |
| 355X10_76 |
| 355X14_76 |
| 355X15_76 |
| 355X16_76 |
| 355X2_76 |
| 355X3_76 |
| 355X4_76 |
| 355X5_76 |

| |
|---------------|
| 355X6_76 |
| 355X7_76 |
| 36W1_76 |
| 376X1_76 |
| 376X2_76 |
| 376X3_76 |
| 376X4_76 |
| 376X5_76 |
| 376X6_76 |
| 384_76 |
| 41W1_43 |
| 43W1_43 |
| 45W1_43 |
| 59W1 |
| 59W2 |
| 5H1 |
| 5H2 |
| Nashua |
| 32170 |
| 03168X |
| 15H2 |
| 15H3 |
| 15H4 |
| 15H5 |
| 15H6 |
| 15W1 |
| 16H1 |
| 16H2 |
| 16H3 |
| 17H1 |
| 17H2 |
| 17H3 |
| 18H1_21 |
| 18H2 |
| 18H3 |
| 23H3 |
| 23W7 |
| 24W1_21 |
| 27H1_22 |
| 27H2_22 |
| 27H3_22 |
| 2H1 |

| |
|-----------|
| 2H2 |
| 3010X_21 |
| 3020X |
| 3110X_21 |
| 3136X_21 |
| 3143X_22 |
| 3144_21 |
| 3144X1_21 |
| 3144X3_21 |
| 314X12_22 |
| 314X14_22 |
| 314X15_22 |
| 314X23_22 |
| 314X26_22 |
| 314X3_22 |
| 314X4_22 |
| 314X46_22 |
| 314X54_22 |
| 3154X1_21 |
| 3154X2_21 |
| 3155X_22 |
| 3155X2_22 |
| 3155X3_22 |
| 3155X7_22 |
| 3155X8_22 |
| 3155X9_22 |
| 3168X_21 |
| 3175X_21 |
| 3175X1_21 |
| 3175X3_21 |
| 3177X1_21 |
| 3177XA_21 |
| 3212X_22 |
| 3217X_22 |
| 3445X_21 |
| 3750_21 |
| 383X1_21 |
| 383X2_21 |
| 383X3_21 |
| 3H1_21 |
| 3H2_21 |
| 40W1 |

| |
|-------------------|
| 6W1_21 |
| 72W1_21 |
| 9H1 |
| 9H2 |
| 9H2_21 |
| HUDSON |
| Newport |
| 16W1 |
| 16W3 |
| 315X2_32 |
| 316_32 |
| 316X1_32 |
| 316X2_32 |
| 3410_32 |
| 3410X1_32 |
| 42X1 |
| 42X3_32 |
| 42X4 |
| 44H1 |
| 46W1 |
| 47W1_32 |
| 48W1_32 |
| 54W1 |
| 55W2 |
| 60W1 |
| 61W2 |
| 74W1 |
| 75W2 |
| NEW_LONDON |
| TB92L |
| Portsmouth |
| 15W4 |
| 16W4_63 |
| 2W4 |
| 2W5 |
| 3102_63 |
| 3105X1_63 |
| 3105X4_63 |
| 3111X1_63 |
| 3112X1_63 |
| 3112X3_63 |
| 3112X4_63 |

| |
|------------------|
| 3153X |
| 3172X1_63 |
| 3191X3_63 |
| 3191X9_63 |
| 339X8_63 |
| 367X2_63 |
| 3850X1_63 |
| 3850X7_63 |
| 48H1 |
| 48H2 |
| 48W2 |
| 58W1 |
| 64W1 |
| 64W2 |
| 64W2_63 |
| 67W1_63 |
| 67W2 |
| 6H1_63 |
| 6H2_63 |
| 71W1 |
| 71W2 |
| 71W3 |
| 71W4 |
| Rochester |
| 115 |
| 122 |
| 3137 |
| 3148X_62 |
| 3148X1_62 |
| 3148X2_62 |
| 3148X3_62 |
| 3157X1_61 |
| 3157X2_61 |
| 3174X1_61 |
| 3174X4_61 |
| 32X3_62 |
| 32X4_62 |
| 32X6_61 |
| 340X1_61 |
| 340X5_61 |
| 34W2 |
| 34W3 |

| |
|-----------|
| 34W4 |
| 34W4_61 |
| 362X1_61 |
| 362X2_61 |
| 371X1_61 |
| 371X14_62 |
| 371X30_62 |
| 371X8_62 |
| 371X9_62 |
| 38W1 |
| 38W2 |
| 392X |
| 392X1_61 |
| 392X2_61 |
| 392X4_61 |
| 392X5_61 |
| 392X7_62 |
| 399X1_62 |
| 399X11_62 |
| 399X13_62 |
| 399X15_62 |
| 399X18_61 |
| 399X5_61 |
| 39W2_61 |
| 40H1 |
| 41H1 |
| 41H2 |
| 42H1_61 |
| 42H2 |
| 51H1 |
| 53W1 |

| |
|---------------|
| 53W2 |
| 54H1_61 |
| 54H2_61 |
| 56H1_61 |
| 56H2_61 |
| 57W1 |
| 73H1 |
| 73W1_61 |
| 73W2 |
| Tilton |
| 10W1 |
| 11W1_41 |
| 11W2_41 |
| 1X4_42 |
| 20W1_42 |
| 20W2 |
| 27X1_41 |
| 29X1_41 |
| 2W1_41 |
| 2W2_41 |
| 30W2_64 |
| 310_41 |
| 310X3_41 |
| 310X5_41 |
| 3114W1_42 |
| 3114X_42 |
| 3137X2_64 |
| 319X1_64 |
| 31W1 |
| 31W2 |
| 3216X2_42 |

| |
|------------|
| 337X8_42 |
| 338X3_41 |
| 342A |
| 343_41 |
| 345B |
| 345X1_42 |
| 345X5_41 |
| 3548_42 |
| 3548X2_42 |
| 3548X6_42 |
| 3548X9_42 |
| 3798X4_42 |
| 37H1 |
| 37H2 |
| 37X4 |
| 398X2_41 |
| 398X3_41 |
| 39H1 |
| 39H2 |
| 39W1 |
| 39W2 |
| 47H7 |
| 47H8 |
| 68W6 |
| 70W1 |
| 70W2 |
| 90H1 |
| 90H2 |
| 90W2 |
| 9W1_41 |
| CHICHESTER |

Section 3

Capital Activity Summary January 1, 2022 – December 31, 2022

CAPITAL - 2022

REJECT POLE REPLACEMENT:

Program Description:

Replace poles determined to be defective during the annual inspection cycle.

Eversource maintains approximately 250,000 poles on its system. These are inspected every 10 years or an average of 25,000 poles per year.

Pole inspection plans are developed based on the total number of poles in the towns to be inspected. Copper, Chrome, Arsenic ("CCA") treated poles less than 20 years old, and those treated with other preservatives and less than 10 years old, are not checked for ground line decay (sound and bore and/or ground line excavation).

Joint owned poles maintained by others are visually inspected for overhead issues.

Total Unit Population:

Depending upon inspection results, Eversource estimates 500 poles to replace each year which corresponds to a 2% failure rate.

Results:

In 2022, 18,151 poles were ground line inspected plus an additional 28,171 poles in joint owner maintenance area were visually inspected for overhead issues. 421 poles were found to be defective requiring replacement. (257 Eversource, 164 CCI). Eversource actively replaces all reject poles in Eversource territory and ensures "C" rejects within CCI maintenance area are addressed. Eversource completed approximately 86% of this population by 2022 year-end, with the remainder to be completed in early 2023. The delay was a result of limited pole availability due to ongoing global supply chain issues.

| \$ Plan | \$ Actual | \$ Variance |
|----------------|------------------|--------------------|
| \$2,225,000 | \$1,384,693 | (\$840,307) |

DIRECT BURIED CABLE REPLACEMENT:

Program Description:

Replace direct buried cable with cable in conduit.

Approximately 2,000,000 feet of direct buried cable was installed at Eversource prior to 1985 with earliest vintages from 1970. Cable insulation is subject to age failure and bare concentric neutral conductors are subject to corrosion. Testing has indicated that in many locations the concentric neutral is no longer sufficient to provide a path to ground for the electric system. This project is to replace unjacketed direct buried cable in specific developments which have experienced a high failure rate. Live front transformers and/or pre-1987 elbows are replaced along with the cable.

Results:

Two cable replacement projects were completed in 2022. (Isolated replacement of failed cable sections are completed under the Obsolescence ("DQ") Annual project).

Tidewater Farm URD Loop - The underground development off Tidewater Rd in Greenland has a history of outages due to failed direct buried cable. The direct buried cable runs through the woods and the pad mount transformer 17/23S2T1 is in an inaccessible vegetated area. This project installed a new pad mounted

transformer and relocated the inaccessible pad to an accessible location by the roadside. The project replaced direct buried cable with new cable in conduit. Page 30 of 41

Riverview UG Replacement - Riverview Apartment Complex was built in the early 1970s and the primary and secondary electric service to the five buildings was all direct buried. A secondary cable failed in February 2022 and temporary repairs were made to restore power. The property is undergoing system improvements to the electric services and the various building systems. This presented an opportunity to upgrade the 50 year-old infrastructure while greatly reducing the likelihood of more failures. The feed to the complex was radial with no existing back feed. The new design incorporated a second primary riser and a loop configuration.

| \$ Plan | \$ Actual | \$ Variance |
|----------------|------------------|--------------------|
| \$670,000 | \$550,164 | \$(119,836) |

OTHER CAPITAL RELIABILITY PROJECTS:

Category Description: This category includes all projects with spending in 2022 in excess of \$100,000 which were at least partially justified based on reliability.

There were 24 reliability improvement projects established in 2022 with spending greater than \$100,000. These projects are listed below. Project descriptions are included in Section 3.1.

| Project | Project Description | Authorized Amount | 2022 Spend | Status (12/31/22) |
|---|-------------------------------------|-------------------|-------------------|--------------------|
| A22C01 | Manchester Network Cable Replacemen | 1,792,000 | 1,617,922 | Under Construction |
| A22C03 | GOFFSTOWN SS ELIM PHASE 2 27W2 CONV | 2,420,000 | 382,543 | Under Construction |
| A22C61 | 323 Line Underbuild Re-attachment | 1,738,000 | 544,790 | Under Construction |
| A22C77 | Mammoth Rd SS TPU Relay Repl | 631,000 | 253,833 | Under Construction |
| A22C85 | 317 Line ROW Section Rebuild | 544,000 | 514,896 | Under Construction |
| A22E41 | RESISTANCE SS RETIREMENT | 1,115,400 | 181,333 | Under Construction |
| A22E47 | 3148X3 REMOVAL - NORTH DOVER | 1,363,000 | 1,052,103 | Under Construction |
| A22E56 | 32 Line Pole Replacement | 5,670,500 | 3,207,332 | Under Construction |
| A22E57 | 371 Line Pole Replacements | 6,281,700 | 3,464,164 | Under Construction |
| A22LS | DISTRIBUTION AUTOMATION LINE SENSOR | 360,000 | 477,644 | Completed |
| A22N60 | 355 Line Emergent Str Replacement | 802,000 | 567,733 | Completed |
| A22N71 | 355 Line Pole Replacement | 481,000 | 188,366 | Under Construction |
| A22RPR | Roadside Reject Pole Replacement | 2,225,000 | 1,384,693 | Under Construction |
| A22S10 | 3217X ROCKY POND RD BACKFEED | 350,000 | 275,809 | Under Construction |
| A22S50 | 3128X GRIFFIN ROAD CONVERSION | 381,000 | 213,574 | Completed |
| A22W02 | 3120X2 RT 119 CONVERSION | 850,000 | 350,262 | Under Construction |
| A22W08 | 3139X SPOFFORD RD RECONDUCTOR | 384,000 | 212,604 | Completed |
| A22W26 | 317/3410 Reconstruction Phase 2 | 3,255,000 | 2,039,405 | Under Construction |
| A22W63 | 313X1 Riverview UG Replacement | 417,000 | 374,362 | Under Construction |
| A22W68 | 3140X Stoddard Rebuild | 575,000 | 226,776 | Completed |
| A22X17 | 2022 WOOD POLE TREATMENT | 419,100 | 232,116 | Under Construction |
| A22X35 | 2022 CIRCUIT PATROL REPAIRS | 946,000 | 988,879 | Completed |
| A22X67 | NH Cutout Installation 2022* | 1,869,000 | 3,169,580 | Completed |
| A22X74 | Tripsaver Initiative | 946,000 | 915,233 | Completed |
| Total 2022 Amount for projects initiated in 2022 | | 35,815,700 | 22,835,951 | |
| (Note the Authorized Amount includes the total for Multi-year projects) | | | | |

*Note: A Supplement Authorization was approved at NHPAC prior to exceeding the authorized amount.

In addition, there were 20 reliability projects established in prior years with spending in 2022 in excess of \$100,000. Project descriptions for these projects are included in Section 3.2.

| Project | Project Description | Sum of 2022 FY Actual |
|--|-------------------------------------|-----------------------|
| A16C08 | Brook St S/S 13TR1 Replacement | 621,483 |
| A17S03 | MILLYARD SS REPLACEMENT | 6,884,270 |
| A18C07 | EDDY SS CONTROL HOUSE | 2,474,126 |
| A18N03 | WHITE LAKE SS REBUILD | 157,341 |
| A18W06 | MONADNOCK SS REPLACE TRANSFRMR TB40 | 297,344 |
| A19C33 | Animal Protection at Rimmon SS | 555,482 |
| A19S40 | AMHERST S/S - PLC AUTOMATION REPLAC | 2,219,446 |
| A20S02 | Millyard SS Distribution Line Work | 3,728,199 |
| A20W18 | 317/3410 RECON BRADFORD TO WARNER | 266,766 |
| A20W37 | RIVER ROAD SS UPGRADES | 543,107 |
| A20X26 | SPARE 345-34.5kV TRANSFORMER | 723,107 |
| A21C07 | MALVERN VALLEY HANOVER CIRCUIT TIE | 137,908 |
| A21C91 | 393 LINE ROW SECTION REBUILD | 4,677,513 |
| A21DA | DISTRIBUTION AUTOMATION POLE TOP | 1,242,339 |
| A21E08 | CIRCUIT TIE 3191X1B TO 377X2 | 158,369 |
| A21E16 | REPLACE ROCHESTER SS BUS TIE AUTOCL | 442,535 |
| A21E94 | TIDEWATER FARM URD LOOP | 173,152 |
| A21N45 | ASHLAND S/S-PLC REPLCMNT& P&C UPGRD | 424,047 |
| A21S17 | 34.5kV CAP BANK SWTCH REP BROAD ST | 310,958 |
| A21X93 | 2021 CIRCUIT PATROL REPAIRS PHASE 2 | 105,237 |
| Total 2022 spend on projects initiated in prior years | | 26,142,728 |

Section 3.1

2022 Projects

A22C01 Manchester Network Cable Replacement (Phase 2) - Under Construction

Phase 2 of the Manchester Network Cable Replacement project will reconnector the 13B and 13D cables from just outside Brook Street Substation to Hampshire Plaza on Elm Street in Manchester, NH. The work in 2022 involves 5 of the 33 transformer vaults. Reconductoring the entire network will take place over four years.

A22C03 GOFFSTOWN SS ELIM PHASE 2 27W2 CONV - Under Construction

Phase 2 will convert the 27W2 12.47 kV circuit to 34.5 kV. Phase 1 converted the 45H1 circuit to 34.5 kV and was completed in February 2022. Implementing both phases of these projects eliminate a 64-year-old, islanded substation and non-standard 3.74 kV circuit, optimizing Distribution Automation and improving system reliability in Goffstown.

A22C61323 Line Under-build Reattachment - Under Construction

Reattach a 2.63-mile long section of the 34.5kV 323 distribution line underbuilt below the V191 Transmission line. 33 of the 41 laminated wood structures on the V191 line will be replaced with lightweight weathering steel structures due to structural integrity failures.

A22C77 Mammoth Rd SS TPU Relay Replacement - Under Construction

Replace one (1) TPU2000R ABB relay in service at Mammoth Road Station with one (1) SEL-387E protection relay. The replacement of this obsolete relay is required as ABB has classified the relays as obsolete and replacement parts are no longer available. Failure could result in a transformer outage, a decrease in system reliability, and unnecessary relay replacement work under emergency conditions.

A22C85317 Line ROW Section Rebuild - Under Construction

Reconstruction of the 317 line in the right of way between Rt.127 in Warner and the line crossing at Dustin Rd. in Webster. Ten (10) aged wooden poles and deteriorated crossarms will be replaced with new steel structures. In addition to the pole replacements, this project proposes the replacement of 1,900 linear feet of 83-year-old #2 copper conductor with 477 MCM spacer cable. This replacement project will harden the system and provide for future load transfer capabilities.

A22E41 RESISTANCE SS RETIREMENT - Under Construction

Provide partial funding for engineering support and environmental analysis for the Solution Design Committee Review of the Resistance Substation retirement. The Resistance SS has a single 1971 vintage, 44.8MVA transformer, and there are concerns with the aging infrastructure, deteriorating foundations, structures, and broken bushings in the substation. Due to the proximity and recent increased capacity at the Portsmouth SS, it is recommended that Resistance SS be retired.

A22E47 3148X3 REMOVAL - NORTH DOVER - Under Construction

Remove seventeen (17) Poles in the 34.5 kV 3148X3 Right of Way (ROW) alternate supply to North Dover Substation in Dover, NH, and install a tap for the 3148X3 and 371 circuits allowing for the removal

of the switches located at pole 130 off Old Rollinsford Road. The results of the March 2022 survey, including below surface investigation, revealed that the 17 wooden structures are showing signs of advanced degradation due in part of the surrounding wet land area. Removing this portion of the ROW line and moving the tap meets the project objective of mitigating the risks associated with the pole failure.

A22E56 32 Line Pole Replacement - Under Construction

Replace 71 wooden poles on the 32 line identified as requiring replacement during a line inspection completed in March 2022. The wood poles will be replaced with self-weathering steel poles, retaining the existing conductor. The wooden poles have experienced advanced deterioration below groundline that is attributable to the surrounding wet land areas. The objective of the project is to prevent long term unexpected failure of wood structures in wetland areas with difficult access with the least cost solution.

A22E57 371 Line Pole Replacements - Under Construction

Replace 69 wooden poles on the 371 line identified as requiring replacement during a line inspection completed in March 2022. The wood poles will be replaced with self-weathering steel poles, retaining the existing conductor. The wooden poles have experienced advanced deterioration below groundline that is attributable to the surrounding wet land areas. The objective of the project is to prevent long term unexpected failure of wood structures in wetland areas with difficult access with the least cost solution. The line inspection was completed in conjunction with the 32 line (A22E56), which shares a right of way.

A22LS DISTRIBUTION AUTOMATION LINE SENSOR - Completed

Install Tollgrade® line sensors at various locations on the distribution system throughout the state. The sensors will monitor current at the installation location and communicate via exception notifications as well as the vendor portal. Future efforts will enable these devices to communicate with the Eversource NH SCADA. This will increase visibility into the Distribution system and may instigate projects to improve reliability on circuits, reveal load balancing or low voltage situations that need to be resolved, or monitor step transformer loading.

A22N60 355 Line Emergent Str Replacement - Completed

Replace four (4) structures located on the right of way of the 34.5 kV 355 line in Northumberland. One structure was identified as in need of immediate replacement. Aerial patrol of the right of way 355 line revealed pole #102 leaning heavily to one side in standing water. Further field investigation revealed poles #103, #104, and #105 need immediate replacement due to advanced degradation below the ground/water line caused by standing water.

A22N71 355 Line Pole Replacement - Under Construction

Helicopter ROW inspection on all 35 miles of the 355 line identified leaning and or damaged structures. The follow up field investigation of those structures showed pole deterioration for upland poles and those below the groundwater surface, rotted crossarms, broken or missing storm guys and crossarm brace(s). This project authorization approves partial funding to perform a full drone inspection, review alternatives, and finalize the scope, engineering design, and environmental controls.

A22RPR Roadside Reject Pole Replacement - Under Construction

The Eversource Maintenance Program requires that all wood poles in Eversource maintenance territory to be inspected every 10 years. This project funds the replacement of poles which are deemed “rejects” as part of the annual inspection program.

A22S10 3217X ROCKY POND RD BACKFEED - Under Construction

This project creates a new feed for the 280 customers at the end of the radial Rocky Pond 3217X ROW tap as well as creating a back feed for the customers at the beginning of this tap. This also provides a more reliable feed to the customers at the end of the 3155X2 circuit currently on the Old Milford Road step transformer who will be transferred to the new feed.

A22S50 3128X GRIFFIN ROAD CONVERSION - Completed

This 3128X project was initiated to address an overloaded step transformer. Removing the overloaded step transformer and converting the full 5,900 feet specified will allow for removal of a 7.2 kV to 19.9 kV step-up transformer feeding an underground development which was built at the higher voltage and will also provide a backfeed to this development.

A22W02 3120X2 RT 119 CONVERSION - Under Construction

The 3120X2 is a large radial circuit with long single-phase taps feeding 191 customers in portions of Fitzwilliam and Richmond. Route 119 in Richmond is fed by Rhododendron Road, which is heavily treed and has several off-road sections. Over the last four years, Rhododendron Road has experienced 28 outages resulting in over 610,000 customer minutes interrupted. To improve reliability, this project will convert 11,300 feet of 2.4 kV to 7.2 kV and construct 2,400 feet of new single-phase to feed Richmond from Route 119.

A22W08 3139X SPOFFORD RD RECONDUCTOR - Completed

The 3193X Distribution line on Spofford Road is the long radial backbone feed into Westmoreland Village with over 600 customers. The road is heavily treed. Outage information revealed that a 2,000 foot section had 10 outages in the last four years caused by trees, resulting in 505,000 customer minutes interrupted. This area has had enhanced tree trimming and danger tree removal but is still susceptible to tree related outages. To improve the resilience of this line, this project will install spacer cable in this high impact line.

A22W26 317/3410 Reconstruction Phase 2 - Under Construction

The 317/3410 line is in poor condition and in a very difficult area due to rugged topography and extensive wetlands. A roadside solution along Route 103 from Bradford to Exit 9 on Interstate 89 in Warner has been approved to improve access to the line at lower cost than rebuilding in the ROW. Phase 1 of this project was completed under project number A20W18. The scope included reconstructing 2.5 miles of the line, from Bradford to Melvin Mills. Phase 2 of this project is to complete the 4.5 miles of roadside construction from Melvin Mills to Warner Exit 9 and to remove the ROW line from Bradford to Warner. Upon completion of Phase 2, the roadside circuit will be fully operational, and the removal of the ROW line can commence.

A22W63 313X1 Riverview UG Replacement - Under Construction

Riverview Apartment Complex was built in the early 1970s and the primary and secondary electric service to the five buildings is all direct buried. A secondary cable failed in February 2022 and temporary repairs were made to restore power. The property is undergoing system improvements to the electric

services and the various building systems. This presents an opportunity to upgrade the 50-year old infrastructure while greatly reducing the likelihood of more failures. The feed to the complex is radial with no existing back feed. The new design incorporates a second primary riser and a loop configuration.

A22W68 3140X Stoddard Rebuild - Completed

The project is to replace a 2,100 foot section of distribution line that was installed in the 1940's and is in poor condition, including three (3) poles that were temporarily repaired during a storm. The line is in a narrow Right of Way (ROW) which is inaccessible because of the rocky terrain and dense vegetation. The new line will be a single phase spacer cable construction on Class 1 poles. A portion of the line will be moved to the roadway and the remaining ROW section will be trimmed to be more accessible.

A22X17 2022 WOOD POLE TREATMENT - Completed

Wood pole treatment of approximately 1,539 structures located on Distribution Right of Way lines in the state of New Hampshire. The treatment is designed to provide a "booster shot" of preservatives to improve the expected performance of the wood poles through the application of a product that provides additional protection against decay and extends the useful life of the pole. Systematic and programmatic implementation of Distribution Wood Pole Treatment has proven to substantially lengthen the service life of wood pole assets.

A22X35 2022 CIRCUIT PATROL REPAIRS - Completed

This project is intended to repair or replace distribution plant discovered to be deficient as a result of the circuit patrols completed in December 2021 and January 2022. The patrols targeted identification of damaged equipment which may result in future outages. The list of items found was assembled and prioritized. A total of approximately 475 items on 2 circuits were repaired or replaced, including broken, leaning, or damaged poles, broken or decayed crossarms and braces, damaged primary conductors, broken or loose guy wires and anchors, damaged insulators or bent pins, broken insulator ties, missing spacer cable spacers, and unfused transformers.

A22X67 NH Cutout Installation 2022 - Completed

To add cutouts to unfused transformers and unfused laterals to improve system reliability. The addition of cutouts to these locations will reduce the number of customers impacted for a fault beyond an unfused location. Specific locations have been identified using patrols and prioritized based upon customer impact.

A22X74 Tripsaver Initiative - Completed

This project is intended to replace approximately 142 existing cut outs with Tripsavers® Cutout-Mounted Reclosers. The installation of these Tripsavers® will increase reliability for Eversource customers by eliminating momentary outages. Tripsavers® will be installed at preselected locations identified through reliability data analytics.

Section 3.2

Prior Years Projects

A16C08 Brook Street S/S 13TR1 Replacement – Under Construction

The 13TR1 switchgear at Brook St S/S is 65 years old and has experienced multiple equipment failures over the last ten years causing the network system to completely lose power. This project will replace the old 13TR1 switchgear with a new 6 bay 15kV metal clad switchgear to provide a reliable power source to the network system.

A17S03 Millyard SS Replacement – Under Construction

This multi-year project rebuilds the Millyard Substation at a new site in Nashua, NH. The existing substation transformers are 68 and 71 years old and the switchgear is of the same vintage. Additionally, over the last few years 3 of the 6 circuit feeders have failed. The substation currently serves 2,700 customers.

A18C07 Eddy SS Control House – Completed

This project is to build a control house in the Eddy Substation yard. The existing control house is in the Public Service Company of New Hampshire Amoskeag Powerhouse adjacent to the Eddy Substation. The Amoskeag generation facilities were sold in 2018 as a result of the generation divestiture in NH. The new control house was needed to house transmission and distribution protection and control systems in a secure building under Eversource access and control.

A18N03 White Lake SS Rebuild – Under Engineering

White Lake Substation in Tamworth, NH became a two (2) transformer 115-34.5 kV substation in the mid-1950s when a 115 kV line (B-112) was constructed as a source to the area. A combustion turbine (CT) generator was added to the substation in 1968 to provide black start capability to the system. The White Lake CT was sold in 2018. This project will rebuild the White Lake SS to address, capacity deficiency, aging equipment, and generation divestiture issues.

A18W06 MONADNOCK SS REPLACE TRANSFRMR TB40 – Under Construction

Full rebuild of Monadnock Substation to address the asset condition of transformer TB40 and the design deficiencies of the existing substation (there are no transformer breakers nor high-side circuit switchers). The rebuild will prevent an outage to the 12,900 customers served by the substation.

A19C33 Animal Protection at Rimmon SS – Completed

There have been sixteen (16) events on the 34.5kV system caused by ravens. TransGard® laser bird defense system will be installed as an engineered solution for this ongoing problem.

A19S40 Amherst SS – PLC Automation Replace - Completed

This project engineers and replaces the PLC designed automation scheme at Amherst Substation. The

PLC designed automation scheme is outdated and a challenge to update and maintain. There are numerous software, firmware, design, and equipment issues with this legacy system.

A20S02 Millyard SS Distribution Line Work – Under Construction

This project is the distribution line work associated with the Millyard Substation rebuild project. The substation project added a pole top SCADA controlled device at Front Street Substation, installed a manhole, and replaced of a section of direct buried cable to a new riser to support the new pole top device.

A20W18 317/3410 Reconductor Bradford to Warner - Completed

The 317/3410 line runs 13.5 miles in ROW from Davisville (Bedford AWC) to Bradford (Newport AWC). The assets are in poor condition and in an area where the terrain is a mixture of year-round water bodies and ravines. Access to the line is challenging for maintenance and emergency repairs. The line does not have a neutral. This project funded the first phase of improving the 317/3410 line. This project constructed a new 2.5 mile roadside 477 MCM spacer cable line from Bradford switching station along Route 103 into Warner.

A20W37 RIVER ROAD SS UPGRADES – Completed

In 2004, Eversource NH purchased the assets and customers from the Connecticut Valley Electric Company (CVEC) including the Sugar River SS in Claremont, NH. The substation has equipment that has been defined as obsolete and replacement parts are no longer available according to the manufacturer. This substation was targeted for upgrades by installing new equipment to improve reliability and to allow the installation of Distribution Automation equipment.

A20X26 Spare 345-34.5 kV Transformer – Under Construction

This is a full funding request to procure a spare 140 MVA 345-34.5 kV transformer, to be designed and installed at Timber Swamp Substation in Hampton, NH. The design and installation will include a new foundation, oil containment, AC power, and alarm inputs to the transformer. In order to provide reliable and timely support to the 34.5kV distribution system transformers at Amherst, Lawrence Road, and Timber substations, an installed spare transformer is necessary.

A21C07 MALVERN VALLEY HANOVER CIRCUIT TIE – Completed

Loss of the Malvern Substation transformer would result in isolation of load because of the Valley 22W1 circuit capacity. Extend the circuit tie between Hanover 16W1 and Malvern 23W2 to increase the backup capability through the 12 kV system for Valley, Malvern, and Hanover substations and reduce the exposure to isolation of load.

A21C91 393 LINE ROW SECTION REBUILD – Completed

Twenty-One (21) aged wooden poles and associated hardware will be replaced with new steel structures along the 393 line in the right of way between Huse Road Substation and Mammoth Road in Manchester, NH. The poles have been identified for replacement due to condition and age. There is no opportunity to relocate this line to a roadway or to rebuild in another location to avoid the wetland area.

A21DA DISTRIBUTION AUTOMATION POLE TOP – Under Construction

This will fund the installation of approximately 75 pole top SCADA controlled devices. These devices provide indication of circuit conditions and allow for remote operation to sectionalize the system and

restore power remotely. Installation of these devices over the last four years have resulted in significant savings in the impact and duration of outages on the distribution system.

A21E08 Circuit Tie 3191X1B to 377X2 – Completed

This project created a new circuit tie between the 3191X1B and 377X2 circuits. The 3191X1B is a radial circuit feeding 1,178 customers and experiences, on average, one fault on the backbone each year impacting the whole circuit. This project reconducted and converted 2,300 feet of #4 bare Cu conductor with 477 spacer cable on the 377X2 on Exeter Road to create a new 34.5 kV circuit tie between the 3191X1B and the 377X2 on Bennett Way in Newmarket, providing a back feed to the 3191X1B from the 377 line.

A21E16 REPLACE ROCHESTER SS BUS TIE AUTOCLOSE – Completed

This project replaced the inoperable GE FANUC 9030 programmable logic controller (PLC) - based auto close scheme at the Rochester substation 34.5kV bus tie breaker BT32 with an updated scheme using a SEL-2411 programmable automatic controller.

A21E94 TIDEWATER FARM URD LOOP – Completed

The underground development off Tidewater Rd in Greenland has a history of outages due to failed direct buried cable. The direct buried cable runs through the woods. And the pad mount transformer 17/23S2T1 is in an inaccessible vegetated area. This project installs a new pad mounted transformer and relocates the inaccessible pad to an accessible location by the roadside. The project replaces direct buried cable with new cable in conduit.

A21N45 Ashland SS – PLC Replacement & P&C Upgrade – Under Construction

This project replaces the Programmable Logic Controller (PLC) based automation scheme at Ashland Substation in Ashland, NH. The PLC based automation scheme is obsolete (approximately 16 years old) and has been difficult to update and maintain.

A21S17 34.5 kV Capacitor Bank Switch Replacement Broad Street – Under Construction

21 vacuum switches were identified as needing replacement in 2008. These switches were prioritized based on age, condition, operating problems, and uniqueness. Seven (7) of these capacitor switches are to be replaced with a vacuum circuit breaker as part of this program.

A21X93 2021 Circuit Patrol Repairs Phase 2 – Completed

This project repaired or replaced distribution plant discovered to be deficient as a result of the circuit patrols on poor performing circuits completed in the Fall, 2021. Repairs and replacements include broken, leaning, or damaged poles, broken or decayed crossarms and braces, damaged primary conductors, broken or loose guy wires and anchors, damaged insulators, bent pins, and broken insulator ties.

Section 4

Worst Performing Circuit Lists

| 2022 Circuit Hit List - Ranked By COSAIDI - IEEE Criteria - Allocated data | | | | | | | | | | | | | | | | | | | |
|--|-----------|---------|-------|-------------|-------|-----------|----------------------------|------------------------|-----------------------------|---------------|---------------------|------------------|---------------|---------------|-------------------|-------------------|--------------------|-------------|---------------|
| Rank | Circuit | COSAIDI | CAIDI | Circuit MBI | CIL | # Outages | Customers Interrupted (CI) | Customer Minutes (CMI) | Customers Served By Circuit | Circuit Miles | Cust Inter Per Mile | Outages Per Mile | Circuit SAIDI | Circuit SAIFI | # Cust_3 Dr Mores | #Cust >4Hr Outage | Customer Weighting | Region | AWC |
| 1 | 316X1_32 | 4.30 | 224 | 4.0 | 107 | 57 | 10,408 | 2,334,639 | 3,475 | 158.8 | 66 | 0.6 | 671.77 | 2,9948 | - | 3,158 | 708.8 | NH WESTERN | NEWPORT AWC |
| 2 | 3133X_31 | 2.28 | 133 | 3.4 | 51 | 184 | 9,298 | 1,240,152 | 2,863 | 151.4 | 61 | 1.2 | 485.65 | 3,4912 | 776 | 732 | 428.0 | NH WESTERN | KEENE AWC |
| 3 | 31W1_64 | 1.73 | 162 | 3.3 | 75 | 69 | 5,173 | 939,980 | 1,428 | 73.8 | 70 | 0.9 | 658.13 | 3,6219 | 1,062 | 1,467 | 662.8 | NH NORTHERN | TILTON AWC |
| 4 | 316_32 | 1.57 | 196 | 9.0 | 34 | 129 | 4,361 | 854,126 | 3,279 | 172.4 | 25 | 0.7 | 260.50 | 1,3301 | 72 | 1,216 | 288.0 | NH WESTERN | NEWPORT AWC |
| 5 | 20W2_42 | 1.39 | 190 | 5.2 | 86 | 46 | 3,370 | 755,422 | 1,711 | 48.9 | 81 | 0.9 | 441.55 | 2,3205 | 456 | 1,707 | 501.8 | NH NORTHERN | TILTON AWC |
| 6 | 3410_32 | 1.28 | 117 | 7.9 | 55 | 108 | 5,324 | 696,039 | 3,879 | 183.8 | 32 | 0.6 | 179.45 | 1,5273 | 1,300 | 735 | 433.1 | NH WESTERN | NEWPORT AWC |
| 7 | 319X1_64 | 1.23 | 145 | 6.4 | 76 | 61 | 4,621 | 867,736 | 2,474 | 116.7 | 40 | 0.5 | 269.89 | 1,8678 | - | 1,102 | 253.8 | NH NORTHERN | TILTON AWC |
| 8 | 355X10_76 | 1.18 | 183 | 8.2 | 43 | 81 | 3,503 | 640,406 | 2,390 | 123.4 | 28 | 0.7 | 267.99 | 1,4884 | - | 302 | 139.1 | NH NORTHERN | LANCASTER AWC |
| 9 | 3217X_22 | 1.10 | 232 | 21.7 | 33 | 63 | 2,048 | 537,081 | 3,708 | 97.3 | 21 | 0.6 | 161.04 | 0,5524 | 534 | 652 | 261.0 | NH SOUTHERN | NASHUA AWC |
| 10 | 336X1_45 | 1.06 | 167 | 12 | 104 | 33 | 3,441 | 576,331 | 346 | 30.2 | 114 | 1.1 | 1,684.49 | 9,9379 | 1,871 | 361 | 1,010.9 | NH NORTHERN | CHOCORUA AWC |
| 11 | 60W1_32 | 1.03 | 248 | 7.3 | 40 | 57 | 2,264 | 580,767 | 1,379 | 33.8 | 67 | 1.7 | 406.62 | 1,6417 | 245 | 537 | 280.9 | NH WESTERN | NEWPORT AWC |
| 12 | 314X4_22 | 1.03 | 98 | 3.2 | 70 | 82 | 5,756 | 561,629 | 1,551 | 99.0 | 58 | 0.8 | 362.22 | 3,7110 | 2,439 | 67 | 636.6 | NH SOUTHERN | NASHUA AWC |
| 13 | 3116X1_45 | 0.98 | 169 | 5.0 | 37 | 85 | 3,162 | 533,971 | 1,307 | 86.8 | 36 | 1.0 | 408.52 | 2,4191 | 962 | 474 | 408.5 | NH NORTHERN | CHOCORUA AWC |
| 14 | 20W1_42 | 0.98 | 135 | 7.5 | 60 | 66 | 3,335 | 531,860 | 2,446 | 63.8 | 62 | 1.0 | 217.45 | 1,6088 | 240 | 937 | 264.7 | NH NORTHERN | TILTON AWC |
| 15 | 348X3_76 | 0.97 | 95 | 4.2 | 90 | 62 | 5,572 | 527,631 | 1,968 | 110.5 | 50 | 0.6 | 268.15 | 2,8318 | 24 | 78 | 110.4 | NH NORTHERN | LANCASTER AWC |
| 16 | 392X7_62 | 0.90 | 132 | 8.7 | 47 | 79 | 3,708 | 487,711 | 2,679 | 100.2 | 37 | 0.8 | 182.04 | 1,3841 | 164 | 534 | 176.6 | NHEASTERN | ROCHESTER AWC |
| 17 | 23W2_22 | 0.89 | 172 | 10.1 | 85 | 33 | 2,794 | 481,885 | 2,389 | 74.2 | 38 | 0.4 | 204.28 | 1,1845 | - | 114 | 240.1 | NH CENTRAL | BEDFORD AWC |
| 18 | 85W1_L12 | 0.86 | 110 | 4.2 | 87 | 49 | 4,267 | 467,331 | 1,476 | 70.5 | 61 | 0.7 | 316.53 | 2,8901 | - | 137 | 131.3 | NH CENTRAL | BEDFORD AWC |
| 19 | 63W1_85 | 0.81 | 126 | 6.9 | 65 | 41 | 3,462 | 436,698 | 2,017 | 77.0 | 45 | 0.5 | 217.55 | 1,7267 | 48 | 28 | 69.9 | NHEASTERN | EPING AWC |
| 20 | 58W2_61 | 0.74 | 57 | 2.2 | 1,010 | 7 | 7,069 | 400,305 | 1,306 | 7.9 | 832 | 0.9 | 306.91 | 5,4117 | - | - | 107.4 | NHEASTERN | ROCHESTER AWC |
| 21 | 24W1_36 | 0.74 | 132 | 8.1 | 33 | 91 | 3,024 | 400,452 | 2,052 | 128.9 | 23 | 0.7 | 135.15 | 1,4735 | 80 | 151 | 107.0 | NH WESTERN | KEENE AWC |
| 22 | 23W5_22 | 0.70 | 122 | 14.4 | 38 | 61 | 3,110 | 380,819 | 3,742 | 122.3 | 25 | 0.7 | 101.78 | 0,8312 | 123 | 131 | 79.9 | NH CENTRAL | BEDFORD AWC |
| 23 | 362X2_61 | 0.67 | 102 | 7.4 | 76 | 47 | 3,589 | 365,348 | 2,210 | 91.1 | 44 | 0.6 | 165.33 | 1,6242 | - | 10 | 53.4 | NHEASTERN | ROCHESTER AWC |
| 24 | 3155W4_36 | 0.67 | 109 | 7.8 | 88 | 38 | 3,333 | 364,798 | 2,171 | 91.3 | 37 | 0.4 | 168.05 | 1,5354 | - | 9 | 60.2 | NH WESTERN | KEENE AWC |
| 25 | 3106_12 | 0.65 | 103 | 6.4 | 80 | 43 | 3,420 | 351,035 | 1,617 | 62.1 | 85 | 0.7 | 193.25 | 1,8827 | - | 90 | 81.1 | NH CENTRAL | BEDFORD AWC |
| 26 | 37W1_12 | 0.62 | 116 | 6.0 | 57 | 51 | 2,914 | 337,346 | 1,463 | 61.6 | 47 | 0.8 | 230.59 | 1,3918 | 52 | 21 | 94.3 | NH CENTRAL | BEDFORD AWC |
| 27 | 2V2_41 | 0.60 | 70 | 5.4 | 113 | 41 | 4,849 | 328,192 | 2,094 | 51.1 | 91 | 0.8 | 156.51 | 2,2306 | - | 1 | 54.9 | NH NORTHERN | TILTON AWC |
| 28 | 399X18_61 | 0.59 | 53 | 1.6 | 608 | 10 | 6,077 | 319,519 | 808 | 15.2 | 399 | 0.7 | 395.57 | 7,5234 | - | 358 | 182.2 | NHEASTERN | ROCHESTER AWC |
| 29 | 347_45 | 0.59 | 97 | 12.2 | 49 | 88 | 3,306 | 321,847 | 3,354 | 100.0 | 33 | 0.7 | 95.95 | 0,9658 | - | 101 | 48.7 | NH NORTHERN | CHOCORUA AWC |
| 30 | 3615X2_11 | 0.58 | 179 | 9.9 | 89 | 20 | 1,770 | 317,368 | 1,453 | 42.9 | 41 | 0.5 | 218.37 | 1,2179 | - | 609 | 167.8 | NH CENTRAL | HOOKSETT AWC |
| 31 | 23W4_12 | 0.58 | 244 | 10 | 321 | 4 | 1,285 | 319,002 | 110 | 6.7 | 182 | 0.6 | 2,856.29 | 11,7262 | - | 878 | 1,131.4 | NH CENTRAL | BEDFORD AWC |
| 32 | 19W2_45 | 0.58 | 143 | 14.3 | 34 | 64 | 2,183 | 312,670 | 2,802 | 102.1 | 21 | 0.6 | 120.16 | 0,8389 | 180 | 503 | 153.5 | NH NORTHERN | CHOCORUA AWC |
| 33 | 42X3_32 | 0.57 | 133 | 11.0 | 44 | 54 | 2,349 | 311,916 | 2,146 | 77.1 | 30 | 0.7 | 145.36 | 1,0947 | 30 | 342 | 108.2 | NH WESTERN | NEWPORT AWC |
| 34 | 317X3_12 | 0.57 | 225 | 11.6 | 35 | 39 | 1,382 | 310,968 | 1,333 | 68.0 | 20 | 0.6 | 233.30 | 1,0368 | - | 714 | 188.8 | NH CENTRAL | BEDFORD AWC |
| 35 | 3133X_23 | 0.57 | 136 | 25.7 | 43 | 53 | 2,287 | 311,358 | 4,906 | 126.8 | 18 | 0.4 | 63.47 | 0,4862 | - | 466 | 92.1 | NH SOUTHERN | DEPPY AWC |
| 36 | W18_31 | 0.56 | 97 | 6.5 | 53 | 60 | 3,170 | 305,991 | 1,718 | 78.9 | 40 | 0.8 | 178.11 | 1,8452 | 623 | 225 | 220.7 | NH WESTERN | KEENE AWC |
| 37 | 75W2_32 | 0.53 | 155 | 11.6 | 44 | 42 | 1,844 | 286,507 | 1,782 | 53.2 | 35 | 0.8 | 160.82 | 1,0350 | 21 | 323 | 108.9 | NH WESTERN | NEWPORT AWC |
| 38 | 327W2_12 | 0.53 | 92 | 7.1 | 57 | 55 | 3,152 | 289,250 | 1,981 | 74.6 | 42 | 0.7 | 155.47 | 1,6942 | 1,082 | 20 | 273.8 | NH CENTRAL | BEDFORD AWC |
| 39 | 310X3_41 | 0.52 | 169 | 6.1 | 44 | 38 | 1,857 | 280,692 | 847 | 18.3 | 86 | 2.0 | 331.23 | 1,9554 | 182 | 496 | 226.7 | NH NORTHERN | TILTON AWC |
| 40 | 333X_45 | 0.50 | 120 | 6.7 | 59 | 38 | 2,247 | 269,935 | 1,247 | 44.1 | 51 | 0.9 | 216.54 | 1,8025 | 303 | 8 | 137.6 | NH NORTHERN | CHOCORUA AWC |
| 41 | 3140X2_36 | 0.50 | 32 | 6.9 | 49 | 59 | 2,912 | 269,236 | 1,666 | 95.8 | 30 | 0.6 | 161.63 | 1,7482 | 120 | 82 | 92.9 | NH WESTERN | KEENE AWC |
| 42 | 11W1_41 | 0.50 | 148 | 12.9 | 42 | 44 | 1,834 | 271,143 | 1,375 | 38.9 | 47 | 1.1 | 137.27 | 0,9285 | 548 | 211 | 183.3 | NH NORTHERN | TILTON AWC |
| 43 | 3173X1_12 | 0.48 | 93 | 6.6 | 68 | 41 | 2,795 | 260,329 | 1,547 | 72.4 | 39 | 0.6 | 168.33 | 1,8072 | 78 | 2 | 74.8 | NH CENTRAL | BEDFORD AWC |
| 44 | 348W2_82 | 0.48 | 122 | 16.8 | 68 | 36 | 2,145 | 261,035 | 2,971 | 171 | 125 | 2.1 | 87.87 | 0,7220 | - | 93 | 44.7 | NHEASTERN | ROCHESTER AWC |
| 45 | 314W1_23 | 0.48 | 75 | 16.5 | 52 | 67 | 3,480 | 261,132 | 4,771 | 113.4 | 31 | 0.6 | 54.74 | 0,7253 | - | 156 | 42.6 | NH SOUTHERN | DEPPY AWC |
| 46 | 313X1_36 | 0.48 | 124 | 13.9 | 33 | 64 | 2,099 | 260,864 | 2,440 | 113.3 | 19 | 0.6 | 106.32 | 0,8603 | - | 160 | 61.4 | NH WESTERN | KEENE AWC |
| 47 | 3010X_21 | 0.48 | 116 | 15.0 | 118 | 19 | 2,233 | 258,337 | 2,796 | 418 | 53 | 0.5 | 92.41 | 0,7988 | - | 98 | 47.0 | NH SOUTHERN | NASHUA AWC |
| 48 | 399X15_62 | 0.47 | 43 | 2.3 | 858 | 7 | 6,006 | 256,049 | 1,146 | 17.5 | 343 | 0.4 | 223.51 | 5,2427 | - | - | 78.2 | NHEASTERN | ROCHESTER AWC |
| 49 | 399X13_62 | 0.47 | 43 | 0.9 | 1,174 | 5 | 5,869 | 252,608 | 422 | 12.9 | 456 | 0.4 | 598.36 | 13,9021 | - | 1 | 203.6 | NHEASTERN | ROCHESTER AWC |
| 50 | 3120_31 | 0.47 | 110 | 7.8 | 78 | 30 | 2,337 | 257,706 | 1,514 | 67.7 | 35 | 0.4 | 170.19 | 1,5433 | - | 13 | 61.5 | NH WESTERN | KEENE AWC |

| 2022 Circuit Hit List - Ranked By Circuit SAIFI - IEEE Criteria | | | | | | | | | | | | | | | | | | | | | | |
|---|---------------|---------|-------|-----|-----------|-----|--------|-----------------------|---------------------|---------------------|----------------|-----------------------------------|-------------------|------------------|------------------|------------------|-------------------|--------------------|---------------|-----|--|--|
| Circuit SAIFI | CoSAIFI | Circuit | COSAI | CAI | Circuit M | CIR | # Out | Customers Affected | Customer Minutes | Customers Served | Total Miles | Customers Affected Per Mile | Outages Per Mi | Circuit SAIDI | Circuit SAIFI | # Cust Or Mon | #Cust_>4 HrOut | Customer Weight | Region | AWC | | |
| 1 | 62 339X87_61 | 0.41 | 40 | 0.0 | 5,623 | 1 | 5,623 | 224,320 | 1 | 0.2 | 31,618 | 5.6 | 224,320 | 5,623.00 | - | - | 78,722.0 | NHEASTERN | ROCHESTER AWC | | | |
| 2 | 370 317_64 | 0.02 | 20 | 0.1 | 418 | 1 | 418 | 8,360 | 2 | 24.9 | 17 | 0.0 | 4,180 | 209.00 | - | - | 1,463.0 | NH CENTRAL | BEDFORD AWC | | | |
| 3 | 66 339X10_62 | 0.41 | 40 | 0.1 | 5,623 | 1 | 5,623 | 224,320 | 58 | 0.8 | 7,087 | 1.3 | 3,878 | 96.95 | - | - | 1,357.3 | NHEASTERN | ROCHESTER AWC | | | |
| 4 | 59 339X4_61 | 0.42 | 40 | 0.2 | 1,878 | 3 | 5,635 | 226,316 | 87 | 0.6 | 9,085 | 4.8 | 2,601 | 64.77 | - | - | 910.5 | NHEASTERN | ROCHESTER AWC | | | |
| 5 | 63 339X42_61 | 0.41 | 40 | 0.2 | 5,623 | 1 | 5,623 | 224,320 | 91 | 1.1 | 5,208 | 0.9 | 2,472 | 61.79 | - | - | 865.1 | NHEASTERN | ROCHESTER AWC | | | |
| 6 | 562 18H3_21 | - | 6 | 0.3 | 107 | 2 | 213 | 1,318 | 5 | 0.2 | 1,046 | 9.8 | 264 | 42.60 | - | - | 92.3 | NH SOUTHERN | NASHUA AWC | | | |
| 7 | 64 339X2_61 | 0.41 | 40 | 0.3 | 5,623 | 1 | 5,623 | 224,320 | 138 | 1.3 | 4,238 | 0.8 | 1,630 | 40.75 | - | - | 570.5 | NHEASTERN | ROCHESTER AWC | | | |
| 8 | 65 339X14_62 | 0.41 | 40 | 0.3 | 5,623 | 1 | 5,623 | 224,320 | 158 | 1.9 | 2,910 | 0.5 | 1,424 | 35.59 | - | - | 498.2 | NHEASTERN | ROCHESTER AWC | | | |
| 9 | 426 3165_63 | 0.01 | 66 | 0.4 | 97 | 1 | 97 | 6,400 | 3 | 8.1 | 12 | 0.1 | 2,133 | 32.33 | - | 2 | 747.0 | NHEASTERN | PORTSMOUTH | | | |
| 10 | 56 58H1_61 | 0.42 | 40 | 0.4 | 2,816 | 2 | 5,631 | 226,360 | 198 | 3.4 | 1,651 | 0.6 | 1,145 | 28.48 | - | - | 400.6 | NHEASTERN | ROCHESTER AWC | | | |
| 11 | 60 339X12_62 | 0.42 | 40 | 0.5 | 1,879 | 3 | 5,636 | 226,010 | 226 | 2.6 | 2,128 | 1.1 | 1,000 | 24.94 | - | - | 350.0 | NHEASTERN | ROCHESTER AWC | | | |
| 12 | 183 3164X7_12 | 0.11 | 187 | 0.5 | 314 | 1 | 314 | 58,718 | 13 | 0.1 | 4,683 | 14.9 | 4,517 | 24.15 | - | - | 1,580.9 | NH CENTRAL | BEDFORD AWC | | | |
| 13 | 57 54H2_61 | 0.42 | 40 | 0.5 | 813 | 7 | 5,693 | 229,653 | 247 | 8.1 | 699 | 0.9 | 928 | 23.01 | - | - | 324.9 | NHEASTERN | ROCHESTER AWC | | | |
| 14 | 61 399_62 | 0.42 | 40 | 0.6 | 1,882 | 3 | 5,645 | 227,534 | 269 | 11.5 | 491 | 0.3 | 847 | 21.01 | - | 5 | 297.2 | NHEASTERN | ROCHESTER AWC | | | |
| 15 | 49 339X13_62 | 0.47 | 43 | 0.9 | 1,174 | 5 | 5,869 | 252,808 | 422 | 12.9 | 456 | 0.4 | 598 | 13.90 | - | 1 | 209.6 | NHEASTERN | ROCHESTER AWC | | | |
| 16 | 31 23X4_12 | 0.58 | 244 | 1.0 | 321 | 4 | 1,285 | 313,002 | 110 | 6.7 | 192 | 0.6 | 2,856 | 11.73 | - | 878 | 1,311.4 | NH CENTRAL | BEDFORD AWC | | | |
| 17 | 58 54H1_61 | 0.42 | 40 | 1.0 | 569 | 10 | 5,692 | 226,435 | 493 | 5.5 | 1,040 | 1.8 | 459 | 11.55 | - | - | 160.8 | NHEASTERN | ROCHESTER AWC | | | |
| 18 | 10 336X1_45 | 1.06 | 167 | 1.2 | 104 | 33 | 3,441 | 576,331 | 346 | 30.2 | 114 | 1.1 | 1,664 | 9.94 | 1,871 | 361 | 1,010.9 | NH NORTHERN | CHOCORUA AWC | | | |
| 19 | 418 322X15_12 | 0.01 | 11 | 1.4 | 529 | 1 | 529 | 5,819 | 61 | 0.0 | 18,872 | 35.7 | 95 | 8.67 | - | - | 33.4 | NH CENTRAL | BEDFORD AWC | | | |
| 20 | 28 339X18_61 | 0.59 | 53 | 1.6 | 608 | 10 | 6,077 | 319,519 | 808 | 15.2 | 399 | 0.7 | 396 | 7.52 | - | 358 | 192.2 | NHEASTERN | ROCHESTER AWC | | | |
| 21 | 20 58H2_61 | 0.74 | 57 | 2.2 | 1,010 | 7 | 7,069 | 400,905 | 1,306 | 7.9 | 892 | 0.9 | 307 | 5.41 | - | - | 107.4 | NHEASTERN | ROCHESTER AWC | | | |
| 22 | 48 339X15_62 | 0.47 | 43 | 2.3 | 858 | 7 | 6,006 | 256,049 | 1,146 | 17.5 | 343 | 0.4 | 224 | 5.24 | - | - | 78.2 | NHEASTERN | ROCHESTER AWC | | | |
| 23 | 170 79W4_12 | 0.13 | 88 | 3.0 | 68 | 12 | 810 | 70,949 | 202 | 12.4 | 65 | 1.0 | 351 | 4.01 | - | 117 | 140.4 | NH CENTRAL | BEDFORD AWC | | | |
| 24 | 12 314W4_22 | 1.03 | 98 | 3.2 | 70 | 82 | 5,756 | 561,829 | 1,551 | 99.0 | 58 | 0.8 | 362 | 3.71 | 2,499 | 67 | 636.6 | NH SOUTHERN | NASHUA AWC | | | |
| 25 | 3 31W1_64 | 1.73 | 182 | 3.3 | 75 | 69 | 5,173 | 939,980 | 1,428 | 73.8 | 70 | 0.9 | 658 | 3.62 | 1,062 | 1,467 | 662.8 | NH NORTHERN | TILTON AWC | | | |
| 26 | 2 313X3_31 | 2.28 | 133 | 3.4 | 51 | 184 | 9,298 | 1,240,152 | 2,663 | 151.4 | 61 | 1.2 | 466 | 3.49 | 776 | 732 | 428.0 | NH WESTERN | KEENE AWC | | | |
| 27 | 72 3115X11_65 | 0.38 | 152 | 3.5 | 124 | 11 | 1,359 | 206,509 | 393 | 6.3 | 215 | 1.7 | 526 | 3.46 | 1,187 | 397 | 481.1 | NHEASTERN | EPPLING AWC | | | |
| 28 | 419 322X14_12 | 0.01 | 11 | 3.6 | 523 | 1 | 523 | 5,819 | 157 | 1.4 | 374 | 0.7 | 37 | 3.37 | - | - | 13.0 | NH CENTRAL | BEDFORD AWC | | | |
| 29 | 375 310X6_41 | 0.02 | 215 | 3.8 | 47 | 1 | 47 | 10,105 | 15 | 0.6 | 77 | 1.6 | 674 | 3.13 | - | - | 235.8 | NH NORTHERN | TILTON AWC | | | |
| 30 | 142 355X1_76 | 0.17 | 145 | 3.9 | 36 | 18 | 649 | 93,779 | 210 | 13.0 | 50 | 1.4 | 446 | 3.08 | 226 | 55 | 209.4 | NH NORTHERN | LANCASTER AWC | | | |
| 31 | 139 360X7_12 | 0.18 | 60 | 4.0 | 83 | 20 | 1,661 | 100,273 | 551 | 26.1 | 64 | 0.8 | 182 | 3.01 | - | - | 63.6 | NH CENTRAL | BEDFORD AWC | | | |
| 32 | 1 316X1_32 | 4.30 | 224 | 4.0 | 107 | 97 | 10,408 | 2,334,639 | 3,475 | 158.8 | 66 | 0.6 | 672 | 2.99 | - | 3,158 | 708.8 | NH WESTERN | NEWPORT AWC | | | |
| 33 | 18 85W1_12 | 0.86 | 110 | 4.2 | 87 | 49 | 4,267 | 467,331 | 1,476 | 70.5 | 61 | 0.7 | 317 | 2.89 | - | 137 | 131.3 | NH CENTRAL | BEDFORD AWC | | | |
| 34 | 15 348X3_76 | 0.97 | 95 | 4.2 | 90 | 62 | 5,572 | 527,631 | 1,968 | 110.5 | 50 | 0.6 | 268 | 2.83 | 24 | 78 | 110.4 | NH NORTHERN | LANCASTER AWC | | | |
| 35 | 225 348X8_76 | 0.08 | 101 | 4.5 | 34 | 12 | 411 | 41,620 | 153 | 8.2 | 50 | 1.5 | 271 | 2.68 | - | 21 | 98.1 | NH NORTHERN | LANCASTER AWC | | | |
| 36 | 448 17H1_21 | 0.01 | 13 | 4.7 | 49 | 5 | 245 | 3,235 | 97 | 0.9 | 265 | 5.4 | 33 | 2.53 | - | - | 11.7 | NH SOUTHERN | NASHUA AWC | | | |
| 37 | 51 30W2_64 | 0.47 | 123 | 4.9 | 60 | 35 | 2,092 | 257,233 | 846 | 48.8 | 43 | 0.7 | 304 | 2.47 | 624 | 168 | 256.4 | NH NORTHERN | TILTON AWC | | | |
| 38 | 525 323X3_12 | - | 57 | 4.9 | 13 | 3 | 39 | 2,238 | 16 | 0.1 | 279 | 214 | 140 | 2.44 | - | - | 49.0 | NH CENTRAL | BEDFORD AWC | | | |
| 39 | 13 3116X1_45 | 0.98 | 169 | 5.0 | 37 | 85 | 3,162 | 533,971 | 1,307 | 88.8 | 36 | 1.0 | 409 | 2.42 | 962 | 474 | 408.5 | NH NORTHERN | CHOCORUA AWC | | | |
| 40 | 147 3137X5_65 | 0.17 | 84 | 5.0 | 84 | 13 | 1,091 | 91,312 | 458 | 15.8 | 69 | 0.8 | 199 | 2.38 | - | 15 | 72.0 | NHEASTERN | EPPLING AWC | | | |
| 41 | 157 3155X8_22 | 0.15 | 136 | 5.1 | 50 | 12 | 594 | 80,824 | 251 | 19.2 | 31 | 0.6 | 322 | 2.37 | - | 1 | 112.9 | NH SOUTHERN | NASHUA AWC | | | |
| 42 | 5 20W2_42 | 1.39 | 190 | 5.2 | 86 | 46 | 3,970 | 755,422 | 1,711 | 48.9 | 81 | 0.9 | 442 | 2.32 | 456 | 1,707 | 501.8 | NH NORTHERN | TILTON AWC | | | |
| 43 | 164 323X10_12 | 0.14 | 158 | 5.2 | 470 | 1 | 470 | 74,260 | 205 | 0.2 | 2,070 | 4.4 | 362 | 2.29 | - | - | 126.8 | NH CENTRAL | BEDFORD AWC | | | |
| 44 | 110 318X2_11 | 0.25 | 82 | 5.3 | 69 | 24 | 1,662 | 136,957 | 730 | 31.3 | 53 | 0.8 | 188 | 2.28 | - | - | 65.6 | NH CENTRAL | HOOKSETT AWC | | | |
| 45 | 104 377X3_65 | 0.27 | 138 | 5.4 | 90 | 12 | 1,081 | 148,938 | 483 | 19.4 | 56 | 0.6 | 308 | 2.24 | - | 279 | 149.8 | NHEASTERN | EPPLING AWC | | | |
| 46 | 27 2W2_41 | 0.60 | 70 | 5.4 | 113 | 41 | 4,649 | 326,192 | 2,084 | 51.1 | 91 | 0.8 | 157 | 2.23 | - | 1 | 54.9 | NH NORTHERN | TILTON AWC | | | |
| 47 | 103 3525X5_77 | 0.24 | 68 | 5.5 | 146 | 13 | 1,694 | 128,477 | 861 | 61.8 | 31 | 0.2 | 149 | 2.20 | - | - | 52.2 | NH NORTHERN | BERLIN AWC | | | |
| 48 | 166 314X14_22 | 0.14 | 171 | 5.5 | 76 | 6 | 456 | 77,990 | 207 | 8.2 | 56 | 0.7 | 376 | 2.20 | - | - | 131.6 | NH SOUTHERN | NASHUA AWC | | | |
| 49 | 230 3137X80_6 | 0.08 | 102 | 5.5 | 58 | 7 | 409 | 41,914 | 187 | 8.9 | 46 | 0.8 | 225 | 2.19 | - | 5 | 79.3 | NHEASTERN | EPPLING AWC | | | |
| 50 | 133 377X16_65 | 0.20 | 104 | 5.7 | 107 | 10 | 1,067 | 110,756 | 504 | 11.9 | 90 | 0.8 | 220 | 2.12 | - | 152 | 99.7 | NHEASTERN | EPPLING AWC | | | |